

A STUDY OF FLEXURAL STRENGTH OF PRISM  
USING OIL PALM SHELL (OPS) AS A PARTIAL  
REPLACEMENT OF COARSE AGGREGATE

MOHD ABDUL HADI BIN MOHD ZAID

B. ENG (HONS.) CIVIL ENGINEERING  
UNIVERSITI MALAYSIA PAHANG

A STUDY OF FLEXURAL STRENGTH OF PRISM USING OIL PALM SHELL (OPS)  
AS A PARTIAL REPLACEMENT OF COARSE AGGREGATE

MOHD ABDUL HADI BIN MOHD ZAID

Thesis submitted in fulfillment of the requirements for the award of the degree of  
B.Eng (Hons.) Civil Engineering

Faculty of Civil Engineering and Earth Resources  
UNIVERSITI MALAYSIA PAHANG

JANUARY 2017

## **SUPERVISOR'S DECLARATION**

I hereby declare that I have checked this thesis and in my opinion, this thesis is adequate in terms of scope and quality for the award of degree of Bachelor of Civil Engineering (Hons.).

Signature :

Name of Supervisor : SHARIZA BINTI MAT ARIS

Position :

Date :

## STUDENT'S DECLARATION

I hereby declare that the work in this thesis is my own except for quotations and summaries which have been duly acknowledged. The thesis has not been accepted for any degree and is not concurrently submitted for award of other degree.

Signature :

Name : MOHD ABDUL HADI BIN MOHD ZAID

Id Number : AA13031

Date :

## ACKNOWLEDGEMENTS

All the praises are for the Almighty, Allah S.W.T. who bestowed me with the ability and strength to complete this thesis. First of all, I would like to express my gratitude and appreciation to all those who gave me the possibility to complete this report. A special thanks to our final year project coordinator, Madam Shariza Binti Mat Aris, whose help, stimulating suggestions and encouragement, helped me to coordinate my project especially in writing this report and given his full effort in guiding the team in achieving the goal as well as his encouragement to maintain our progress in track

I would also like to acknowledge with much appreciation the crucial role of the staff of Concrete Structure Laboratory, who gave the permission to use all required machinery and the necessary material to complete my final year project.

Special thanks go to my team mate, Isma Farhan, Hafis Osman, Noor Hanisya, Aiman Hakimi, Asraf Kamaluddin, Nur Syahidah, Nur Syuhada, Iradatul Hanis and Hafizuddin, who help me to assemble the parts and gave suggestion about the final year project.

Last but not least, I would to appreciate the guidance given by other supervisor Mr. Arif and Dr. Sharifah as well as the panels especially in our project presentation that has improved our presentation skills by their comment and tips.

## TABLE OF CONTENT

	<b>Page</b>
<b>SUPERVISOR’S DECLARATION</b>	iv
<b>STUDENT’S DECLARATION</b>	iv
<b>ACKNOWLEDGEMENTS</b>	iv
<b>ABSTRACT</b>	v
<b>ABSTRAK</b>	vi
<b>TABLE OF CONTENT</b>	vii
<b>LIST OF TABLES</b>	x
<b>LIST OF FIGURES</b>	xii
<b>CHAPTER 1            INTRODUCTION</b>	<b>1</b>
1.1    Background of the Study	1
1.2    Problem Statement	2
1.3    Objective	3
1.4    Scope of Project	3
<b>CHAPTER 2            LITERATURE REVIEW</b>	<b>4</b>
2.1    Introduction	4
2.2    Concrete	5
2.1.1    Types of Concrete and Applications	6
2.2.2    Normal concrete	7
2.2.3    Light Weight Concrete	8
2.2.4    High Weight Concrete	10
2.3    Materials	11
2.3.1    Cement	11
2.3.1.1 Chemical Composition of Portland Cement	12
2.3.1.2 Types of Portland Cement	13

2.3.2	Aggregate	14
2.3.3	Water	17
2.3.3.1	Batch water	17
2.3.3.2	Water added by the truck operator	18
2.3.3.3	Recycled water	18
2.4	Concrete quality	18
2.4.1	Factors affecting the strength of the concrete	19
2.4.2	Water-Cement Ratio	19
2.4.3	Aggregate-Cement Ratio	19
2.4.4	Degree of Compaction	20
2.4.5	Grading	20
2.5	Oil palm shell	22
2.5.1	Properties of oil palm shell	23
2.6	Previous study	23
2.6.1	Testing	23
2.6.1.1	Compressive Strength	23
2.6.1.2	Flexural Strength	25
<b>CHAPTER 3</b>		<b>27</b>
<b>METHODOLOGY</b>		
3.1	Introduction	27
3.2	Methodology Flow Chart	28
3.3	Materials Used	30
3.3.1	Oil palm shell	30
3.3.2	Cement	30
3.3.3	Coarse Aggregate	31
3.3.4	Fine Aggregate	33
3.3.5	Water	34
3.3.5.1	Water Cement Materials Ratio (w/cm)	34
3.4	Concrete Mix Design	35
3.5	Preparation of Sample	36
3.5.1	Oil Palm Shell Concrete	36
3.6	Curing Concrete Sample	37
3.7	Test Conducted	38
3.7.1	Sieve Analysis	38
3.7.1.1	Apparatus	39
3.7.1.2	Procedure	40
3.7.2	Workability Test	40
3.7.2.1	Slump Test	41

3.7.2.2 Apparatus	42
3.7.2.3 Procedure	42
3.7.3 Compressive Test	43
3.7.3.1 Apparatus	44
3.7.3.2 Procedure	44
3.7.4 Test	45
3.7.4.1 Apparatus	46
3.7.4.2 Procedure	47
<b>CHAPTER 4 RESULTS AND DISCUSSION</b>	<b>48</b>
4.2 Slump Test	48
4.3 Compressive Strength Test	50
4.4 Flexural Test	58
<b>CHAPTER 5 CONCLUSIONS AND RECOMMENDATIONS</b>	<b>66</b>
5.1 Introduction	66
5.2 Conclusions	66
5.3 Recommendations for Future Study	67
<b>REFERENCES</b>	<b>69</b>
<b>APPENDIX A</b>	<b>71</b>
<b>APPENDIX B</b>	<b>72</b>
<b>APPENDIX C</b>	<b>73</b>
<b>APPENDIX D</b>	<b>74</b>
<b>APPENDIX E</b>	<b>75</b>
<b>APPENDIX F</b>	<b>76</b>
<b>APPENDIX G</b>	<b>77</b>
<b>APPENDIX H</b>	<b>78</b>
<b>APPENDIX I</b>	<b>79</b>



<b>APPENDIX J</b>	<b>80</b>
<b>APPENDIX K</b>	<b>82</b>
<b>APPENDIX L</b>	<b>83</b>
<b>APPENDIX M</b>	<b>84</b>

## LIST OF TABLES

<b>Table No.</b>	<b>Title</b>	<b>Page</b>
2.1	The main compounds of Portland cement	13
2.2	Types of Portland cement	14
2.3	Average compressive strength of Rock-bridge	16
2.4	Compressive Strength for 28 days	24
3.1	Concrete Mix Design	36
4.1	Slump Test	49
4.2	Maximum Load with days	50
4.3	Maximum Compressive Strength with days	51
4.4	Cube Test for 7 days Curing Period	53
4.5	Cube Test for 14 days Curing Period	55
4.6	Cube Test for 28 days Curing Period	56
4.7	Maximum Load of Flexural with days	58
4.8	Flexural Strength with days	59
4.9	Flexural Test for Control of Oil Palm Shell Concrete	60
4.10	Flexural Test for 5% of Oil Palm Shell Concrete	61
4.11	Flexural Test for 10% of Oil Palm Shell Concrete	62
4.12	Flexural Test for 15% of Oil Palm Shell Concrete	63

**LIST OF FIGURES**

<b>Figure No.</b>	<b>Title</b>	<b>Page</b>
2.1	Concrete Composition	7
2.2	Categories of Aggregate Grading	21
2.3	Relationship between Compressive and Flexural Strength	26
3.1	Methodology Flow Chart	28
3.2	Study Work Plan	29
3.3	Oil Palm Shell	30
3.4	Type of Cement Used	31
3.5	Coarse Aggregate	33
3.6	Fine Aggregate	34
3.7	Water	35
3.8	Oil Palm Shell Concrete	37
3.9	Type of Curing	38
3.10	Types of slump	41
3.11	Compression Machine	44
3.12	Example of flexural strength 4-point	45
3.13	Example of flexural strength test	46
4.1	Slump Height for OPS Concrete	50
4.2	Maximum Load of the Cubes	51
4.3	Compressive Strength of the Cubes	52
4.4	Cube Test for 7 days curing period	54
4.5	Cube Test for 14 days curing period	55

4.6	Cube Test for 28 days curing period	57
4.7	Maximum Load of the Prisms	58
4.8	Flexural Strength of the Prisms	59
4.9	Flexural Test for Control of Oil Palm Shell Concrete	61
4.10	Flexural Test for 5% of Oil Palm Shell Concrete	62
4.11	Flexural Test for 10% of Oil Palm Shell Concrete	63
4.12	Flexural Test for 15% of Oil Palm Shell Concrete	64