ASSESSMENT OF CONSTRUCTION PLANNING OF NEW PROJECT: MEDAN IKAN BAKAR CASE STUDY

SITI FARAHANUM BINTI AB RAHIM

B. ENG(HONS.) CIVIL ENGINEERING
UNIVERSITI MALAYSIA PAHANG

UNIVERSITI MALAYSIA PAHANG

| DECLARATION OF THESIS AND COPYRIGHT | | | | |
|---|---------------------------------|---|--|--|
| Author's Full Name | : SITI FARAHANUM BINTI AB RAHIM | | | |
| Date of Birth | : 10 th O | CTOBER 1995 | | |
| Title | : ASSE | SSMENT OF CONSTRUCTION PLANNING | | |
| | OF NI | EW PROJECT: MEDAN IKAN BAKAR | | |
| | CASE | ESTUDY | | |
| Academic Session | : 2017/2 | 2018 | | |
| I declare that this thesis | e ie classi | fied as: | | |
| | | | | |
| ☐ CONFIDENTIA | AL | (Contains confidential information under the Official Secret Act 1997)* | | |
| □ RESTRICTED | | (Contains restricted information as specified by the | | |
| ☑ OPEN ACCESS | | organization where research was done)* I agree that my thesis to be published as online open access (Full Text) | | |
| I acknowledge that Universiti Malaysia Pahang reserves the following rights: | | | | |
| The Thesis is the Property of Universiti Malaysia Pahang The Library of Universiti Malaysia Pahang has the right to make copies of the thesis for the purpose of research only. The Library has the right to make copies of the thesis for academic exchange. | | | | |
| Certified by: | - | • | | |
| | | | | |
| (Student's Signa | ıture) | (Supervisor's Signature) | | |
| <u>951010-11-56</u> | | DR. MOHAMAD IDRIS BIN ALI | | |
| New IC/Passport N Date: 6 th JUNE 20 | | Name of Supervisor Date: 6 th JUNE 2018 | | |

NOTE: * If the thesis is CONFIDENTIAL or RESTRICTED, please attach a thesis declaration letter.



SUPERVISOR'S DECLARATION

I hereby declare that I have checked this thesis and in my opinion, this thesis is adequate in terms of scope and quality for the award of the Bachelor Degree of Civil Engineering

(Supervisor's Signature)

Full Name : DR. MOHAMAD IDRIS BIN ALI

Position : SUPERVISOR & DEAN FACULTY OF CIVIL ENGINEERING

AND EARTH RESOURCES

Date : 6th June 2018



STUDENT'S DECLARATION

I hereby declare that the work in this thesis is based on my original work except for quotations and citations which have been duly acknowledged. I also declare that it has not been previously or concurrently submitted for any other degree at Universiti Malaysia Pahang or any other institutions.

(Student's Signature)

Full Name : SITI FARAHANUM BINTI AB RAHIM

ID Number : AA14128

Date : 6th June 2018

ASSESSMENT OF CONSTRUCTION PLANNING OF NEW PROJECT: MEDAN IKAN BAKAR CASE STUDY

SITI FARAHANUM BINTI AB RAHIM

Thesis submitted in fulfillment of the requirements

for the award of the

Bachelor Degree in Civil Engineering

Faculty of Civil Engineering and Earth Resources
UNIVERSITI MALAYSIA PAHANG

JUNE 2018

ACKNOWLEDGEMENTS

Alhamdulillah, because of His willingness, I had finished my degree's project research that had been required by Universiti Malaysia Pahang (UMP).

A big thank you to Dr. Mohamad Idris bin Ali, because of you I had finished my research sufficiently. Thanks to all advises, knowledge, information that been shared within my research period. I also thanks to your helping hands and willingness to spend your times to ensure my research will be as required by UMP.

I also appreciate, the supports that been given by my mother, Mdm. Kamariah binti Ibrahim and also my father, Mr. Ab Rahim bin Abu Bakar. Without their dynamic support I cannot finished this research. I also thanks to my siblings and my fellow family mates.

Last but not lease, to my course lecturers and my fellow friends and mates that always gave me positive input and information in preparing my research report. Thank you so much, your good deeds are too much to be paid by me, only He can ever repay all of you and your good prayer for me.

ABSTRAK

Projek pembinaan dianggap berjaya apabila dapat diselesai pada masa yang dijadualkan, mengikut kos yang dianggarkan, dan menepati spesifikasi kualiti yang ditetapkan. Semasa pelaksanaan projek, kelewatan dalam menyiapkan projek adalah merupakan satu kegagalan yang biasanya berlaku dalam industri pembinaan, yang menyebabkan pelanjutan masa di mana projek itu tidak dapat diselesaikan mengikut perancangan. Objektif utama kajian ini adalah memberi tumpuan kepada penilaian perancangan pembinaan projek baru Medan Ikan Bakar. Pelan perancangan sedia ada projek Medan Ikan Bakar telah dianalisis dan didapati bahawa terdapat kelewatan berlaku semasa pelaksanaan projek. Hal yang demikian, pelan perancangan semula bagi projek Medan Ikan Bakar telah dilaksanakan dengan mempertimbangkan bilangan hari hujan dan juga cuti umum. Oleh itu, bilangan hari bekerja yang optimum dapat diperolehi dan projek juga dapat diselesaikan mengikut perancangan supaya pengguna tidak akan menghadapi kerugian dari segi penggunaan atas kelewatan penyiapan projek tersebut yang tidak mengikut tempoh masa yang telah ditetapkan. Selepas memperoleh hari kerja yang optimum dalam perancangan pembinaan, beberapa cadangan dapat diwujudkan untuk pembangunan strategi dengan tujuan untuk memperbaiki amalan perancangan pembinaan dan boleh menjadi garis panduan untuk kajian masa hadapan dalam merancang projek pembinaan.

ABSTRACT

A construction project is commonly acknowledged as successful when it is completed on time, within budget, in accordance with specifications and to stakeholder satisfaction. During the project execution, delay in the project is one of the failures that usually occurred in the construction industry, which leads to extension of time where the project cannot be completed according to the plan. The objective of this study was focused on assessment of construction planning of new project Medan Ikan Bakar. The existing plan of the Medan Ikan Bakar project is analysed and it has been identified that the delay was occurred during the project execution. Due to the extension of time that occurred in the project, the reschedule plan of the Medan Ikan Bakar project is carried out by considering the number of rainy days and the public holidays. Hence, the optimum working days is obtained and the project could be completed according to the plan so that the users may not face the lost in the term of the operation of the building where the completed project is beyond the expected date. After acquiring the optimum working days in construction planning, several suggestions could be created for the development of strategies with the purpose in improving construction planning practices and can be as a guideline for future study in planning the construction project.

TABLE OF CONTENT

DECLARATION

| TITI | Æ | PA | GE |
|------|---|----|----|

| ACF | KNOWLEDGEMENTS | ii |
|------|---------------------------------|------|
| ABS | STRAK | iii |
| ABS | STRACT | iv |
| TAE | BLE OF CONTENT | v |
| LIST | T OF TABLES | viii |
| LIST | T OF FIGURES | ix |
| LIST | T OF ABBREVIATIONS | X |
| CHA | APTER 1 INTRODUCTION | 1 |
| 1.1 | Introduction | 1 |
| 1.2 | Problem Statement | 6 |
| 1.3 | Aim and Objectives | 7 |
| 1.4 | Scope of Study | 7 |
| 1.5 | Important of Study | 7 |
| 1.6 | Thesis Structure | 8 |
| CHA | APTER 2 LITERATURE REVIEW | 9 |
| 2.1 | Introduction | 9 |
| 2.2 | Project Life Cycle | 10 |
| | 2.2.1 Pre-project phase | 13 |
| | 2.2.2 Planning and design phase | 14 |

| | 2.2.3 | Contractor selection phase | 15 |
|-----|--------|--|----|
| | 2.2.4 | Project mobilization phase | 15 |
| | 2.2.5 | Project operation phase | 16 |
| | 2.2.6 | Project close-out and termination phase | 17 |
| | 2.2.7 | Risk in the PLC | 17 |
| 2.3 | Risk I | Management Process for Construction Projects | 19 |
| | 2.3.1 | Definition of Risk Management Objective | 20 |
| | 2.3.2 | Risk Identification | 21 |
| | 2.3.3 | Qualitative Risk Analysis | 24 |
| | 2.3.4 | Quantitative Risk Analysis | 27 |
| | 2.3.5 | Risk Response and Monitoring | 29 |
| 2.4 | Risk l | Factors in Construction Project | 31 |
| ~ | | | |
| СНА | PTER 3 | 3 METHODOLOGY | 33 |
| 3.1 | Introd | luction | 33 |
| 3.2 | Data (| Collecting | 35 |
| | 3.2.1 | Primary Data Collection | 35 |
| | 3.2.2 | Secondary Data Collection | 35 |
| | 3.2.3 | Tertiary Data Collection | 36 |
| 3.3 | Pre-pr | rocessing | 37 |
| 3.4 | Data l | Processing/Analysis | 37 |
| 3.5 | Resul | t | 37 |
| СПУ | DTED / | A DECLI TO AND DISCUSSION | 20 |
| СПА | TIEK 4 | 4 RESULTS AND DISCUSSION | 39 |
| 4.1 | Introd | luction | 39 |
| 4.2 | Factor | rs Affecting Duration Estimation Process | 40 |

| | | B MICROSOFT PROJECT FOR RESCHEDULE PLAN OF AN BAKAR PROJECT | 74 |
|------|---------|--|----|
| | | A MICROSOFT PROJECT FOR EXISTING PLAN OF MEDAN R PROJECT | 73 |
| REFE | RENC | ES | 70 |
| 5.3 | Recom | nmendation | 67 |
| 5.2 | Conclu | asion | 65 |
| 5.1 | Introdu | action | 65 |
| СНАН | PTER 5 | CONCLUSION AND RECOMMENDATION | 65 |
| 4.5 | Summ | ary of the chapter | 64 |
| | 4.4.3 | Tasks of Surau | 62 |
| | 4.4.2 | Tasks of Public Toilet | 60 |
| | 4.4.1 | Tasks of Gerai Hasil Laut | 59 |
| 4.4 | Durati | on Estimation Process | 58 |
| 4.3 | Planni | ng and Scheduling | 46 |
| | 4.2.2 | Number of public holidays | 42 |
| | 4.2.1 | Number of rainy days | 41 |

LIST OF TABLES

| Table 1.1 | Factors of delay in project | 3 |
|-----------|--|----|
| Table 2.1 | Phases, stages and steps in PLC | 11 |
| Table 4.1 | Average number of rainy days in Kuantan | 41 |
| Table 4.2 | Percentage of work progress of planned and actual of Medan Ikan Bakar project | 47 |
| Table 4.3 | Medan Ikan Bakar project | 49 |
| Table 4.4 | Kompleks Hasil Laut | 50 |
| Table 4.5 | Restoran Ikan Bakar | 51 |
| Table 4.6 | Gerai Hasil Laut | 53 |
| Table 4.7 | Public Toilet | 54 |
| Table 4.8 | Surau (Musholla) | 56 |
| Table 4.9 | External Works | 57 |
| Table 5.1 | The duration of existing plan reschedule plan of Medan Ikan Bakar project | 67 |
| Table 5.2 | Factors of delay in project | 68 |

LIST OF FIGURES

| Figure 1.1 | Malaysia GDP from construction | 1 |
|-------------|--|----|
| Figure 1.2 | Average price of construction material | 3 |
| Figure 1.3 | Number of rainy days | 5 |
| Figure 1.4 | Workers wage rates | 6 |
| Figure 2.1 | PLC for a construction project | 13 |
| Figure 2.2 | Risk management process for construction projects | 20 |
| Figure 2.3 | Example of a P-I table | 25 |
| Figure 2.4 | Probability-Impact Matrix for opportunities and threats | 26 |
| Figure 2.5 | Mapping risk mitigation strategies with levels of probability and consequences | 29 |
| Figure 3.1 | Research Methodology Flowchart | 34 |
| Figure 4.1 | Public National Holidays and State Holidays in 2015 | 43 |
| Figure 4.2 | Public National Holidays and State Holidays in 2016 | 45 |
| Figure 4.3 | Percentage of work progress of planned and actual of Medan Ikan Bakar project | 48 |
| Figure 4.4 | Existing plan of Gerai Hasil Laut | 59 |
| Figure 4.5 | Reschedule plan of Gerai Hasil Laut | 59 |
| Figure 4.6 | Existing plan of Public Toilet | 60 |
| Figure 4.7 | Reschedule plan of Public Toilet | 61 |
| Figure 4.8 | Existing plan of Surau | 62 |
| Figure 4.9 | Reschedule plan of Surau | 62 |
| Figure 4.10 | Existing plan of Surau | 63 |
| Figure 4.11 | Reschedule plan of Surau | 63 |

LIST OF ABBREVIATIONS

GDP Gross Domestic Product

MYR Malaysia Ringgit MP Malaysia Plan

JKR Jabatan Kerja Raya
PLC Project Life Cycle

RMP Risk Management Plan

RM Risk Management
P-I Probability-Impact

CHAPTER 1

INTRODUCTION

1.1 Introduction

Construction industry plays very important role and known as highly dynamic sector in the development of country in Malaysia. The industry is a distinct sector of the economy which makes its direct contribution to economic growth like all the other sectors such as agriculture, manufacturing and services. It is a vital contributor to the gross domestic product (GDP) growth and produces the built environment that supports other sectors of the economy in most part of the world (Oladapo, 2015; NELF, 2013). According to the Department of Statistics, Malaysia (2017), GDP From Construction in Malaysia increased to 13838 MYR Million in the third quarter of 2017 from 12892 MYR Million in the second quarter of 2017. GDP from Construction in Malaysia averaged 10038.16 MYR Million from 2010 until 2017, reaching an all-time high of 13838 MYR Million in the third quarter of 2017 and a record low of 6464 MYR Million in the first quarter of 2010.



Figure 1.1 Malaysia GDP from Construction

In GDP of construction in Malaysia, Malaysia Plan are one of the biggest contribution towards the economic growth for the construction sector. Based on the Malaysia Plan report, the construction sector is growing rapidly from year to year with the increasing number of projects awarded in Malaysian Plan. In 9th Malaysia Plan (9MP), Kementerian Kerja Raya constructing 542 projects for road and buildings and its rose to 5095 projects in 10th Malaysia Plan (10MP) with the increasing amount allocated for all the projects from 21.47 MYR Billion to 470 MYR Billion.

Based on 9MP and 10MP, not all of the projects are completed according to the Malaysia Plan. In 9MP, there are consists of 221 numbers of projects that are facing delay issue which cannot be completed due to several factors while in 10MP, the same issue happened where 770 projects by JKR are delayed. For instance in 2006 under 9MP, Putrajaya was forced to spend an extra RM800 million to build the East Coast Highway largely due to delays by the Public Works' Department (JKR)'s contractors.

According to the audit, JKR had performed poorly in its task to build roads measuring 139.4km in total for the highway's second phase, with the government department missing both its March 2009 deadline and RM2.09 billion budget. Other factors that contributed to the higher cost included the hike in building materials' prices and additional facilities. The cost was mainly due to the increase of construction materials that caused the tender prices for the re-tendering of a few packages to rise drastically. Other factors that contributed to the cost increase is the additional payment for land acquisition, increase of design costs and security, the construction of toll plazas and additional components (Malay Mail Online, 2013).




Figure 1.2 Average price of construction material

Based on the Figure 1.2 provided above, it is proven that building material's prices is one of the factor contribution towards the delay occurred in East Coast Highway project. This can be seen from the graph where the price for concrete rose by years from 145 MYR in 2006 of 9MP to 210 MYR in 2017 of 11MP. Besides that, there are also another factors that may leads to delay in construction project.

Table 1.1 Factors of delay in project

| No | Factors of delay in project | Critical | Not |
|----|--|-----------|-----------|
| | | | critical |
| 1 | General | | |
| | 1.1 Weather | $\sqrt{}$ | - |
| | 1.2 Poor planning of work execution | $\sqrt{}$ | - |
| | 1.3 Poor facilities at construction site | - | $\sqrt{}$ |
| | 1.4 Natural disaster | - | $\sqrt{}$ |
| 2 | Lack of Labours | | |
| | 2.1 Professional management | $\sqrt{}$ | - |
| | 2.2 Skilled workers | $\sqrt{}$ | - |

| | 2.3 General workers | \checkmark | $\sqrt{}$ |
|---|--|--------------|-----------|
| 3 | Material Sources | | |
| | 3.1 Lack of construction building materials | $\sqrt{}$ | - |
| | 3.2 Increase in material price | $\sqrt{}$ | - |
| 4 | Source of Income | | |
| | 4.1 Lack of budget | $\sqrt{}$ | - |
| | 4.2 Delay of payment from contractor to sub- | $\sqrt{}$ | - |
| | contractor | | |
| | 4.3 Problem with bank loan | - | - |
| 5 | Client Needs | | |
| | 5.1 Changing scope of design | $\sqrt{}$ | - |
| | 5.2 Changing design and structure that been | $\sqrt{}$ | - |
| | constructed | | |
| | 5.3 Delay in approving the changes in works | _ | $\sqrt{}$ |
| 6 | Machinery Sources | | |
| | 6.1 Shortage of machineries | - | $\sqrt{}$ |
| | 6.2 Defective machineries | | $\sqrt{}$ |

Source: Idris (2006).

From the factors listed in Table 1.1, it can be seen that weather and lack of labours are classified as critically contribution towards the delay occurred in construction industry. Hence, it is very important to have the good planning where it is strictly necessary in construction planning to avoid uncertainty from occur especially delays in project.




Figure 1.3 Number of rainy days

Number of rainy days must be considered during the planning phase of construction work execution so that the project could be completed within the optimum time according to the plan. This is because the number of rainy days are fluctuated through the months where it can't be predicted and categorised as uncertainty that may leads to extension of time in construction process.

Moreover, increase in local worker wages rate also contribute to the shortage of labour. This is proven based on the Figure 1.4 where the wages rate of concreter, brick layer, plasterer and etc. are increasing from years in 9MP, 10MP and 11MP. Shortage of labour happened because most of the contractor are preferred to choose moderate wages rate of construction worker to avoid exceeding of budget for the construction project. Figure 1.4 showed the workers wage rates with selected occupations for local and foreign workers in 9MP, 10MP and 11MP.




Figure 1.4 Workers wage rates

In construction industry, construction time, cost and quality of the project are major considerations in project management and also known as most important parameters for measuring the successful of the project. The need to monitor and control these three variables evolved is so that there is no compromise on either of them. Good project management is to ensure that all the three variables meet the standards defined in the original commitment (Vector Consulting Group, 2015).

1.2 Problem Statement

During the project execution, delay in the project is one of the failure that usually occurred in construction industry which leads to extension of time where the project cannot be completed according to the plan. Delays and disruptions are commonly known as the challenges that must be faced by people and organization who are involving in construction industry. It may give an effects towards the cost of the budget, time to complete the project and quality of the work production.

Therefore, the extension of time in construction project could be avoided by considering the risks that may occurred in construction phase. As a consultant, it is crucial to have the good planning of duration estimation for construction work to be executed before open tendering process. The good planning must be established before carrying

out the construction work by considering the main important criteria for example by considering the number of rainy days and public holidays in construction. This initiative must be done in order to produce the good performance in the mean of time, quality and cost of the project.

1.3 Aim and Objectives

The study is focused on assessment of construction planning of new project. In order to ensure the objective is achieved, the specific objectives are created as a guideline to complete the studies. The specific objectives of the studies were:

- a) To determine the typical number of rainy days and the public holidays.
- b) To identify the effective number of days in construction planning.

1.4 Scope of Study

In order to achieve the objectives for this study, the scope of the study will be focusing on:

- a) The study is focused on the Medan Ikan Bakar project.
- b) The study is focused on establishing the good planning in construction considering the important factors which are the rainy days and public holidays.
- c) The study will carried out by comparing the existing planning of Medan Ikan Bakar project with the new planning and obtaining the more optimum working days.

1.5 Importance of Study

Based on the other research and the related issues, the major aim of this research is to establish a system which will help to enhance the performance of building construction projects in developing countries, without cost and time exceeding the initial plan while achieving optimal quality. The good performance of construction project could be establish by considering the risk factors that may occurred so that the building operation could be used in time without late of completion. The users also may gain the benefits or profits potentially through the use of the completed project and in the same time produce work that meets the client's expectation and satisfaction.

1.6 Thesis Structure

This chapter comprises of five chapters. The first chapter consists of introduction section. It states the background, problem statement, aim and objectives, scope of study and lastly importance of study. For chapter two, the key terms in-purpose for this research are described and also the literature review that related and suitable for this research. Chapter three explains the research methodology for research data collected and the method of data analysis to be employed. For chapter four, the results obtained from study area and year of study were presented and the analysis from the results obtained from study area and year of study were presented and the analysis from the result was discussed. Finally, chapter five comprises the conclusion from the overall chapter and relates some recommendations for future work on research field.

CHAPTER 2

LITERATURE REVIEW

2.1 Introduction

Construction planning is known as a fundamental and challenging activity in the management and execution of construction projects. The definition of work task, the choice of technology, the duration for individual tasks and the estimation of the required resources, and the identification of any interactions among the different work task are involving in the construction planning. A good construction plan is important for the budget estimation and for the scheduling of work. Conducting a construction plan is a critical task in construction management, neither the plan is formally recorded nor not written.

In recent times, construction works are still faced with problems of working capital, poor management and lack of good organization (Oladapo, 2015). These inefficiencies often causes to disruption of work and productivity loss, and extension of time for completing the building projects. The construction industry is not shaped to respond quickly to the needs of the clients which in most cases take far longer than expected and frequently fail to meet the target technical performance (Choughry and Iqbal, 2013). At the same time, distortions in prices and the shortage of materials and other inputs tend to cause all locative inefficiencies which make the works in hand economically more costly than they should be (The World Bank, 1984). In general, it can be said that risk management in developing countries is inadequate, lacks a systematic and formal approach, and its performance is not measured (Serpell et al, 2015).

In order to reduce many problems related to duration in construction project, a research should be carry out to make a better understanding on how the construction project planning is important to produce the good performance of work execution while

conducting the project, in the same time meets the client needs by the mean of time, cost and quality of the project. We need to make a good start by effectively and efficiently planning and scheduling in order to achieve our ultimate goal in the project life cycle.

2.2 Project Life Cycle

In business domain regardless of the area, each activity or process has a beginning and an end. In the engineering world, it's the similar concepts used to systemize projects over time. To improve a project's performance, the term of project life cycle is used as a management tool. The scope of life cycles differs among industries and diverse terminology with a various number of phases is used depending on the sectors. However, several terms are often used within one particular sector even though a number of phases can vary (Smith et al., 2006). Therefore, it is hard to systemize and serve one common scope and definition of a project life cycle.

For construction projects, for instance, the PLC model can consist of eight succeeding phases including pre-feasibility, feasibility, design, contract/procurement, implementation, commissioning, handover and operation (Smith et al., 2006). The most widely used framework which Pinto and Prescott (1988) present a four stage PLC developed by Adams and Brandt, and King and Cleland where conceptualization, planning, execution and termination are the main phase. The principal project steps which also known as a similar model is used by Westland (2006) who identifies initiation, planning, execution and closure.

Moreover, Ward and Chapman (1995) develop another model which sets up concept, planning, execution and termination to constitute PLC. The same authors in another publication make a further division of each of the four phases into another number of stages and steps. Such fragmentation of the activities provides easier and more accurate potential risk identification and makes risk management processes more effective (Chapman and Ward, 2003). PLC requires adjustments and an individual approach due to the variety of project types. Depending on its scope and structure, the number of further stages within each phase should be adjusted to a particular project. A framework used in one project can turn out to be completely inapplicable in another since each project is unique. As the one proposed by Chapman and Ward (2003) that is shown in Table 2.1, the model should be used as an example and not as ready-made template.

Table 2.1 Phases, stages, and steps in the PLC

| Phases | Stages | Steps |
|-------------------|---------------------------|--------------------------------------|
| Conceptualization | Conceive | Trigger event |
| | The product | Concept capture Clarification of |
| | | purpose Concept elaboration Concept |
| | | evaluation |
| Planning | Design | Basic design |
| | The product strategically | Development of performance criteria |
| | | Design development |
| | | Design evaluation |
| | Plan | Basic activities and resources basic |
| | The execution | plan Development of targets and |
| | strategically | milestones |
| | | Plan development |
| | | Plan evaluation |
| | Allocate | Basic design and activity-based plan |
| | Resources tactically | detail |
| | | Development of resource allocation |
| | | criteria |
| | | Allocation development |
| | | Allocation evaluation |
| Execution | Execute | Co-ordinate and control |
| | Production | Monitor progress |
| | | Modification of targets and |
| | | milestones Allocation modification |
| | | Control evaluation |
| Termination | Deliver | Basic deliverable verification |
| | The product | Deliverable modification |
| | | Modification of performance criteria |
| | | Deliver evaluation |

Review Basic review

The process Review development

Review evaluation

Support Basic maintenance and liability

The product perception

Development of support criteria

Support perception development

Source: Chapman and Ward (2003).

Based on the literature emerges, the most common PLC model is consists of four main project phases. The scope of presented examples of PLC can be adjusted depending on the industry and applicable to a general project concept. Some authors describe PLC's which are typical for a certain industry or sector to make a project planning in the PLC more convenient.

A PLC framework which is typical for construction projects is presented by Bennet (2003). For the construction project, the framework differs from those general models mentioned above, and distinguishes phases and steps characteristics. Its graphic illustration is presented in Figure 2.1 which is consist of six phases of different lengths and starts with Pre-project phase followed by Planning and design, Contractor selection, Project mobilization, Operations, and Close-out and Termination phase. The construction industry requires a special approach due to the complexity of projects undertaken and thus such modified PLC should bring benefits to project management and its performance (Bennett, 2003).




Figure 2.1 PLC for a construction project

2.2.1 Pre-project phase

The purpose of the initial phase in a PLC is to develop an idea for a potential project (Bennett, 2003). This step is described by Westland (2006) in more detail as developing a business opportunity which includes identification of a subject matter or problem which could be further developed into a project. In creating a project idea, the number of assessments and discussions are required in order to identify the business opportunities. Initial problem description, its scope, time frames and an outline of a plan for activities and steps in next phases of the PLC, are some of the factors which should be determined by the time the proposal is presented to a potential sponsor (Westland, 2006).

Furthermore, a project delivery system is chosen in the pre-project phase. The relationships between main actors in the project which is the owner, the designer and the construction organization are established. It indicates that there is a relation between the factors where other researches show that the choice of procurement system has a great impact of how risks are managed in the construction industry. Chege and Rwelamila (1999) emphasized the relationship between risk response in the RMP and the procurement system.

2.2.2 Planning and design phase

Bennet (2003) presented the second phase in the PLC, where the planning and design phase are relatively longer than the others. For more convenient phase completion and project delivery, the project development process consists of three sequential stages.

Project organization starts to be formulated in the first step. Main actors in the project and their roles are defined along with competences which are assigned to each position in particular (Bennett, 2003). A project brief is written which in details describes the scope of the project and its objectives after the project team is appointed. In a construction project, first the needs of the stakeholders must being identified and then the design team makes initial sketches of each idea separately (Bennett, 2003). It helps to recognised potential risks associated with proposed solutions. As a result of this examination, all identified ideas are ranked and the most feasible one is chosen for further development (Westland, 2006).

Further on, site investigation and constructability analysis should be undertaken in the planning phase. A number of potential sites in respect to soil conditions, topography, location and price should be examined. A proposed structured is determined by the constructability analysis whether it is easy to build and what effect will it have on schedule, budget or safety. It is vital to determine in a planning phase whether potential investment is financially feasible. Thus the cost estimator should prepare a preliminary budget of a project where all types of possible costs and the price per unit or activity are determined (Bennett, 2003).

The project team chooses the best alternatives when all options in the feasibility study are analysed and proceeds to the next step in the PLC which is the design process. All assumptions made in previous stages are put into practice. In other words, the actual detail plans are developed from schematic drawings drawn up under planning phase. A small specialized group of engineers are developed every technical aspect such as structure calculation or accessory planning. A clear vision of the investment emerges as a result of the whole design process.

Development of a contract document is the last activity in the planning and design phase. Technical specifications, up-front documents and drawings are included in the contract document. By various institutions such as FIDIC, its format can be based on standards issues which is a standard widely used in international projects. This document sets forms as well as invitation to tender and instructions. Established tendering processes enable the project team to proceed to the next stage which is contractor selection (Bennett, 2003).

2.2.3 Contractor selection phase

In this stage a contractor is selected (Bennett, 2003). However it is not always price which decides who will be awarded the contract (Potts, 2008). The number of criteria in the selection process are taken into consideration such as qualifications, resources held or bid price and compiled in a criteria matrix. Such collected data are evaluated and if no other criteria have been set, the offer which scores highest is usually awarded the contract. For the selection phase to be completed, a legally bidding contract agreement is signed between the owner and contractor (Bennett, 2003).

2.2.4 Project mobilization phase

There is a number of activities which need to be considered in between choosing contractor and beginning of construction. To apply for any type of necessary permits and licenses prior to construction works initiations, it is in the contractor's responsibility. Moreover, detail schedule is developed with the help of computer software in this phase where it is initially drawn up in the planning phase. It is further used to plan employment and other resource utilities over time (Bennett, 2003).

2.2.5 Project operation phase

There are three key activities in addition to the construction itself during the operation phase, which are monitor and control, resource management, and documentation and management. Monitor and control covers supervision of, among others, time, cost and quality (Bennett, 2003). The person who undertakes this management process to keep track of undergoing activities is usually the project manager. Time, cost and quality as previously mentioned are key aspects of each project and hence managing them is an important activity. To log actual time spent for execution of certain task, time management is used. It also helps to allocate resources more effectively and control schedule of performing works (Westland, 2006).

The actual schedule and work progress is compared to the schedule drawn up in previous phases. If any discrepancies are detected, a person responsible should take an appropriate action in order to bring the project back into conformance (Bennett, 2003). Other key issues, finances and quality are possible to manage by keeping track of the time aspect. To record all actual expenses within the project, the cost control is used and it gives control over a budget and out-of-pocket expenditures. Whereas quality monitoring is performed in order to deliver what was promised to the client (Westland, 2006), it also controls whether the work performed is in compliance with technical requirements stated in tender documentation (Bennett, 2003).

Undertaking the second activity which is resource management results in the better project performance. Personnel supervision is to ensure that workers perform their tasks in a right manner and comply with officially set working hours. Other resources like materials or equipment need to be tracked along with personnel. Any irregularity in these matters may negatively impact the schedule, budget or quality, causing delays or cost overruns (Bennett, 2003).

Document management is the last activity in the operation phase, but its importance should not be ignored because it treats communication within the project and grandness of other documents. As in previous examples, proper management of this matter will make the project proceed in a timely, cost-effective and quality assurance manner (Bennett, 2003).

2.2.6 Project close-out and termination phase

At the execution phase, most of PLC's end up where the final product is handed over after being accepted by the client. Performing a project summary requires additional resources, time and money, which investors tend to prefer to spend on new investments instead (Westland, 2006). However, from a legal perspective, project close-out and termination is important among others. There are still activities which must take place before installation works can be considered as completed. The main ones are final clean up, inspections, handover to the owner and project closure (Bennett, 2003).

As suggested by Westland (2006), the final procedure in the PLC is to review the project completion. The overall project assessment is performed in this step. To improve their performance, it gives possibility to draw conclusions for next projects. The completed activities are compared with all initially planned activities such as budget, schedule or scope to assess how the product was delivered in comparison to the plan. Such a review can be performed some time after the project handover in order to be able to assess all benefits (Westland, 2006).

2.2.7 Risks in the PLC

One common definition should be drawn up for the purpose of the particular project to make sure that everybody connected with a project is aware what a risk is. Westland (2006) uses a tool where likelihood of occurring risk is rated to quantify identified risks. When risk plan is completed the risk management process execution starts, which is a tool to track and control previously identified risks (Westland, 2006).

Risks are associated with every project and in order to avoid negative impacts on the overall performance, it should be identified. Many problems which are faced in later phases of the PLC result from unmanaged risks from the earlier stage (Chapman and Ward, 2003). It can be prove where it is very important to carry out accurate analysis especially in an initial phase of a project. Raz *et al.* (2002) sees RM as a process which starts at project definition and continues through planning, execution, control and closure phase. However, Lyons and Skitmore (2002) conducted a study proves that planning and execution are the two phases where RM is most widely used. In contrast, Elkington and

Sallman (2002) figure out that the conceptualization phase is the most important in the RMP.

It has been identified by Westland (2006) that project steps where more attention should be directed toward risk management. The feasibility study is undertaken in the initial project phase which is a thorough analysis of a project proposal. A number of solutions are identified and assessed at this stage and the study is conducted to identify potential risks associated with proposed solutions. A risk plan is drawn up further in the planning phase where potential risks related to project planning are identified. All the stakeholders must contribute in drawing up this plan to ensure that every potential risk has been identified. The risk plan assigns the type of action which should be taken in addition to identifying risk in order to respond to a particular problem. Performing this stage in the planning phase aims at mitigating risk before the execution phase, during which any occurring risk is very costly if no action is taken in advance (Westland, 2006).

It has been suggested by Westland (2006) that risk assessment should be performed during the review of each phase of the PLC. A high level of uncertainty is expected at the beginning of a project which decrease along with project progress. It is necessary to go back and revise controversial issues from their origin where doubts are rise at any point. There is a procedure where required to go back to previous steps and discussing them with the new assumptions. There is also a need for adjustments in previous steps while making decisions when moving further in the PLC. In other words, changing concepts of steps further up in the PLC which were made at the initial phase may occurred where there are decisions made at a certain point of time.

Monitoring and control are performed in the execution phase of the PLC in order to make sure that the process is going according to the plan and all identified risks are being handled. Starting with the point in time when the risks were recognized, such monitoring should be done under the whole project process. The project's objectives, benefits and deliverables are evaluated where the whole project is summarized at the project closure. All activities or risks which were not fully managed within the project will be listed by the all parties. Those unmanaged risks can be a subject of further discussion and be used as warning for next projects (Westland, 2006).

2.3 Risk Management Process for Construction Projects

Risk management is a cyclical process where it is made up of critical steps and the number of risk management processes is proposed. Risk management is the effort to optimize decisions in order to reduce uncertainty about future events when the information is incomplete, unclear or under discussion (Jafari, Rezaeenour, Mazdeh and Hooshmandi, 2011). Previous studies on risk management had outlined different approaches to risk management. For instance, Chapman and Ward (1997) listed out a generic project risk management process which consists of nine phases:

- Define the key aspects of the project
- Focus on a strategic approach to risk management
- Identify where risks might arise
- Structure the information about risk assumptions and relationships
- Assign ownership of risks and responses
- Estimate the extent of uncertainty
- Evaluate the relative magnitude of the various risks
- Plan responses and
- Manage by monitoring and controlling execution.

A process that consists of identification, analysis, assessment and control also been suggested by Akintola and Macleod (1997). However, it has been recognized by the construction industry that a systematic risk management is essential to manage the risk affecting construction projects. There are four well-known approaches to risk management which have been propagated by the following institutes (Jafari et al, 2011). These are; PMBOK (2004), Project Risk Analysis and Management (PRAM) (APM, 2004), Management of Risk (MOR) (Office of Government Commerce, 2007) and the standard AS/NZS4360:2004 (Standard Australia/standards New Zealand, 2007), however, there is no major difference between them. All these approaches are presenting the key steps of planning, identification, qualitative and quantitative analysis, reaction to risk, and controlling.

Jia, Ni, Chen, Hong, Chen, Yang and Lin (2013), presents Figure 2.2 that illustrates six processes and their relationships. Risk management planning is the starting point of the entire risk management procedure among these processes. To regulate and

promote four successive processes in the core risk management, it is very useful and besides it's also to roll forward with management system oriented self-improvement in the whole project development flow from project inception through design and construction to project completion. In the entire risk management procedure, risk management reporting is the finishing point. It is very useful for organizations to understand current situations and take corresponding measures in their risk management practice. Besides, it also helps to summarize the risk management with regular outputs with regard to predefined risk control points.




Figure 2.2 Risk management process for construction projects Source: Jia et al (2013).

Hence, this cycle of risk management process also agree with the definitions of construction with the related professional institutions for example, Association of Project Management (APM, 2004), Institution of Civil Engineers (ICE, 2015) and the Construction Industry Research and Information Association (CIRIA, 5015). These construction institutions believe that a structured and systematic risk management is necessary to manage the risk affecting construction projects.

2.3.1 Definition of Risk Management Objective

The objectives of the risk identification and assessment process can be clearly defined at the first stage of the risk management process. This stage is important because

it shows the scope and margin for the extensive risk identification and assessment procedures (Issac, 1995).

2.3.2 Risk Identification

Tchankova (2002) states that risk identification is the beginning of the process of risk management which develops the basis for the next steps of analysis, assessment and control. It ensures risk management effectiveness if it is done correctly. Consequently, it illustrates that risk identification must be seen in a broader way and not just be seen as what can be insured or mitigated (Tchankova, 2002). Risk identification should start with the basic question like;

- How can the project resources be threatened?
- What adverse effect can prevent the project from achieving its goals?
- What favourable possibility can be revealed?

The identification process at start enables a good basis for the implementation of the project and does not put up any barrier about the type of risk that would be identified or the resources that can be influenced (Tchankova, 2002). Risk identification reveals and determines the possible project risk as well as conditions (Williams et al, 1998). The project managers able to study activities and places where resources are exposed to risk through risk identification. Risk identification, presented by Tchankova (2002), can be describe based on these elements:

- **Sources of risk:** these are the elements of the project environment that can bring some positive or negative outcome.
- **Hazard:** it is a condition or a circumstance that increases the chances of losses or gains and their severity.
- **Peril:** this is a circumstance that is close to risk and has negative, non-profitable results. Peril can happen at any time and cause unknown, predictable losses. Peril is the cause of losses.
- Exposure to risk: this is an object facing possible loss or gain. They will be affected if the risk occurs.

Risk identification is a continuous process. It is not possible to identify risk as a one off activity (Tchankova, 2002). Basically, to thoroughly identify the critical risks

affecting a building construction project, the techniques used include but is not limited to;

- i. **Brainstorming:** This is the commonly used method (APM, 2004). The technique used to identify and assess risk in a building construction project is by bringing together all interested and relevant parties or personnel. The purpose of this technique is to identify a large quantity of potential risks affecting a project. Accordingly, this process encourages the identification of risk concerns in a non-critical way and not ascribing blame to the identified risk (Banes, 2000). In order to gain an effective brainstorming session, it must include individuals of knowledge, experience and expertise in risk management with an optimum size of twelve members (Chapman, 1997; Smith and Bohn, 1999).
- ii. The Delphi Technique: This is involving a process where the questionnaires are used to identify risks or the impact estimation, and even the probability of previously identified specified risks towards the qualified people by consultation and ask. The opinions given anonymously to allow the technique to be carried out remotely. The responses are summarized and the estimates are drawn out by the risk coordinator based on the results. This information is re-circulated for a repeat session. The process will continue until a stable opinion is reached (Banes, 2000). This technique is more time consuming and expensive compared to the brainstorming technique (Chapman 1998). The lack of interaction and communication is one of the shortage of this technique because the respondents may encounter difficulties in interpreting the questions and results.
- iii. Interviews: As a follow-up to the group-oriented techniques previously described, the interviews may be used. To assess risk parameters, identify possible mitigation and contingency measures and to elicit data, the interview is held towards the individuals with expertise relevant to a particular risk issue. This is a precursor to any quantitative analysis that maybe required (Banes, 2000). This technique is about the time consuming. The question must be properly structured in order to effectively gather the required information due to time limitations. Vague and confusing questions should be avoided so that the feedback gained from the interviewees is not misleading (Chapman, 2001). Another disadvantage of this technique is that the information gathered is based on expert's subjective judgement which may not be free from bias.

- **iv. Experiential knowledge:** This is a process where individuals obtain information through their experience in the construction industry (Clear Risk, 2015). It is important to understand that knowledge based information acquired in this kind of process must be relevant and applicable to the existing building construction project.
- v. Outputs from Risk-oriented Analysis: Clear Risk report (2015) describes that there are numerous types of risk oriented analysis. For instance, there are the fault tree analysis and event tree analysis. These approaches are top down analysis approach that intends to determine what event, conditions or faults that could lead to an undesirable or unacceptable event. These events can be associated to a risk in a construction project. (Odimabo, 2016).
- vi. Risk Register: Risk register consists of standard format that will be used to record risk information gathered using the risk identification techniques previously describe. It records various data for each individual risk issue, including a description, potential causes, ownership, probability, impacts, mitigation and fall-back plans and status (Banes, 2000). In its detailed form it may even include an identification of secondary risks, contingency plans and quantitative parameters (Banes, 2000). Nevertheless, the use of checklists to initiate the risk identification process is not advisable since they may constrain the identification of new risks (ICE et al., 2005).

2.3.2.1 Sources of Construction Risks

A direct relationship between effective risk management and project success is acknowledged since risks are assessed by their potential impact on the project objectives (Balio and price, 2003). Hence, engaging effective risk management techniques to manage risk associated with variable construction activities has never been more important for the successful delivery of projects (Zou et al. 2007).

In managerial practice, different definitions and classifications can be used in managerial practice. Tchankova (2002), states that general classification may use physical, social and economic sources. However, an in-depth investigation of the problem of risk identification may need classification that can cover all types of risk in more detail (Tchankova, 2002). Thus, depending on the construction environment, the sources of risk can be represented.

Many approaches are suggested for classifying risk. It has been presented by El-Sayegh (2008) the list of several factors in the terms of owners, design, contractors, sub-contractors, suppliers, political, social and cultural, economic and natural. Nieto-Morote and Ruz-Vila (2011) presented four ways of classifying risk which are project management, engineering, execution and supplier's risk. Kuo and Lu (2012) group risk into five sub-sets which are engineering design, construction management, construction safety-related, natural hazards, socio and economic. Moreover, Dikmen et al (2007) categorised risk into eight ways which are technical, managerial, resource, productivity, design, payment, client and subcontractor's risk. To classify the risks, many ways can be used associated with construction projects.

2.3.3 Qualitative Risk Analysis

Qualitative risk analysis is regarded as the most useful part of the risk management process as the results gained from the analysis will be used extensively in the subsequent stages (Smith, 1999). The requirement at this stage is the important information about risks for example the likelihood of occurrence, the risk severity, and risk ownership. Risk are usually assessed by using Probability-Impact (P-I) Grids.

i. Probability-Impact (P-I) Grids – known for assessing and ranking risks by using a tabular format. The rows and columns of the grid are formed from these two attributes which are the probability of occurrence and risk impact as seen in Table 2.3. The advantage of using probability-impact grids is their simplicity, and risks can be assessed conveniently without precisely specifying their impacts and probabilities of occurrence (Ward, 1999).

| | V High | | | | | |
|--------|--------|-------|-----|-----------|------|--------|
| | High | | | | | |
| ±. | Med | | | | | |
| Impact | Low | | | | | |
| 1 | V Low | | | | | |
| | | V Low | Low | Med | High | V High |
| | | | Pı | robabilit | y | |

Figure 2.3 Example of a P-I table Source: Vose (2008).

The estimates of likelihood of events and consequence of events for each risk characteristics can be assigned qualitatively, for instance High, Medium and Low etc. as shown in Table 2.3. Besides, each of these verbal scales can be related to a scale value. The P-I score for each cell in the grid can be determined as the result of the multiplication of probability and impact scale values; an arbitrary value; or an alphabet (Ward, 1999). Consequently, it is necessary to achieve a consistent quantification of risk likelihood of occurrence and the magnitude of the risk by using a common language in describing them as been suggested by Tah and Carr (2001).

2.3.3.1 Risk Exposure

Fraser and Simkins (2010), states that risk exposures as the extent to which the situation where one is exposed to risk. It is describing as the potential impact of a risk event and its probability of occurrence. These potential risk events however can impact on a construction organization in achieving its goals (Fraser and Simkins, 2010). Accordingly, risk exposure is used to quantify and compare then decide how to respond to them if more than two events may occur.

It has been presented by Lock (2013), the use of four main quadrants for risk exposure which are:

- High chance High impact
- High chance Low impact

- Low chance High impact
- Low chance Low impact

Low chance-low impact is known as the least important type of risk, while high chance-high impact is known as the most important type of risk. The purpose of describing risk assesses qualitatively is to determine their likelihood and potential effect on project objectives. Besides, Hilson (2002) describes that the Probability-Impact Matrix is useful where it is involving rotating opportunity half as shown in Figure 2.4. By focusing on the "Arrow of Attention", this allows key threats and opportunities to be visualised. If the organisation is more risk-adverse or if more effort is available for risk management, the size of this wedge can be increased.




Figure 2.4 Probability-Impact Matrix for opportunities and threats Source: Hillson (2002).

Based on Figure 2.4, the probability and impacts of each risk are assessed against defined scales, and plotted on a two-dimensional grid. Position on the matrix represents the relative significance of the risk, and high/ medium/low zones may be defined, allowing risks to be ranked (Odimabo, 2016).

2.3.3.2 Risk Acceptability

Godfrey (2006) suggests that individual risk can be classified depending on the amount of risks an organization might be facing as:

- i. Unacceptable intolerable must be eliminated or transferred.
- **ii. Undesirable** to be avoided if reasonably practical, detailed investigation of cost justification is required, top level approval is needed, monitoring is essential.
- iii. Acceptable can be accepted provided that the risk is managed.
- iv. Negligible no further consideration needed.

2.3.4 Quantitative Risk Analysis

This process is made easier with the creation of a model, which represents the project being studied (Banes, 2000). The model may then be modified to quantify impacts on the project of the specific risks identified using qualitative techniques (Banes, 2000). It also explains the effect of general uncertainty on the project (Banes, 2000). The model that will be constructed is based on an activity network, spread sheet, or a diagrammatic tool. Whichever modelling method is used, it will include all those elements comprising the undertaking (tasks, costs, durations etc.), which are relevant to the risk analysis (Eaton, 2010). Against these elements, uncertainty variables can be entered rather than deterministic values, in order to reflect areas of significant uncertainty (Eaton, 2010).

- i. Decision tress: A decision tree is a graphical method of modelling a project, showing the possible effects of individual risks requiring project decisions and immediate-planned courses of action to the overall outcome (Eaton, 2010). The probability of occurrence for each outcome is assigned and it allowed the most probable outcome to be determined. Alternative actions can be explored within the model in order to identify the most beneficial expected outcome of the project or activity (Banes, 2000).
- **ii. Influence Diagrams:** The influence diagram was first defined as an aid to formulating problems prior to decision-making (Banes, 2000). Odimabo Otobo (2016) states that influence diagrams allow the construction of models representing the influences upon a project goal or target. The model exposes the key influences and allows the effect of uncertainty to be determined. These models can become very complex, leading to the need for effective graphical presentation as well as computational efficiency (PRAM, 2004).
- **iii. Probability Analysis:** This is a statistical method, which calculates the impact of every single risk factor, or the impacts of all risk factors on the project (Boothroyd and Emmett, 1996). In this technique, Optimistic, Most Probable, and Pessimistic

- time and cost estimates are given for each activity, or for the project as whole (Eaton, 2010).
- **iv. Sensitivity Analysis:** This technique seeks to examine the sensitivity of a risk model to individual risk (Banes, 2000). This analysis could be done by doing a repetitive calculation of the effect on the project outcome through the range values of the variables. The project outcome is usually considered in terms of time of construction, or the final cost of a project (Eaton, 2010).
- v. Monte Carlo Simulation: This is a technique where single value estimates (of duration, resource, cost, and logic) are replaced by a distribution to reflect the perceived uncertainty of those estimates (Banes, 2000). Then it is generating a random number and a corresponding value sampled from the distribution. A single value is calculated for each target for e.g. time and cost overruns once samples have been taken from all variables in the model. To get the possible outcomes from the distribution, the process must be repeated in many times.
- vi. Simple Assessment: This is a relatively simple mathematical method that investigates the significant risks separately by inspecting their probable effect on total project time/cost (Boothroyd and Emmett, 1996). The evaluation is based on the expected impact calculated from every significant risk. The total impact is used as foundation for a contingency plan once the impacts are added up.
- vii. Criticality Analysis: Usually in project planning, the duration of each project task is given in a single value which it is most likely for the duration of the project. The tasks which is the analysis is performed to determine the critical path where it will directly determine the duration of the project. Criticality analysis allows the project manager to determine which activities could become critical if risks are not being effectively managed. Besides, it also indicates the subcritical paths which could be monitored alongside the main project critical path (Odimabo, 2016). Particular attention should be paid to tasks with a high criticality index, especially if they also have significant risks associated with them (Banes, 2000).

In the quantitative risk analysis phase, Sodhi and Tang (2012), figured out expected outcomes for risk analysis in construction. This is so that it can be used to define the expectations to be supported by risk model as to:

- Understand the nature of threats and other risks to help counter these better
- Support risk measures for informing their stakeholders,

- Help management focus on specific areas and
- Support allocation of risk management efforts and budget to different risk mitigations such as to answer the question of who should make such an investment (contractors, subcontractors or its clients) in construction industries.

In order fulfil the defined purposes of the building construction risk analysis, the selected model should be able to provide the outcomes.

2.3.5 Risk Response and Monitoring

The risks that have been identified and analysed are not neglected in the implementation phase of construction projects. The result of risk analysis helps the responsible parties to understand the risk impacts, afterwards plan and undertake effective risk mitigation actions to control the effect before or when they occur.

Based on the previous research, (Odimabo, 2016), states that some organisations prepare to cope with uncertainty by different strategies and this can affect the building construction process system. How much the effects of adverse events can disrupt the building project performance depends on how well the current mitigating actions are implemented. The interaction of risk mitigating policies for different aspects has also been shown through the concept of risk-reward relationship (Chopra and Sodhi, 2004). The understanding of possible risk mitigating actions is important as it is defined as the key concept for systematic risk modellers. It has been clearly explained by Vose (2008) in Figure 2.5 on general risk mitigating actions especially in terms of implementing different risk mitigating strategies in different situations.




Figure 2.5 Mapping risk mitigation strategies with levels of probability and consequence

Source: Vose (2008).

According to Vose (2008) the responses for threats are:

- 1. Risk avoidance changing some aspect of the project so that the threat either cannot have an impact anymore or can no longer happen.
- 2. Risk transfer is another form of "reduce" response for reducing the impact only, and it is mostly only the financial impacts (a third party takes this responsibility). Common practice in risk transfer is to sign contracts that guarantee a certain level of performance and set penalties for when the contractor fails to meet it. Insurance is an attractive option when the adverse event that will happen is above the expected cost of insurance.
- 3. Risk reduction is a proactive action taken to either reduce the probability of the event occurring or to reduce the impact of it. However, this needs to be done at the strategic level because relevant high level of cost is involved. This option is suitable for any level of risk that is not severe (high probability and high impact) by trading off between benefits and costs.
- 4. Risk reserve/flexibility aims to increase responsiveness by adding some reserve (buffer) to cover risks or using redundancy policy. This risk reserved option is suitable for small or medium impact risks.
- 5. Risk retention/absorption/acceptance can be called self-insurance, because some risks are not critical so the cost of insuring against those risks may be higher than the cost of the loss if the adverse event happens. In other words, it is a conscious decision taken for retaining the threats. This option is suitable for risks that are not significant because they have both low likelihood and impact, compared with the cost of control.

And the responses for opportunities are:

- 1. Exploit: Grasping an opportunity to make sure it will happen and its impact will be realized.
- 2. Enhance: A proactive action taken to enhance the probability of the event occurring or to enhance the impact of it.

- 3. Reject: A deliberate decision taken for not exploiting or enhancing the opportunity.
- 4. Share: Parties sharing the gain (within pre-agreed limits), normally when the cost is less than the cost plan.

In practice, decision maker may be satisfied with their current level of risk with respect to the risk-reward trade-off where higher risk is associated with greater probability of higher return and lower risk with a greater probability of smaller return. In other words some decision makers may think that they have spent too much on resources (money, time, etc.) for managing risks which may not necessarily happen, so they may want to reduce their level of risk protection (Vose, 2008). However, it may adversely affect the organisation's reputation and image because this option can lower the public credibility of the construction organisation. Another option is gathering more data to reduce uncertainties of unknown (epistemic uncertainties) in order to make a robust decision (Ellegaard, 2008; Vose, 2008). Besides the direct strategy to manage risks, knowledge creation is useful as it can help to reduce either probability or the effects of risk effectively (Ellegaard, 2008).

2.4 Risk Factors in Construction Project

Wet weather can be a problem for a number of different types of construction jobs, roofing, excavating, and even concrete (Ida May, 2017). Heavy rain can also reduce visibility for the drivers of vehicles and equipment aside from being extremely unpleasant to work in. It poses its own risks for the safety of the workers where it can turn the ground on the site into mud. Wet weather can cause more problems, big delays, and increased costs. Wet weather is frequently the reason contactors use to request increased contract time or money (Joseph L., 2005).

Paul Netscher (2016) states that if the rain is 500mm in 3 months it will almost certainly disrupt the project. In many places, heavy rains can cause the ground to become sodden and the water tables to rise causing problems with excavating for utilities or basements. Heavy rains can cause problems even for completed construction jobs. Flood waters can erode roads to the point where they break and get swept away by the flow. Wet weather is especially dangerous and difficult when it comes to working on roofs. Even the most skilled worker can potentially get injured (Ida May, 2016).

Besides, there are many public holidays, which also cause the suspension of work (M. Haseeb, 2012). If public holidays and/or the annual builders' holidays fall into this 'extended' period, the contractor is entitled to extend this period further by the working days lost to holidays (Uwe Putlitz, 2016). Extension of time required when the public holidays are not considered in project planning because the work cannot be proceeded due to unavailability of workers during public holidays.

Malaysia, as a multi-racial country, multi-festivals are celebrated each year. This resulted in a high number of public holidays. These holidays can sometimes last for a week or two, or even more, depending on individual organisations. This situation affects projects as multiple organisations (consist of multiple races) are involved and they depend on each other to progress. If any of them is missing in action, it would certainly affect others. This situation, if not accounted for properly would lead to huge project delay (Salman Riazi, 2013).

CHAPTER 3

METHODOLOGY

3.1 Introduction

This chapter describes the research methodology used to identify how the duration estimation was done and to develop the optimum planning for construction project. In this chapter, it will discuss in detail about the methodology and procedures that will be applied in order to achieve all the data needed in this research. It will describe orderly manner in the aspect on how the data will be collected, where the sources of data obtained and the last one do the data management process and representing the result. Figure 3.1 below shows the methodology flow chart.

Methodology or research design is known as plan or framework which act as a guideline to complete a research. This chapter discusses the procedure which the research is conducted by using a chosen approach to achieve the research aim and objective. In this chapter, it consists of three parts which are data collection techniques, research materials and data analysis. Hence, every data collected must be related and applicable with the topic of study. Two approaches are taken into this research to gather all the reliable and relevant data which are the literature review and case study.




Figure 3.1 Research Methodology Flowchart

3.2 Data Collecting

The important stage in obtaining all required information from the fundamental is known as data collection where the purpose is to achieve objectives of the research. All related data are collected in accordance with the objectives as stated which to determine the typical number of rainy days and the public holidays, and to identify the effective number of days in construction planning.

3.2.1 Primary Data Collection

Primary data are collected from the literature review. Data collections for this research are all regarding to planning and scheduling process in order to estimate the duration process for a construction project. The primary data for this study were gathered through literature review of thesis, journals and textbook regarding the planning and scheduling process in construction industry by identifying the factor that may causes the extension of time for construction work. More information on the subject of planning and scheduling process are gathered. This primary data also functioned as a guideline for secondary data collection.

3.2.1.1 Literature Review

The comprehensive literature review had been carried out through variety information sources, which include journal, articles, research papers, information from the internet, newspaper and reference book. All this information given more understanding in:

- i. Planning and scheduling process in construction project
- ii. The duration estimation activity in construction project
- iii. Planning and scheduling by using Microsoft Project

3.2.2 Secondary Data Collection

Secondary data are based on the data that have been collected from related agencies for instance to determine the number of rainy days in Kuantan for each month. Secondary data are needed to obtain the optimum planning for construction project. After the secondary data are collected, the number of effective days are obtained and the planning and scheduling process could be proceed.

3.2.2.1 Related Agencies

The number of rainy days and public holidays are required for this research to obtain the optimum working days of this Medan Ikan Bakar project. The number of rainy days could be obtain by getting the data from the website such as Wunderground where all the weather forecast and reports could be acquired. Thus, the working day estimation could be produced along with the presence of data of public holidays in Malaysia. The public holidays possibly obtained from calendar where it consists of all the public holidays and for surely will help the process of working day estimation.

3.2.3 Tertiary Data Collection

Tertiary data are a data that gained from a research problem then with using a procedure that fit the research problem best. An often method of data collection used is case study and conducting interview. A case study is just like puzzles that have to be solved. Case study research brings an understanding of a complex issue or object and can extend experience or add strength to what is already known through previous research. (Nor Hashimah, 2016).

3.2.3.1 Project Report

For the case study, 'Cadangan Pembangunan Anjung Makanan Laut dan Kompleks Hasil Laut' which also known as 'Medan Ikan Bakar' is selected in order to achieve the objectives of the research. This study focus on this Medan Ikan Bakar project that have been constructed and fully finished in 2016. From the case study, data that need to gathered are such as the planning and scheduling of the project, weekly progress report, tender, duration estimation of the project and date of completion.

The Medan Ikan Bakar project report has been analysed and studied. The main construction program of Medan Ikan Bakar project has been studied in order to identify on how the project activities is planned and scheduling, linking activities for the whole project and the factors that will affect the duration of the project completion. By comparing the scheduling of the Medan Ikan Bakar report, the lacking and imperfectness of the scheduling prepared in the reports are analysed. For this research, we are focusing on the number of rainy days and public holidays.

The project reports covered for all the buildings that have been constructed in Medan Ikan Bakar and the budget cost for the project. The reports that had been analysed are listed below:

- Weekly Progress Report (January 2016): Cadangan Projek Pembangunan Anjung
 Makanan Laut dan Kompleks Hasil Laut Daerah Pekan, Pahang Darul Makmur.
- ii. Tender of Medan Ikan Bakar project (2016)

Based on the case study of the two reports mentioned above, each report will be analysed separately in term of their preparation of the planning and scheduling.

3.3 Pre-processing

Based on each case study, the scheduling for the main programmed will be studied. Data gathered will clarify the steps that include in the duration estimation process as to meet the objectives. The high risk factor that affects the construction work is identified and the understanding of risk management in construction industry is studied. For this research, we are focusing on the number of rainy days and the public holidays for the risk factors in this construction project.

These factors that are obtained from the literature review process are then proceed by figuring out the effective days that the construction project this Medan Ikan Bakar must produce in order to obtain the optimum planning. The design day could be done by obtaining the data from previous process which data collecting where the data are collected from the related agencies.

3.4 Data Processing/Analysis

The data processing which also known as analysis is the process where the new planning is produced based on the data collected from the previous process. This data processing could be done after the design day is produced. The summary of the project's planning is tabulated and comparison is done to the existing plan. The comparison is done in order to figure out the most optimum planning of construction work execution.

3.5 Result

After data processing or analysis is completed, the result could be obtained where the typical number of rainy days and the public holidays are determined and the effective number of days in construction planning is identified. Hence, the discussion from the result obtain could be made by elaborating the weakness and the missing items for the project that does not have the good and optimum planning. Besides, suggestion for the proposed preliminary guidelines is proposed to enhance the better performance of the building construction projects without extension of time.

CHAPTER 4

RESULT AND DISCUSSION

4.1 Introduction

This chapter will analyse and discussed all the result based on the case study. In

terms of presentation, the analysed data will be recorded in corresponding figure and table

with interrelated explanation.

From the study, the existing and reschedule of Medan Ikan Bakar project planning

are gathered and created. All data obtained from the Weekly Progress Report (January

2016) of Cadangan Projek Pembangunan Anjung Makanan Laut dan Kompleks Hasil

Laut Daerah Pekan, Pahang Darul Makmur and tender of Medan Ikan Bakar project

(2016) will be analysed. With the purpose of gaining data from the weekly progress report

and tender of Medan Ikan Bakar project, the project will be rescheduled to obtain the

optimum working days by considering the number of rainy days and public holidays due

to the extension of time that occurred.

Finally, the result came out in line with the determined objectives. In this chapter

therefore will explain in detail on the data gathered. Below are the background and scope

of works for the case study project that are being studied in this research.

Case Study: Existing plan

Project Title: "Cadangan Projek Pembangunan Anjung Makanan Laut dan

Kompleks Hasil Laut Daerah Pekan, Pahang Darul Makmur"

Start date: 02/02/2015

End date: 01/01/2016

39

Case Study: Reschedule plan

 Project Title: "Cadangan Projek Pembangunan Anjung Makanan Laut dan Kompleks Hasil Laut Daerah Pekan, Pahang Darul Makmur"

Start date: 02/02/2015End date: 01/02/2016

Scope of Works

1) Main Buildings - Restoran Ikan Bakar

- Gerai Pengumpulan Hasil Laut

- Industri Hasil Laut

2) Ancillary Buildings - Surau

- Tandas Awam

- Wakaf

3) External Works - Site Preparation & Earthwork

- Surface Water Drainage

Roads and Parking

Water Reticulation System

- Sewerage System

4) Mechanical and Electrical Works - Sanitary Plumbing Services

Fire Fighting Installation

Electrical Installation

5) Provisional Sum - Hard and Soft Landscape

Rubbish Bin

- Children Playground

- Signages

4.2 Factors Affecting Duration Estimation Process

Preparation of a construction planning for any project is a very complex process. Process of a construction planning contains many variable factors. Every variable has to be correctly estimated based on proper study, past experience and research to produce the effective planning with good performance of work.

There are many factors which affect the construction duration estimation and have significant impact on project duration where it will cause the project to delay and required extension of time. In this study, there are two factors that we considered during the duration estimation process. The two factors affecting construction duration as shown are the most significant factors. These factors were listed and explained as follows:

- i. Number of rainy days
- ii. Number of public holidays

4.2.1 Number of rainy days

Weather conditions can also have an effect on how long the duration of the construction project needed to be completed. Some tasks cannot be completed due to the rain. This means that the project may be put on hold until the weather passes and at the same time can slow down the construction project where it will cause delay.

Malaysia faces two monsoon winds seasons, the Southwest Monsoon from April to September, and the Northeast Monsoon from October to March. Between October and the end of March the climate at the eastern side of the peninsula is affected by the rainy season or monsoon season. It is known as the Northeast Monsoon which involving the Pahang, Terengganu and Kelantan. The Northeast Monsoon brings in more rainfall compared to the Southwest Monsoon.

It can be seen where the average number of rainy days in Kuantan is slightly higher during the end of the year starting in October. The average number of rainy days in Kuantan is presented in the table as follows:

Table 4.1 Average number of rainy days in Kuantan

| Month | Number of rainy days |
|-----------|----------------------|
| January | 7 |
| February | 4 |
| March | 5 |
| April | 6 |
| May | 8 |
| June | 6 |
| July | 6 |
| August | 8 |
| September | 7 |
| October | 9 |
| November | 10 |
| December | 12 |

For the Medan Ikan Bakar project, the project starts to slow down during the end of the year. It can be related to the weather condition where Kuantan is having the monsoon season that causes the project to slow down or put on hold. This is the reason why the number of rainy days needs to be considered during the planning of the project, where it could affect the completion of the work progresses.

4.2.2 Number of public holidays

The number of public holidays must be considered in the construction industry because some of the issues of delay that happens in construct project are regarding to the public holidays. This can be seen where some of the project manager did not include public holiday in the duration of construction and it will cause delay. Extension of time required when the public holidays are not considered in project planning because the work cannot be proceeded due to unavailability of workers during public holidays.

In this study, the number of public holidays for year 2015 and 2016 are presented as follows:

Public National Holidays and State Holidays

| Date | Holiday | Applicable to |
|--------------|--|---|
| 1 Jan (Thu) | New Year | All except Johor, Kedah, Kelantan, Perlis & Terengganu |
| 3 Jan (Sat) | Prophet Muhammad's Birthday (Maulidur Rasul) | National |
| 14 Jan (Wed) | Yang di-Pertuan Besar Negeri Sembilan's Birthday | Negeri Sembilan only |
| 18 Jan (Sun) | Sultan of Kedah's Birthday | Kedah only |
| 1 Feb (Sun) | Federal Territory Day | Federal Territory of Kuala Lumpur, Labuar & Putrajaya only |
| 3 Feb (Tue) | Thaipusam | Kuala Lumpur, Putrajaya, Johor, Kedah, Negeri Sembilan, Perak, Penang & Selangor only |
| 19 Feb (Thu) | Chinese New Year | National |
| 20 Feb (Fri) | Chinese New Year (2nd Day) | National |
| 4 Mar (Wed) | Anniversary of Installation of Sultan of Terengganu | Terengganu only |
| 23 Mar (Mon) | Coronation of Sultan Ibrahim Ibni Almarhum Sultan Iskandar of Johor | Johor only |
| 3 Apr (Fri) | Good Friday | Sabah & Sarawak only |
| 15 Apr (Wed) | Declaration of Malacca as a Historical City | Malacca only |
| 26 Apr (Sun) | Sultan of Terengganu's Birthday | Terengganu only |
| 1 May (Fri) | Labour Day | National |
| 3 May (Sun) | Vesak Day | National |
| 7 May (Thu) | Hari Hol Pahang | Pahang only |
| 16 May (Sat) | Israk & Mikraj | Kedah, Negeri Sembilan & Perlis only |
| 17 May (Sun) | Raja Perlis' Birthday | Perlis only |
| 30 May (Sat) | Harvest Festival | Sabah & Labuan only |
| 31 May (Sun) | Harvest Festival | Sabah & Labuan only |
| 1 Jun (Mon) | Hari Gawai | Sarawak only |
| 2 Jun (Tue) | Hari Gawai | Sarawak only |
| 6 Jun (Sat) | Agong's Birthday | National |
| 18 Jun (Thu) | Awal Ramadan * | Johor, Kedah & Malacca only |
| 4 Jul (Sat) | Nuzul Al-Quran | Kelantan, Pahang, Perak, Perlis, Penang Selangor ,Terengganu and Federal Territories (Kuala Lumpur, Putrajaya and Labuan) only |
| 7 Jul (Tue) | Georgetown World Heritage City Day | Penang only |
| 11 Jul (Sat) | Penang Governor's Birthday | Penang only |
| 17 Jul (Fri) | Hari Raya Puasa * | National |
| 18 Jul (Sat) | Hari Raya Puasa * | National |
| 31 Aug (Mon) | National Day | National |
| 12 Sep (Sat) | Sarawak Governor's Birthday | Sarawak only |
| 16 Sep (Wed) | Malaysia Day | National |
| 24 Sep (Thu) | Hari Raya Haji * | National |

| 25 Sep (Fri) | Hari Raya Haji (2nd Day) * | Kedah, Kelantan, Perlis & Terengganu Only |
|--------------|---|--|
| 3 Oct (Sat) | Sabah Governor's Birthday | Sabah only |
| 9 Oct (Fri) | Malacca Governor's Birthday | Malacca only |
| 14 Oct (Wed) | Awal Muharram (Maal Hijrah) | National |
| 24 Oct (Sat) | Sultan of Pahang's Birthday | Pahang only |
| 10 Nov (Tue) | Deepavali | National except Sarawak |
| 11 Nov (Wed) | Sultan of Kelantan's Birthday | Kelantan only |
| 12 Nov (Thu) | Sultan of Kelantan's Birthday | Kelantan only |
| 18 Nov (Wed) | Hari Hol Almarhum Sultan Johor | Johor only |
| 22 Nov (Sun) | Sultan of Johor's Birthday | Johor only |
| 27 Nov (Fri) | Sultan of Perak's Birthday | Perak only |
| 11 Dec (Fri) | Sultan of Selangor's Birthday | Selangor only |
| 24 Dec (Thu) | Prophet Muhammad's Birthday (Maulidur Rasul) | National |
| 25 Dec (Fri) | Christmas | National |

Figure 4.1 Public National Holidays and State Holidays in 2015 Source: One Stop Malaysia (2015).

Public National Holidays and State Holidays

| Date | Holiday | Applicable to |
|--------------|---|--|
| 1 Jan (Fri) | New Year | All except Johor, Kedah, Kelantan, Perlis & Terengganu |
| 14 Jan (Thu) | Yang di-Pertuan Besar Negeri Sembilan's Birthday | Negeri Sembilan only |
| 17 Jan (Sun) | Sultan of Kedah's Birthday | Kedah only |
| 24 Jan (Sun) | Thaipusam | Kuala Lumpur, Putrajaya, Johor, Kedah, Negeri Sembilan, Perak, Penang & Selangor only |
| 1 Feb (Mon) | Federal Territory Day | Federal Territory of Kuala Lumpur, Labuan & Putrajaya only |
| 8 Feb (Mon) | Chinese New Year | National |
| 9 Feb (Tue) | Chinese New Year (2nd Day) | National |
| 4 Mar (Fri) | Anniversary of Installation of Sultan of Terengganu | Terengganu only |
| 23 Mar (Wed) | Sultan of Johor's Birthday | Johor only |
| 25 Mar (Fri) | Good Friday | Sabah & Sarawak only |
| 15 Apr (Fri) | Declaration of Malacca as a Historical City | Malacca only |
| 26 Apr (Tue) | Sultan of Terengganu's Birthday | Terengganu only |
| 1 May (Sun) | Labour Day | National |
| 5 May (Thu) | Israk & Mikraj | Kedah, Negeri Sembilan & Perlis only |
| 7 May (Sat) | Hari Hol Pahang | Pahang only |
| 17 May (Tue) | Raja Perlis' Birthday | Perlis only |
| 21 May (Sat) | Vesak Day | National |
| 30 May (Mon) | Harvest Festival | Sabah & Labuan only |
| 31 May (Tue) | Harvest Festival | Sabah & Labuan only |
| 1 Jun (Wed) | Hari Gawai | Sarawak only |
| 2 Jun (Thu) | Hari Gawai | Sarawak only |
| 4 Jun (Sat) | Agong's Birthday | National |
| 6 Jun (Mon) | Awal Ramadan * | Johor, Kedah & Malacca only |
| 22 Jun (Wed) | Nuzul Al-Quran | Kelantan, Pahang, Perak, Perlis, Penang, Selangor ,Terengganu and Federal Territories (Kuala Lumpur, Putrajaya and Labuan) only |
| 6 Jul (Wed) | Hari Raya Puasa * | National |
| 7 Jul (Thu) | Hari Raya Puasa * | National |
| 7 Jul (Thu) | Georgetown World Heritage City Day | Penang only |
| 9 Jul (Sat) | Penang Governor's Birthday | Penang only |
| 31 Aug (Wed) | National Day | National |
| 10 Sep (Sat) | Sarawak Governor's Birthday | Sarawak only |

| 12 Sep (Mon) | Hari Raya Haji * | National |
|--------------|---|--|
| 13 Sep (Tue) | Hari Raya Haji (2nd Day) * | Kedah, Kelantan, Perlis & Terengganu Only |
| 16 Sep (Fri) | Malaysia Day | National |
| 1 Oct (Sat) | Sabah Governor's Birthday | Sabah only |
| 2 Oct (Sun) | Awal Muharram (Maal Hijrah) | National |
| 14 Oct (Fri) | Malacca Governor's Birthday | Malacca only |
| 24 Oct (Mon) | Sultan of Pahang's Birthday | Pahang only |
| 29 Oct (Sat) | Deepavali * | National except Sarawak |
| 6 Nov (Sun) | Hari Hol Almarhum Sultan Iskandar | Johor only |
| 11 Nov (Fri) | Sultan of Kelantan's Birthday | Kelantan only |
| 12 Nov (Sat) | Sultan of Kelantan's Birthday | Kelantan only |
| 27 Nov (Sun) | Sultan of Perak's Birthday | Perak only |
| 11 Dec (Sun) | Sultan of Selangor's Birthday | Selangor only |
| 12 Dec (Mon) | Prophet Muhammad's Birthday (Maulidur Rasul) | National |
| 25 Dec (Sun) | Christmas | National |

Figure 4.1 Public National Holidays and State Holidays in 2016 Source: One Stop Malaysia (2016).

4.3 Planning and Scheduling

Planning in construction plays the very important role in the construction management. Planning of construction activities is crucial in order to help engineers to complete the project on time, within the budget and good quality. In the management and execution of construction projects, construction planning is known as a fundamental and challenging activity where it involves the choice of technology, the definition of work tasks, the estimation of the required resources and durations for individual tasks. A good construction plan is the basis for developing the budget and the schedule for work.

For this study, the existing plan of Medan Ikan Bakar project has been analysed and it has been identified that the project is delayed. Based on the tabulated graph below, the percentage of actual progress is slightly higher than the percentage of planned for the first seven months of the project. Unfortunately, the project begins to slow down on the ninth month of the project which is during October. On January 2016 where the project supposed to be completed, the percentage of actual progress only reaches 89%, while it is supposed to be 100% completed within the period. This required extension of time in order to finish up the project.

Table 4.2 Percentage of work progress of planned and actual of Medan Ikan Bakar project

| Month | Feb-15 | Mar-15 | Apr-15 | May-15 | Jun-15 | Jul-15 | Aug-15 | Sep-15 | Oct-15 | Nov-15 | Dec-15 | Jan-16 |
|-------------|------------|-----------|------------|------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|
| Monthly | 558,382.50 | 1,240,850 | 1,985,360 | 2,729,870 | 3,288,252.50 | 3,846,635 | 4,405,017.50 | 4,901,357.50 | 5,397,697.50 | 5,956,080 | 6,142,207.50 | 6,204,250 |
| Cumulative | 0 | 0 | 801,580.69 | 801,580.69 | 1,687,695.22 | 2,094,060.25 | 2,094,060.25 | 2,773,509.10 | 3,450,109.40 | 3,450,109.40 | 3,450,109.40 | 4,044,762.05 |
| Planned (%) | 9 | 20 | 32 | 44 | 53 | 62 | 71 | 77 | 85 | 96 | 98 | 100 |
| Actual (%) | 17 | 30 | 42 | 55 | 61 | 63 | 72 | 77 | 83 | 85 | 88 | 89 |



Figure 4.2 Percentage of work progress of planned and actual of Medan Ikan Bakar project

This situation can be related to the weather condition in Malaysia where the average number of rainy days is slightly higher during the end of the year. Besides, the number of public holidays may also affect the duration to execute the construction work. This can be related where the effective planning is very important in project management to produce the effective number of working days. This initiative is to ensure that the users may not face the lost in the term of the operation of the building where the completed project is beyond the expected date.

Hence, the reschedule plan of Medan Ikan Bakar project has been made to produce the effecting planning with the effective number of working days without having the extension of time. The existing plan and reschedule plan are tabulated in the table according to the tasks as follows:

Table 4.3 Medan Ikan Bakar project

| No | Task | Existing – | Reschedule – |
|----|----------------------------------|------------|--------------|
| | | Duration | Duration |
| | | (days) | (days) |
| 1 | Membina dan Menyiapkan Sebuah | | |
| | Pusat Pembangunan Anjung Makanan | 240 days | 252 days |
| | Laut Dan Kompleks | | |
| 2 | Start | 0 days | 1 day |
| 3 | Mobilisation On Site | 3 days | 3 days |
| 4 | Water & Power Temporary Supply | 28 days | 28 days |
| 5 | Site Office Set-Up | 28 days | 28 days |
| 6 | Surveying Work | 14 days | 14 days |
| 7 | Site Preparation & Earthwork | 56 days | 56 days |
| 8 | Clear The Site | 14 days | 14 days |
| 9 | Imported Earth / Sand Zone A | 14 days | 14 days |
| 10 | Imported Earth / Sand Zone B | 28 days | 28 days |
| 11 | External Work 1 | 14 days | 14 days |
| 12 | Wash Through/Silt Trap | 14 days | 14 days |
| 13 | Water Tank 200 Gallon | 14 days | 14 days |
| 14 | External Work 2 | 123 days | 127 days |
| 15 | Temporary Paving | 14 days | 14 days |
| 16 | Gabion Wall | 115 days | 119 days |

Table 4.4 Kompleks Hasil Laut

| | Table 4.4 Rompleks 1. | | |
|-----------|---------------------------------|------------|-----------------|
| No | Task | Existing – | Reschedule – |
| | | Duration | Duration |
| - | | (days) | (days) |
| 17 | Building Work | 313 days | 192 days |
| | KOMPLEKS HASIL I | LAUT | |
| 18 | Kompleks Hasil Laut | 112 days | 113 days |
| 19 | Preparation On Site | 1 day | 1 day |
| 20 | Setting Out | 1 day | 1 day |
| 21 | Work Below Floor Level | 9 days | 9 days |
| 22 | Column Stump | 9 days | 9 days |
| 23 | Re-bar | 2 days | 2 days |
| 24 | Formwork | 2 days | 2 days |
| 25 | Concreting | 2 days | 2 days |
| 26 | Striking Formwork | 3 days | 3 days |
| 27 | Backfilling | 1 day | 1 day |
| 28 | Ground Floor Slab & Ground Beam | 24 days | 24 days |
| 29 | Ground Beam | 15 days | 15 days |
| 30 | Excavation | 1 day | 1 day |
| 31 | Lean Concrete | 3 days | 3 days |
| 32 | Formwork | 3 days | 3 days |
| 33 | Re-bar | 2 days | 2 days |
| 34 | Concreting | 2 days | 2 days |
| 35 | Striking Formwork | 3 days | 3 days |
| 36 | Backfilling | 1 day | 1 day |
| 37 | Ground Slab | 10 days | 10 days |
| 38 | Termite Treatment | 2 days | 2 days |
| 39 | DPM Sheet | 1 day | 1 day |
| 40 | BRC | 2 days | 2 days |
| 41 | Formwork | 2 days | 2 days |
| 42 | Concreting | 1 day | 1 day |
| 43 | Striking Formwork | 3 days | 3 days |
| 44 | GF Column | 9 days | 9 days |
| 45 | Re-bar | 3 days | 3 days |
| 46 | Formwork | 3 days | 3 days |
| 47 | Concreting | 1 day | 1 day |
| 48 | Striking Formwork | 2 days | 2 days |
| 49 | Roof Beam & Slab | 43 days | 43 days |
| 50 | Formwork | 14 days | 14 days |
| 51 | Re-bar | 4 days | 4 days |
| 52 | Concreting | 1 day | 1 day |
| 53 | Striking Formwork | 3 days | 3 days |
| 54 | Roof | 21 days | 21 days |
| 55 | R.C Slab & Roof Truss System | 14 days | 14 days |
| 56 | Clay Roof Tile | 7 days | 7 days |
| 57 | Brick Work And Partition | 10 days | 10 days |
| 58 | External Wall (Ground Floor) | 10 days | 10 days |
| 59 | Internal Wall (Ground Floor) | 10 days | 10 days |
| 60 | Window, Door & Ironmongeries | 42 days | 43 days |
| 61 | Windows | 3 days | 3 days |
| | | • | • |

| 62 | Outer Frame | 3 days | 3 days |
|-----------|---------------------------|---------|---------|
| 63 | Inner Frame & Glass Panel | 3 days | 3 days |
| 64 | Doors | 3 days | 3 days |
| 65 | M.S Steel | 3 days | 3 days |
| 66 | Door Frame | 3 days | 3 days |
| 67 | Door Leaf | 3 days | 3 days |
| 68 | Internal Wall | 28 days | 29 days |
| 69 | Plastering | 14 days | 14 days |
| 70 | Tiling Work | 14 days | 14 days |
| 71 | Painting Work | 14 days | 15 days |
| 72 | Pebble Work | 7 days | 7 days |
| 73 | Internal Floor | 14 days | 14 days |
| 74 | Rendering | 2 days | 2 days |
| 75 | Tiling Work | 14 days | 14 days |
| 76 | Internal Ceiling | 7 days | 7 days |
| 77 | External Finishing | 14 days | 14 days |
| 78 | Plastering | 14 days | 14 days |
| 79 | Tiling Work | 14 days | 14 days |
| 80 | Ceiling Finishing | 7 days | 7 days |
| 81 | Plumbing Work | 7 days | 8 days |
| 82 | Electrical Work | 7 days | 8 days |
| 83 | Mechanical Work | 7 days | 8 days |
| 84 | Sanitary Fitting | 7 days | 8 days |
| 85 | Apron | 7 days | 8 days |

Table 4.5 Restoran Ikan Bakar

| No | Task | Existing – | Reschedule – | | | | | |
|-----|--|------------|--------------|--|--|--|--|--|
| | | Duration | Duration | | | | | |
| | | (days) | (days) | | | | | |
| | RESTORAN IKAN BAKAR | | | | | | | |
| 86 | Restoran Ikan Bakar | 204 days | 145 days | | | | | |
| 87 | Preparation On Site | 1 day | 1 day | | | | | |
| 88 | Setting Out | 1 day | 1 day | | | | | |
| 89 | Work Below Floor Level | 10 days | 10 days | | | | | |
| 90 | Column Stump | 10 days | 10 days | | | | | |
| 91 | Re-bar | 2 days | 2 days | | | | | |
| 92 | Formwork | 2 days | 2 days | | | | | |
| 93 | Concreting | 2 days | 2 days | | | | | |
| 94 | Striking Formwork | 3 days | 3 days | | | | | |
| 95 | Backfilling | 1 day | 1 day | | | | | |
| 96 | Ground Floor Slab & Ground Beam | 0 days | 26 days | | | | | |
| 97 | Ground Beam | 15 days | 15 days | | | | | |
| 98 | Excavation | 1 day | 1 day | | | | | |
| 99 | Lean Concrete | 3 days | 3 days | | | | | |
| 100 | Formwork | 3 days | 3 days | | | | | |
| 101 | Re-bar | 2 days | 2 days | | | | | |
| 102 | Concreting | 2 days | 2 days | | | | | |
| 103 | Striking Formwork | 3 days | 3 days | | | | | |
| | | | | | | | | |

| 104 | Backfilling | 1 day | 1 day |
|-----|---------------------------------|----------|---------|
| 105 | Ground Slab | 11 days | 12 days |
| 106 | Termite Treatment | 2 days | 2 days |
| 107 | DPM Sheet | 1 day | 2 days |
| 108 | BRC | 2 days | 2 days |
| 109 | Formwork | 2 days | 2 days |
| 110 | Concreting | 1 day | 1 day |
| 111 | Striking Formwork | 3 days | 3 days |
| 112 | GF Column | 9 days | 9 days |
| 113 | Re-bar | 3 days | 3 days |
| 114 | Formwork | 3 days | 3 days |
| 115 | Concreting | 1 day | 1 day |
| 116 | Striking Formwork | 2 days | 2 days |
| 117 | Roof Beam & Slab | 196 days | 45 days |
| 118 | Formwork | 14 days | 14 days |
| 119 | Re-bar | 4 days | 4 days |
| 120 | Concreting | 1 day | 1 day |
| 121 | Striking Formwork | 3 days | 3 days |
| 122 | Roof | 0 days | 23 days |
| 123 | R.C Slab & Roof Truss System | 14 days | 14 days |
| 124 | Clay Roof Tile | 7 days | 9 days |
| 125 | Brick Work And Partition | 0 days | 11 days |
| 126 | External Wall (Ground Floor) | 10 days | 11 days |
| 127 | Internal Wall (Ground Floor) | 10 days | 11 days |
| 128 | Window, Door & Ironmongeries | 0 days | 44 days |
| 129 | Windows | 0 days | 4 days |
| 130 | Outer Frame | 3 days | 4 days |
| 131 | Inner Frame & Glass Panel | 3 days | 4 days |
| 132 | Doors | 0 days | 4 days |
| 133 | Door Frame | 3 days | 4 days |
| 134 | Door Leaf | 3 days | 4 days |
| 135 | Internal Wall | 0 days | 16 days |
| 136 | Plastering | 14 days | 16 days |
| 137 | Cement Render | 7 days | 7 days |
| 138 | Painting Work | 14 days | 16 days |
| 139 | Internal Floor | 0 days | 14 days |
| 140 | Rendering | 7 days | 7 days |
| 141 | Tiling Work | 14 days | 14 days |
| 142 | Roof Truss Painting | 7 days | 10 days |
| 143 | Wet Kitchen Painting | 7 days | 10 days |
| 144 | External Finishing | 14 days | 16 days |
| 145 | Plastering | 14 days | 16 days |
| 146 | Timber Treatment | 14 days | 16 days |
| 147 | Plumbing Work | 7 days | 10 days |
| 148 | Electrical Work | 7 days | 10 days |
| 149 | Mechanical Work | 7 days | 10 days |

Table 4.6 Gerai Hasil Laut

| 150 151 152 153 154 155 156 157 | GERAI HASIL LAU Gerai Hasil Laut Preparation On Site Setting Out Work Below Floor Level Column Stump Re-bar Formwork | 79 days 1 day 1 day 8 days 8 days | Reschedule – Duration (days) 89 days 1 day 1 day 8 days |
|--|--|--|--|
| 151 152 153 154 155 156 | Gerai Hasil Laut Preparation On Site Setting Out Work Below Floor Level Column Stump Re-bar | (days) JT 79 days 1 day 1 day 8 days 8 days | (days) 89 days 1 day 1 day |
| 151 152 153 154 155 156 | Gerai Hasil Laut Preparation On Site Setting Out Work Below Floor Level Column Stump Re-bar | 79 days 1 day 1 day 8 days 8 days | 89 days 1 day 1 day |
| 151 152 153 154 155 156 | Gerai Hasil Laut Preparation On Site Setting Out Work Below Floor Level Column Stump Re-bar | 79 days 1 day 1 day 8 days 8 days | 1 day 1 day |
| 151 152 153 154 155 156 | Preparation On Site Setting Out Work Below Floor Level Column Stump Re-bar | 1 day 1 day 8 days 8 days | 1 day 1 day |
| 152 153 154 155 156 | Setting Out Work Below Floor Level Column Stump Re-bar | 1 day 8 days 8 days | 1 day |
| 153 154 155 156 | Work Below Floor Level Column Stump Re-bar | 8 days 8 days | • |
| 154 155 156 | Column Stump Re-bar | 8 days | 0 444 |
| 155 156 | Re-bar | • | 8 days |
| 156 | Formwork | 2 days | 2 days |
| | | 2 days | 2 days |
| 137 | Concreting | 1 day | 1 day |
| 158 | Striking Formwork | 2 days | 2 days |
| 159 | Backfilling | 1 day | 1 day |
| 160 | Ground Floor Slab & Ground Beam | 21 days | 22 days |
| 161 | Ground Beam | 10 days | 10 days |
| 162 | Excavation | 1 day | 1 day |
| 163 | Lean Concrete | 1 day | 1 day |
| 164 | Formwork | 2 days | 2 days |
| 165 | Re-bar | 2 days | 2 days |
| 166 | Concreting | 1 day | 1 day |
| 167 | Striking Formwork | 2 days | 2 days |
| 168 | Backfilling | 1 day | 1 day |
| 169 | Ground Slab | 12 days | 13 days |
| 170 | Termite Treatment | 1 day | 1 day |
| 171 | DPM Sheet | 1 day | 1 day |
| 172 | BRC | 2 days | 2 days |
| 173 | Formwork | 2 days | 2 days |
| 174 | Concreting | 1 day | 1 day |
| 175 | Striking Formwork | 2 days | 2 days |
| 176 | Apron | 3 days | 4 days |
| 177 | GF Column | 8 days | 8 days |
| 178 | Re-bar | 2 days | 2 days |
| 179 | Formwork | 2 days | 2 days |
| 180 | Concreting | 1 day | 1 day |
| 181 | Striking Formwork | 3 days | 3 days |
| 182 | Roof Beam & Slab | 27 days | 27 days |
| 183 | Formwork | 7 days | 7 days |
| 184 | Re-bar | 2 days | 2 days |
| 185 | Concreting | 1 day | 1 day |
| 186 | Striking Formwork | 3 days | 3 days |
| 187 | Roof | 14 days | 14 days |
| 188 | R.C Slab & Roof Truss System | 7 days | 7 days |
| 189 | Clay Roof Tile | 7 days | 7 days |
| 190 | Brick Work And Partition | 7 days | 7 days |
| 191 | External Wall (Ground Floor) | 7 days | 7 days |
| 192 | Internal Wall (Ground Floor) | 7 days | 7 days |
| 193 | Window, Door & Ironmongeries | 21 days | 30 days |
| 194 | Windows | 3 days | 3 days |

| 195 | Outer Frame | 3 days | 3 days |
|------------|------------------------------|---------|---------|
| 196 | Inner Frame & Glass Panel | 3 days | 3 days |
| 197 | Doors | 3 days | 3 days |
| 198 | Roller Shutter | 3 days | 3 days |
| 199 | Door Frame | 3 days | 3 days |
| 200 | Door Leaf | 3 days | 3 days |
| 201 | Internal Wall | 14 days | 23 days |
| 202 | Plastering | 7 days | 7 days |
| 203 | Tiling Work | 7 days | 7 days |
| 204 | Painting Work | 7 days | 9 days |
| 205 | Internal Floor | 7 days | 9 days |
| 206 | Rendering | 1 day | 1 day |
| 207 | Tiling Work | 7 days | 9 days |
| 208 | Internal Ceiling | 3 days | 3 days |
| 209 | External Finishing | 1 day | 1 day |
| 210 | Plastering | 1 day | 1 day |
| 211 | Cement Render | 1 day | 1 day |
| 212 | Pebble Work | 1 day | 1 day |
| 213 | Tiling Work | 1 day | 1 day |
| 214 | Ceiling Finishing | 1 day | 1 day |
| 215 | Plumbing Work | 7 days | 10 days |
| 216 | Electrical Works | 7 days | 10 days |
| 217 | Mechanical Works | 7 days | 10 days |
| 218 | Builder's Work In Connection | 1 day | 1 day |
| 219 | Apron | 7 days | 7 days |

Table 4.7 Public Toilet

| No | Task | Existing – | Reschedule – | |
|---------------|---------------------------------|------------|--------------|--|
| | | Duration | Duration | |
| | | (days) | (days) | |
| PUBLIC TOILET | | | | |
| 220 | Public Toilet | 114 days | 116 days | |
| 221 | Preparation On Site | 1 day | 1 day | |
| 222 | Setting Out | 1 day | 1 day | |
| 223 | Work Below Floor Level | 9 days | 9 days | |
| 224 | Column Stump | 9 days | 9 days | |
| 225 | Re-bar | 2 days | 2 days | |
| 226 | Formwork | 2 days | 2 days | |
| 227 | Concreting | 1 day | 1 day | |
| 228 | Striking Formwork | 3 days | 3 days | |
| 229 | Backfilling | 1 day | 1 day | |
| 230 | Ground Floor Slab & Ground Beam | 28 days | 30 days | |
| 231 | Ground Beam | 11 days | 11 days | |
| 232 | Excavation | 1 day | 1 day | |
| 233 | Lean Concrete | 1 day | 1 day | |
| 234 | Formwork | 2 days | 2 days | |
| 235 | Re-bar | 2 days | 2 days | |

| 236 | Concreting | 1 day | 1 day |
|---------|------------------------------|---------|---------|
| 237 | Striking Formwork | 3 days | 3 days |
| 238 | Backfilling | 1 day | 1 day |
| 239 | Ground Slab | 18 days | 20 days |
| 240 | Termite Treatment | 1 day | 1 day |
| 241 | DPM Sheet | 1 day | 1 day |
| 242 | BRC | 2 days | 2 days |
| 243 | Formwork | 3 days | 3 days |
| 244 | Concreting | 1 day | 1 day |
| 245 | Striking Formwork | 3 days | 3 days |
| 246 | Apron | 7 days | 9 days |
| 247 | GF Column | 9 days | 9 days |
| 248 | Re-bar | 2 days | 2 days |
| 249 | Formwork | 3 days | 3 days |
| 250 | Concreting | 1 day | 1 day |
| 251 | Striking Formwork | 3 days | 3 days |
| 252 | Roof Beam & Slab | 42 days | 42 days |
| 253 | Formwork | 14 days | 14 days |
| 254 | Re-bar | 3 days | 3 days |
| 255 | Concreting | 1 day | 1 day |
| 256 | Striking Formwork | 3 days | 3 days |
| 257 | Roof | 21 days | 21 days |
| 258 | R.C Slab & Roof Truss System | 14 days | 14 days |
| 259 | Clay Roof Tile | 7 days | 7 days |
| 260 | Brick Work And Partition | 14 days | 14 days |
| 261 | External Wall (Ground Floor) | 14 days | 14 days |
| 262 | Internal Wall (Ground Floor) | 14 days | 14 days |
| 263 | Window, Door & Ironmongeries | 45 days | 45 days |
| 264 | Doors | 3 days | 3 days |
| 265 | Door Frame | 3 days | 3 days |
| 266 | Door Leaf | 3 days | 3 days |
| 267 | Internal Wall | 28 days | 28 days |
| 268 | Plastering | 14 days | 14 days |
| 269 | Tiling Work | 14 days | 14 days |
| 270 | Painting Work | 7 days | 7 days |
| 271 | Internal Floor | 7 days | 7 days |
| 272 | Rendering | 2 days | 2 days |
| 273 | Tiling Work | 7 days | 7 days |
| 274 | Internal Ceiling | 7 days | 7 days |
| 275 | External Finishing | 14 days | 14 days |
| 276 | Plastering | 14 days | 14 days |
| 277 | Cement Render | 1 day | 1 day |
| 278 | Pebble Work | 7 days | 8 days |
| 279 | Tiling Work | 7 days | 8 days |
| 280 | Ceiling Finishing | 7 days | 8 days |
| 281 | Pl2umbing Work | 7 days | 10 days |
| 282 | Electrical Works | 7 days | 10 days |
| 283 | Mechanical Works | 7 days | 10 days |
| 284 | Sanitary Fitting | 7 days | 10 days |
| <u></u> | Samuely 1 ming | , augo | 10 days |

Table 4.8 Surau (Musholla)

| No | Task | Existing – | Reschedule – |
|-----|---------------------------------|------------|--------------|
| 110 | A 400A | Duration | Duration |
| | | (days) | (days) |
| | SURAU (MUSHOLI | | (dujs) |
| 285 | Surau (Musholla) | 91 days | 106 days |
| 286 | Preparation On Site | 1 day | 1 day |
| 287 | Setting Out | 1 day | 1 day |
| 288 | Work Below Floor Level | 10 days | 10 days |
| 289 | Column Stump | 10 days | 10 days |
| 290 | Re-bar | 2 days | 2 days |
| 291 | Formwork | 3 days | 3 days |
| 292 | Concreting | 1 day | 1 day |
| 293 | Striking Formwork | 3 days | 3 days |
| 294 | Backfilling | 1 day | 1 day |
| 295 | Ground Floor Slab & Ground Beam | 28 days | 29 days |
| 296 | Ground Beam | 12 days | 12 days |
| 297 | Excavation | 1 day | 1 day |
| 298 | Lean Concrete | 1 day | 1 day |
| 299 | Formwork | 3 days | 3 days |
| 300 | Re-bar | 2 days | 2 days |
| 301 | Concreting | 1 day | 1 day |
| 302 | Striking Formwork | 3 days | 3 days |
| 303 | Backfilling | 1 day | 1 day |
| 304 | Ground Slab | 17 days | 18 days |
| 305 | Termite Treatment | 1 day | 1 day |
| 306 | DPM Sheet | 1 day | 1 day |
| 307 | BRC | 2 days | 2 days |
| 308 | Formwork | 2 days | 2 days |
| 309 | Concreting | 1 day | 1 day |
| 310 | Striking Formwork | 3 days | 3 days |
| 311 | Apron | 7 days | 8 days |
| 312 | GF Column | 9 days | 9 days |
| 313 | Re-bar | 2 days | 2 days |
| 314 | Formwork | 3 days | 3 days |
| 315 | Concreting | 1 day | 1 day |
| 316 | Striking Formwork | 3 days | 3 days |
| 317 | Roof Beam & Slab | 35 days | 35 days |
| 318 | Formwork | 7 days | 7 days |
| 319 | Re-bar | 3 days | 3 days |
| 320 | Concreting | 1 day | 1 day |
| 321 | Striking Formwork | 3 days | 3 days |
| 322 | Roof | 21 days | 21 days |
| 323 | R.C Slab & Roof Truss System | 14 days | 14 days |
| 324 | Clay Roof Tile | 7 days | 7 days |
| 325 | Brick Work And Partition | 7 days | 7 days |
| 326 | External Wall (Ground Floor) | 7 days | 7 days |
| 327 | Internal Wall (Ground Floor) | 7 days | 7 days |
| 328 | Window, Door & Ironmongeries | 35 days | 29 days |
| | , | | |

| 330 | Outer Frame | 3 days | 3 days |
|-----|--------------------------------|---------|---------|
| 331 | Inner Frame & Glass Panel | 3 days | 3 days |
| 332 | Doors | 1 day | 1 day |
| 333 | Door Frame | 1 day | 1 day |
| 334 | Door Leaf | 1 day | 1 day |
| 335 | Internal Floor Finishes | 21 days | 21 days |
| 336 | Plastering | 14 days | 14 days |
| 337 | Tiling Work | 7 days | 7 days |
| 338 | Painting Work | 7 days | 7 days |
| 339 | Internal Floor Finishes | 8 days | 8 days |
| 340 | Rendering | 1 day | 1 day |
| 341 | Tiling Work | 7 days | 7 days |
| 342 | Internal Ceiling | 7 days | 7 days |
| 343 | External Finishing | 28 days | 28 days |
| 344 | Plastering | 14 days | 14 days |
| 345 | Tiling Work | 7 days | 7 days |
| 346 | Ceiling Finishing | 7 days | 7 days |
| 347 | Plumbing Work | 7 days | 10 days |
| 348 | Electrical Works | 7 days | 10 days |
| 349 | Mechanical Works | 7 days | 10 days |

Table 4.9 External Works

| No | Task | Existing – | Reschedule – | | |
|----------------|----------------------------|------------|-----------------|--|--|
| | | Duration | Duration | | |
| | | (days) | (days) | | |
| EXTERNAL WORKS | | | | | |
| 350 | External Works | 135 days | 162 days | | |
| 351 | Surface Water Drainage | 116 days | 147 days | | |
| 352 | Drain, Box Concrete | 60 days | 70 days | | |
| 353 | 900mm x 1000mm | 60 days | 70 days | | |
| 354 | 900mm x 900mm | 60 days | 70 days | | |
| 355 | Others | 90 days | 90 days | | |
| 356 | Roadworks & Pavements | 45 days | 51 days | | |
| 357 | Interlocking | 21 days | 24 days | | |
| 358 | Roadworks | 30 days | 33 days | | |
| 359 | Road Furniture | 15 days | 18 days | | |
| 360 | Water Reticulation | 44 days | 47 days | | |
| 361 | Pipe line | 30 days | 33 days | | |
| 362 | Pipe Fittings | 30 days | 33 days | | |
| 363 | JBA - Meter Speed | 14 days | 14 days | | |
| 364 | Sewerage (Septic Tank) | 14 days | 14 days | | |
| 365 | Fencing & Railings | 21 days | 21 days | | |
| 366 | Fencing | 21 days | 21 days | | |
| 367 | Railing | 21 days | 21 days | | |
| 368 | Electrical Services | 40 days | 40 days | | |
| 369 | LV Cable | 40 days | 40 days | | |
| 370 | Compound Lighting | 40 days | 40 days | | |
| 371 | TESTING AND COMMISIONING | 20 days | 20 days | | |

| 372 | FINAL INSPECTION | 1 day | 1 day |
|-----|------------------|-------|-------|
| 373 | HANDING OVER | 1 day | 1 day |

This Medan Ikan Bakar project is rescheduled based on the factors that affects the duration estimation process which are the number of rainy days and public holidays to produce the effective working days. From the table, it can be seen that the total duration of reschedule plan is 12 days longer than the existing plan. This is because some of the tasks in the existing plan are not considering the public holidays for instance National Day and Malaysia Day. Hence, the rearrange of the duration of work progress has to be made to ensure that the task could be completed according to the plan without delay occur. Besides, it can be seen that the project starts to slow down at the end of the year, which is during the rainy season or monsoon season that occur on the eastern side of the peninsula.

By considering the public holidays and the number of rainy days, the effective number of working days is be produced and the extension of time to construct the work progression is avoided. Furthermore, the operation of the Medan Ikan Bakar project also could be used on time right after completion of the project, and at the same time the losses of the client due to the late completion and operation of the project could be avoided.

4.4 Duration Estimation Process

The duration estimation process is the activity duration estimating to quantify the amount of time that is required for the activity will take to complete. The duration estimation process is needed to be done before the project takes place and the right duration estimation is important so that there is no extension of time required to finish up the project. Therefore, accurately estimating that activity's duration is required to describe its different aspects and the effect of each one on the activity's length.

4.4.1 Tasks of Gerai Hasil Laut




Figure 4.4 Existing plan of Gerai Hasil Laut




Figure 4.5 Reschedule plan of Gerai Hasil Laut

The figures above are showing the duration of the Plumbing Work, Electrical Work and Mechanical Work under the construction of the Gerai Hasil Laut. Based on the existing schedule, the project cannot be completed according to the plan where the percentage of work completed is still not achieve 100%. It is clearly proven that the tasks are dragging out and will cause the project to delay. In order to improve and produce the

better planning, the duration of work progression should be incressed from 7 days to 10 days, so that there is no delay occuring in the project and at the same time the tasks can be completed within the time given and also according to the plan.

For the reschedule of the project, 3 days are added to the duration of these three work tasks. According to the existing plan, the duration of the tasks to be completed is not enough. This is because there are public holidays during the duration given in those work progression which is the Hari Raya Haji that occurred on 24th and 25th of September 2015. The construction work couldn't be proceeded during public holiday and for sure will affect the work progression of the project. In this case, extra days need to be added for the duration of the work to ensure enough time is given to the workers to complete the tasks. By including the public holidays, 10 days of work duration are given to complete these Plumbing, Electrical and Mechanical Work.

4.4.2 Tasks of Public Toilet




Figure 4.6 Existing plan of Public Toilet




Figure 4.7 Reschedule plan of Public Toilet

The figures above are representing the duration of Plumbing Work, Electrical Work, Mechanical Work and Sanitary Fitting for the construction of the Public Toilet. Based on the existing schedule, the work cannot be completed according to the plan because the day provided to finish up the Public Toilet for the works mentioned is not enough. This is because the public holiday which is occurring on 14th October during the construction period is not counted. The construction work cannot be proceeded on 14th October due to the national public holiday which is Awal Muharram.

Hence, the extra 3 days are added for the duration of this construction work by considering the public holiday and also the number of rainy days. The number of rainy days needs to be counted and extra days must be added due to the high probability of number of rains at the end of the year. It has been calculated that the average number of rainy days during October is 9 days per month, which is high compared to the other month. So, the extra 2 days are added for this duration of work progression as the precaution and preparation in case the work progression cannot be proceed due to the rainy days.

4.4.3 Tasks of Surau

4.4.3.1 Ground floor column




Figure 4.8 Existing plan of Surau




Figure 4.9 Reschedule plan of Surau

The figures for existing and reschedule of Medan Ikan Bakar Project planning above are showing the striking formwork of ground floor column for the construction of

Surau. On the existing schedule, it is shown that the working days to conduct the striking formwork are including the public holiday which is on 31st August, the Malaysia National Day. So, the reschedule and proper planning need to be done to ensure that the enough number of days is provided to execute the work.

4.4.3.2 Roof beam and slab




Figure 4.10 Existing plan of Surau




Figure 4.11 Reschedule plan of Surau

The figures above are showing the plan for work execution of Surau where the duration needed to conduct work task of striking formwork for roof beam and slab are three days. From the existing plan, it is shown that the duration to complete the striking formwork is including the national public holiday where 16th September is the public holiday for Malaysia which is Malaysia Day. In this case, the right and proper planning must be executed so that the work task could be completed according to the plan.

The error of project planning could affect the duration of time to finish up the project. Hence, the extension of time for the project could occur. It is very important to have the right planning by considering the number of rainy days and public holidays in Malaysia to avoid the unforeseen circumstances that may occur.

4.5 Summary of the chapter

In this study, the analysis regarding to the existing plan of Medan Ikan Bakar project has been done. From the analysis, it has been identified that the project is facing delay where the extension of time is required to finish the project. Hence, the reschedule of the project has been produced to obtain the effective working days for the project.

The two factors that may affect the duration of the estimation process for the project planning is being considered for this reschedule plan which are the number of rainy days and public holidays. Therefore, the reschedule plan is produced and the result is tabulated in the table and figure by comparing the existing plan and the reschedule plan with associated explanation. The rescheduled plan with effective number of working days is produced. Hence, all the aim and objectives for this study were achieved.

CHAPTER 5

CONCLUSION AND RECOMMENDATION

5.1 Introduction

In this study with the intention of obtaining result related, there are literature study and case study involved. After the data is being analysed, the assessment result was made. The main aim of this research focuses on assessment of construction planning of new project. From the main aim, there are two highlighted in producing the construction planning of new project according to the specific objectives and the objectives of this study are:

- i. To determine the typical number of rainy days and the public holidays.
- ii. To identify the effective number of days in construction planning.

In this study, the analysation of the existing plan of Medan Ikan Bakar project has been done. The extension of time of the project has been identified during the work execution progress where it causes the delay in the project completion. After that, the existing plan of Medan Ikan Bakar project is rescheduled by considering the number of rainy days and the number of public holidays to produce the effective working days. The plan finally being rescheduled and the results are presented in tables and figures with associated explanation. Recommendation for better future study also will be discuss in this chapter.

5.2 Conclusion

In construction projects, project planning is an important process to ensure that the buildings perform according to the design and to the owner's operational requirements. Construction projects are always changing, and the uncertainty can often bring conflict to project terms. This is the reasons why doing the project planning is crucial where the goals is to complete the project within the time and cost, while maintaining quality for the success of projects.

Based on the aim and objectives for this study as explained in chapter 1, there are several conclusion has been made. The results of this study indicate that from the case study, there are delay occurred in the existing on Medan Ikan Bakar project. The project is going smoothly for the first seven months where the percentage of actual progress is slightly higher than the percentage of planned. The project begins to slow down on the ninth month of the project which is during October. The project is supposed to be completed on January 2016 but the extension of time is required due to the uncompleted of work progression where the percentage of work completed is only 89% instead of 100%. We can relate this delay with these two main factors that we are considering for this study, which are the number of rainy days and public holidays.

As we know in Malaysia, we are facing two monsoon winds seasons and for this project, the project happens to slow down at October which is during the Northeast Monsoon. Weather condition for sure will affect the duration of the construction project where the construction work cannot be proceeded or put on hold due to the heavy rain for instance. Besides, the number of public holidays also causing the project to delay. The Medan Ikan Bakar project happens to face delays because some of the public holidays were not included in the project plan. Hence, the extension of time required when the public holidays are not considered in project planning because work cannot be proceeded due to unavailability of workers during public holidays.

Therefore, the reschedule of Medan Ikan Bakar project has been made with the objectives of determining the typical number of rainy days and the public holidays, and producing the effective number of days in construction planning. These objectives are achieved by considering the two important factors which are the rainy days and public holidays. The duration of existing plan and reschedule plan of Medan Ikan Bakar project are tabulated as follows:

Table 5.2 The duration of existing plan and reshedule plan of Medan Ikan Bakar project

| No | Task | Existing – Duration (days) | Reschedule – Duration (days) |
|----|-------------------------------------|----------------------------------|------------------------------------|
| 1 | Membina dan Menyiapkan Sebuah Pusat | | |
| | Pembangunan Anjung Makanan Laut Dan | 240 days | 252 days |
| | Kompleks | | |
| 2 | Kompleks Hasil Laut | 112 days | 113 days |
| 3 | Restoran Ikan Bakar | 204 days | 145 days |
| 4 | Gerai Hasil Laut | 79 days | 89 days |
| 5 | Public Toilet | 114 days | 116 days |
| 6 | Surau (Musholla) | 91 days | 106 days |
| 7 | External Works | 135 days | 162 days |

From the table, it can be seen that the total duration of reschedule plan is 12 days longer than the existing plan. This reschedule plan is produced after considering the two important factors in this study. By considering these two factors of delay in project, the typical number of rainy days and the public holidays are determined and the effective number of days in construction planning are produced. Therefore, the extension of time to complete the work progression is avoided where the delay will not occur and the client may not face losses due to the operation of the building that could be proceeded according to the initial plan. From this study, the consultant and also the project owner could use this outcome as a guide to do the project planning. Hence, the good performance of construction work is produced in the mean of time, cost and quality of the project.

5.3 Recommendation

This study, while specifically concentrated on the case study project, is only limited to this where the only factors that being considered in this planning are the number of rainy days and public holidays. Based on findings, several recommendations could be made in order to obtain a better understanding in construction project planning that being practiced nowadays. However, regarding to this study, there are some improvements that could be done in order to obtain better result for future study. For further study, it is suggested that a recommendation to improve the result is by considering the other factors that causes delay in the project. The other factors that may lead to delay in construction projects are tabulated in table as follows:

Table 5.2 Factors of delay in project

| No | Factors of delay in project | Critical | Not |
|----|--|-----------|-----------|
| | | | critical |
| 1 | General | | |
| | 1.5 Weather | $\sqrt{}$ | - |
| | 1.6 Poor planning of work execution | $\sqrt{}$ | - |
| | 1.7 Poor facilities at construction site | - | $\sqrt{}$ |
| | 1.8 Natural disaster | - | $\sqrt{}$ |
| 2 | Lack of Labours | | |
| | 2.1 Professional management | $\sqrt{}$ | - |
| | 2.2 Skilled workers | $\sqrt{}$ | - |
| | 2.3 General workers | $\sqrt{}$ | $\sqrt{}$ |
| 3 | Material Sources | | |
| | 3.1 Lack of construction building materials | $\sqrt{}$ | - |
| | 3.2 Increase in material price | $\sqrt{}$ | - |
| 4 | Source of Income | | |
| | 4.1 Lack of budget | $\sqrt{}$ | - |
| | 4.2 Delay of payment from contractor to sub- | $\sqrt{}$ | - |
| | contractor | | |
| | 4.3 Problem with bank loan | - | - |
| 5 | Client Needs | | |
| | 5.1 Changing scope of design | $\sqrt{}$ | - |
| | 5.2 Changing design and structure that been | $\sqrt{}$ | - |
| | constructed | | |
| | 5.3 Delay in approving the changes in works | - | $\sqrt{}$ |
| 6 | Machinery Sources | | |
| | 6.1 Shortage of machineries | - | $\sqrt{}$ |
| | 6.2 Defective machineries | - | $\sqrt{}$ |
| | Source: Idris (2006) | | |

Source: Idris (2006).

Factors of delay in project that are categorized as critical should be considered for future study in construction planning. This can be seen, for instance the weather, lack of labours, material sources and source of income are contributed as critical for the delay

happens in construction project. Hence, the proper project planning in construction is crucial to produce the effective working days and effective planning so that there is no extension of time required to finish up the project. The good performance in construction projects in the mean of time, cost and quality could be produced for future study by considering the factors of delay that occurred in construction.

REFERENCES

- GAJEWSKA, E., & ROPEL, M. (2011). Risk Management Practices in a Construction Project a Case Study, 13-18.
- MISRAN, N. (2012). PENENTU KEPIMPINAN BERORIENTASIKAN PEKERJA DAN TUGAS TERHADAP KEJAYAAN PROJEK DI KALANGAN KONTRAKTOR BINAAN DI KUANTAN PAHANG, 20-21.
- JAMADI, M. A. (2012). FOREIGN LABOUR EMPLOYMENT IN CONSTRUCTION PROJECT.
- Ibrahim, H. (2012). OPTIMISING TIME PERFORMANCE FOR CONSTRUCTION OF PUBLIC BUILDING SECTOR PROJECTS IN PENINSULAR MALAYSIA. *Vol.1*(July), no.1.
- Euripides, R. A. (2008). TROUBLED PROJECTS IN CONSTRUCTIONS DUE TO INADEQUATE RISK MANAGEMENT.
- Onengiyeofori, O. O. (2016). RISK MANAGEMENT SYSTEM TO GUIDE BUILDING CONSTRUCTION PROJECTS' IN DEVELOPING COUNTRIES: A CASE STUDY OF NIGERIA, 39-51.
- Van Odeyinka, H. A, Oladapo, A. A. and Akindele, O. (2008): Assessing Risk Impacts on Construction Cost. Proceedings of the Annual Research; Conference of the Royal Institution of Chartered Surveyors, pp. 7-8
- Malaysia GDP From Construction | 2010-2018 | Data | Chart | Calendar. (n.d.). Retrieved from https://tradingeconomics.com/malaysia/gdp-from-construction
- Group, V. C. (2015, December 30). What is more important in projects Time, cost or quality? Retrieved December 13, 2017, from https://www.vectorconsulting.in/engineering-construction-insight/what-is-more-important-in-projects-time-cost-or-quality/
- LIM, I. (2013, December 2). After PWD delays, East Coast Highway cost balloons by RM800m. Malay Mail Online. Retrieved November 19, 2017, from http://www.themalaymailonline.com/malaysia/article/after-pwd-delays-east-coast-highway-cost-balloons-by-rm800m#5xxGDfXCxsmHQzjS.97

- Factors influencing the construction time of civil engineering projects in Malaysia. (n.d.). Retrieved from https://www.emeraldinsight.com/doi/full/10.1108/09699980610690756
- Weather History for WMKD. (2006, December). Retrieved October 12, 2017, from https://www.wunderground.com/history/airport/WMKD/2006/12/12/MonthlyCalendar. html?req_city=&req_state=&req_statename=&reqdb.zip=&reqdb.magic=&reqdb.wm=
- MALAYSIA COUNTRY REPORT (pp. 14-16, Rep. No. 8). (2009). Malaysia.
- Unit Penyelarasan Pelaksanaan Jabatan Perdana Menteri. (2009). MEMPERCEPATKAN PELAKSANAAN PROJEK PEMBANGUNAN RMK9. *I*(June).
- Muhamad Salleh, A. H., & Arul, J. J. (2008). *Projek Pembangunan RMKe-9 Kementerian Kerja Raya*, Vol.1(2008).
- Munns, A. K., & Bjeirmi, B. F. (2006). The role of project management in achieving project success. *Vol. 14*(No. 2), 81-87.
- Meng, X. (2012). The effect of relationship management on project performance in Hwang, B., & Ng, W. J. (2013). Project management knowledge and skills for green construction: Overcoming challenges. construction.
- Hwang, B., & Ng, W. J. (2013). Project management knowledge and skills for green construction: Overcoming challenges.
- Memon, A. H., Rahman, I. A., & Abdul Aziw, A. (2012). Time and Cost Perfomance in Costruction Projects in Southern and Central Regions of Penisular Malaysia. *Vol.1*(March), no.2, 45-52.
- Kikwasi, G.J. (2012) 'Causes and effects of delays and disruptions in construction projects in Tanzania', Australasian Journal of Construction Economics and Building, Conference Series, 1 (2) 52-59
- Ramanathan, C et al. (2012) 'Construction delays causing risks on time and cost a critical review', *Australasian Journal of Construction Economics and Building*, **12** (1) 37-57
- Yee Cheong Yong, Nur Emma Mustaffa, (2012) "Analysis of factors critical to construction project success in Malaysia", Engineering, Construction and Architectural Management, Vol. 19 Issue: 5, pp.543-556, https://doi.org/10.1108/09699981211259612

- Akinsiku, O. E., & Akinsulire, A. (2012). Stakeholders' Perception of the Causes and Effects of Construction Delays on Project Delivery.
- Rahman, I. A., Memon, A. H., & Abd. Karim, A. T. (2013). Significant Factors Causing Cost Overruns in Large Construction Projects in Malaysia. *13*, 2nd ser., 286-293.

APPENDIX A MICROSOFT PROJECT FOR EXISTING PLAN OF MEDAN IKAN BAKAR PROJECT

|) | 0 | Task Mode | Task Name | Duration | Start | Finish | | 21 January 18/1 22/3 | 1 June 24/5 26/7 | 11 October 27/9 29/11 | 21 February 31/1 3/4 | 1 J 5/6 |
|-------|----------|--------------|--|----------|-------------|-----------------------|---|-------------------------|---------------------|--------------------------|-------------------------|--------------|
| 1 | | * | Membina dan Menyiapkan Sebuah Pusat Pembangunan Anjung Makanan Laut Dan Kompleks Hasil Laut | | Mon 2/2/15 | Fri 1/1/16 | | | | | | |
| 2 | ✓ | -5 | Start | 0 days | Mon 2/2/15 | Mon 2/2/15 | | 2/2 | | | | |
| 3 | ✓ | -5 | Mobilisation On Sit | 3 days | Tue 3/2/15 | Thu 5/2/15 | | | | | | |
| 4 | V | -5 | Water & Power Temporary Supply | 28 days | Fri 6/2/15 | Tue 17/3/15 | | | | | | |
| 5 | V | -5 | Site Office Set-Up | 28 days | Fri 6/2/15 | Tue 17/3/15 | | | | | | |
| 6 | | -5 | Surveying Work | 14 days | Tue 10/2/15 | Fri 27/2/15 | | | | | | |
| 7 | | -5 | Site Preparation & Earthwork | 56 days | Wed 18/3/15 | Wed 3/6/15 | | | 1 | | | |
| 8 | ✓ | -5 | Clear The Site | 14 days | Wed 18/3/15 | Mon 6/4/15 | | Tur | | | | |
| 9 | V | - | Imported Earth / Sand Zone A | 14 days | Tue 7/4/15 | Fri 24/4/15 | | | | | | |
| 10 | | -5 | Imported Earth / Sand Zone B | 28 days | Mon 27/4/15 | Wed 3/6/15 | | | | | | |
| 11 | | -5 | External Work 1 | 14 days | Tue 7/4/15 | Fri 24/4/15 | | I-1 | | | | |
| 12 | | -5 | Wash Through/Silt | 14 days | Tue 7/4/15 | Fri 24/4/15 | | | | | | |
| 13 | | -5 | Water Tank 200 Gallon | 14 days | Tue 7/4/15 | Fri 24/4/15 | | | | | | |
| | | | Task | | | Inactive Summary | | external Tasks | | | | |
| | | | Split | | | Manual Task | E | External Milestor | e 💠 | | | |
|)rois | FV | ISTING | Milestone | • | ♦ | Duration-only | | Deadline | • | | | |
| - | | 11/4/18 | Summary | | | Manual Summary Rollup | | Critical | | | | |
| | | , ., . | Project Sum | mary | | Manual Summary | | Critical Split | | | | |
| | | | Inactive Task | k [| | Start-only | F | Progress | | | | |
| | | | Inactive Mile | estone | | Finish-only |] | Manual Progress | | | | |
| | | | 1 | | | Page 1 | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | | tember 16/11 | 21 January 18/1 22/ | 1 Jun 3 24/5 | | 11 October 27/9 29/11 | 21 Feb | ruary 3/4 | 1 J 5/6 |
|------------|------------|------------------|------------------------|----------|-------------|-----------------------|---|-----------------|------------------------|-----------------|------------|--------------------------|--------|--------------|------------|
| 14 | | * | External Work 2 | 123 days | Wed 15/4/15 | Fri 2/10/15 | | | | | | | | | |
| 15 | | -5 | Temporary Pavii | 14 days | Wed 15/4/15 | Mon 4/5/15 | | | | | | | | | |
| 16 | | -5 | Gabion Wall | 115 days | Mon 27/4/15 | Fri 2/10/15 | | | | | | | | | |
| 17 | | -5 | Building Work | 313 days | Mon 2/2/15 | Wed 13/4/16 | | | | | | | | | |
| 18 | | -5 | Kompleks Hasil | 112 days | Mon 27/4/15 | Tue 29/9/15 | | | | | | 1 | | | |
| 19 | | -5 | Preparation C | 1 day | Mon 27/4/15 | Mon 27/4/15 | | | | | | | | | |
| 20 | | -5 | Setting Out | 1 day | Tue 28/4/15 | Tue 28/4/15 | | | | † | | | | | |
| 21 | | -5 | Work Below F | 9 days | Tue 28/4/15 | Fri 8/5/15 | | | ı | -10 | | | | | |
| 22 | | - | Column Stu | 9 days | Tue 28/4/15 | Fri 8/5/15 | | | ı | -i | | | | | |
| 23 | | - | Re-bar | 2 days | Tue 28/4/15 | Wed 29/4/15 | | | | | | | | | |
| 24 | III | - 5 | Formwork | 2 days | Thu 30/4/15 | Fri 1/5/15 | | | | <u> </u> | | | | | |
| 25 | | - | Concretin | 2 days | Mon 4/5/15 | Tue 5/5/15 | | | | <u> </u> | | | | | |
| 26 | | -5 | Striking F | 3 days | Wed 6/5/15 | Fri 8/5/15 | | | | † | | | | | |
| 27 | === | -5 | Backfilling | 1 day | Wed 6/5/15 | Wed 6/5/15 | | | | <u>†</u> | | | | | |
| 28 | | -5 | Ground Floor Slab & | 24 days | Thu 7/5/15 | Tue 9/6/15 | | | | | | | | | |
| 29 | | -5 | Ground Beam Beam | 15 days | Thu 7/5/15 | Wed 27/5/15 | | | | | | | | | |
| 30 | III | - | Excavatio | 1 day | Thu 7/5/15 | Thu 7/5/15 | | | | <u> </u> | | | | | |
| 31 | | - 5 | Lean Con | 3 days | Fri 8/5/15 | Tue 12/5/15 | | | | <u> </u> | | | | | |
| 32 | | - | Formwork | 3 days | Wed 13/5/15 | Fri 15/5/15 | | | | <u> </u> | | | | | |
| 33 | | - 5 | Re-bar | 2 days | Mon 18/5/15 | Tue 19/5/15 | | | | <u> </u> | | | | | |
| 34 | | -5 | Concretin | 2 days | Wed 20/5/15 | Thu 21/5/15 | | | | <u> </u> | | | | | |
| , | | | Task | | | Inactive Summary | | | External Tasks | 5 | | | | | |
| | | | Split | | | Manual Task | | | External Miles | stone | \Diamond | | | | |
| . . | . =\ | CTINIC | Milestone | | ♦ | Duration-only | | | Deadline | | • | | | | |
| • | | STING 11/4/18 | Summary | | | Manual Summary Rollup | | | Critical | | | | | | |
| Dale. | vveu | 11/4/10 | Project Sum | mary | | Manual Summary | | | Critical Split | | | | | | |
| | | | Inactive Tasl | • | | Start-only | Е | | Progress | | | | | | |
| | | | Inactive Mile | | | Finish-only | 3 | | Manual Progr | ess | | | | | |
| | | | 1 | | | Page 2 | | | | | | | | | |

| 36 37 38 39 40 41 42 | | | Slab Termite To | 1 day 10 days 2 days 1 day 2 days | Fri 22/5/15 Wed 27/5/15 Wed 27/5/15 Wed 27/5/15 Thu 28/5/15 Fri 29/5/15 | Tue 26/5/15 Wed 27/5/15 Tue 9/6/15 Thu 28/5/15 Thu 28/5/15 | 14/9 16/11 | | 24/5 2 | 26/7 27/9 | 29/11 | 31/1 | 3/4 | 5/6 |
|----------------------------------|------------|----------------------|---|-----------------------------------|--|--|------------|-------------------|--------------|-----------|-------|------|-----|-----|
| 37 38 39 40 41 42 | | | Ground Slab Termite To DPM Shee BRC Formwork | 10 days 2 days 1 day 2 days | Wed 27/5/15 Wed 27/5/15 Thu 28/5/15 Fri 29/5/15 | Tue 9/6/15 Thu 28/5/15 Thu 28/5/15 | | P | 1 | | | | | |
| 38 39 40 41 42 42 | | -5 -5 -5 -5 | Slab Termite To DPM Sheet BRC Formwork | 2 days 1 day 2 days | Wed 27/5/15 Thu 28/5/15 Fri 29/5/15 | Thu 28/5/15 Thu 28/5/15 | | 1 | -11 | | | | | |
| 39 40 41 42 | | -5 -5 -5 | DPM Shee BRC Formwork | 1 day 2 days | Thu 28/5/15 Fri 29/5/15 | Thu 28/5/15 | | | | | | | | |
| 40 41 42 | | -5 -5 | BRC Formwork | 2 days | Fri 29/5/15 | | | _ | | | | | | |
| 41 42 | III | -5 -5 | Formwork | | | NA 4 /C /4 F | | i | | | | | | |
| 42 | III | | | 2 days | | Mon 1/6/15 | | | <u> </u> | | | | | |
| | | _ | Concretin | | Tue 2/6/15 | Wed 3/6/15 | | | | | | | | |
| 40 | | | | 1 day | Thu 4/6/15 | Thu 4/6/15 | | | | | | | | |
| 43 | | - | Striking Fo | 3 days | Fri 5/6/15 | Tue 9/6/15 | | | | | | | | |
| 44 | | -5 | GF Column | 9 days | Wed 10/6/15 | Mon 22/6/15 | | | m | | | | | |
| 45 | | -5 | Re-bar | 3 days | Wed 10/6/15 | Fri 12/6/15 | | | | | | | | |
| 46 | - | -5 | Formwork | 3 days | Mon 15/6/15 | Wed 17/6/15 | | | 5 | | | | | |
| 47 | | -5 | Concreting | 1 day | Thu 18/6/15 | Thu 18/6/15 | | | 5 | | | | | |
| 48 | | -5 | Striking Form | | Fri 19/6/15 | Mon 22/6/15 | | | K | | | | | |
| 49 | | -9 | Roof Beam & Slab | 43 days | Tue 23/6/15 | Thu 20/8/15 | | | | 1 | | | | |
| 50 | | -5 | Formwork | 14 days | Tue 23/6/15 | Fri 10/7/15 | | | | | | | | |
| 51 | | 5 | Re-bar | 4 days | Mon 13/7/15 | Thu 16/7/15 | | | K | | | | | |
| 52 | - | -5 | Concreting | 1 day | Fri 17/7/15 | Fri 17/7/15 | | | | | | | | |
| 53 | | -5 | Striking Form | 3 days | Mon 20/7/15 | Wed 22/7/15 | | | | | | | | |
| 54 | | - | Roof | 21 days | Thu 23/7/15 | Thu 20/8/15 | | | | 7 | | | | |
| | | | Task | | | nactive Summary | | External Tasks | - | | | | | |
| | | | Split | | N | Manual Task | | External Mileston | e \Diamond | > | | | | |
| | | | Milestone | • | • | Ouration-only | | Deadline | 1 | • | | | | |
| Project | | | Summary | | | Manual Summary Rollup 🕳 | | Critical | | | | | | |
| Date: V | wea | 11/4/18 | Project Sum | mary | | Manual Summary | | Critical Split | | | | | | |
| | | | Inactive Task | • | | Start-only | | Progress | | | | | | |
| | | | Inactive Mile | | | Finish-only | | Manual Progress | _ | | | | | |
| | | | | | | Page 3 | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | | September 1/9 16/11 | 21 January 18/1 22/3 | 1 Jun | e 26/7 | 11 October 27/9 29/11 | bruary 3/4 | 1 Ju 5/6 |
|-------|-------------|------------------|-----------------------------|----------|-------------|----------------------|---|------------------------|-------------------------|-------|------------|--------------------------|---------------|-------------|
| 55 | | -5 | R.C Slab & Roof Truss | 14 days | Thu 23/7/15 | Tue 11/8/15 | | | | | | | | |
| 56 | | -5 | Clay Roo | 7 days | Wed 12/8/15 | Thu 20/8/15 | | | | | | | | |
| 57 | | -5 | Brick Work And Partition | - | Mon 20/7/15 | Fri 31/7/15 | | | | | m | | | |
| 58 | | -5 | External Wall | 10 days | Mon 20/7/15 | Fri 31/7/15 | | | | , | | | | |
| 59 | | -5 | Internal Wall | 10 days | Mon 20/7/15 | Fri 31/7/15 | | | | | | | | |
| 60 | | 5 | Window, Door & | _ | Mon 3/8/15 | Tue 29/9/15 | | | | | 1 | 1 | | |
| 61 | | -5 | Vindows | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | | | | |
| 62 | | -5 | Outer Fra | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | T | | | |
| 63 | | -5 | Inner Frame & Glass | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | | | | |
| 64 | | -5 | Doors | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | | | | |
| 65 | | -5 | M.S Stee | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | † | | | |
| 66 | | - | Door Fra | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | T | | | |
| 67 | | -5 | Door Leaf | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | Ť | | | |
| 68 | | -5 | Internal Wa | 28 days | Fri 21/8/15 | Tue 29/9/15 | | | | | | 1 | | |
| 69 | | - | Plasterin | 14 days | Fri 21/8/15 | Wed 9/9/15 | | | | | | | | |
| 70 | | - | Tiling Wo | 14 days | Thu 10/9/15 | Tue 29/9/15 | | | | | | | | |
| 71 | === | - | Painting | 14 days | Thu 10/9/15 | Tue 29/9/15 | | | | | | | | |
| 72 | == | -5 | Pebble V | 7 days | Thu 10/9/15 | Fri 18/9/15 | | | | | | | | |
| | | | Task | | | Inactive Summary | | | External Tasks | | | | | |
| | | | Split | | | Manual Task | | | External Milestor | e | \Diamond | | | |
| | . =\.// | CT11.10 | Milestone | | ♦ | Duration-only | | - | Deadline | | • | | | |
| _ | | STING 11/4/18 | Summary | | | Manual Summary Rollu | | | Critical | | | | | |
| Dale. | vveu | 11/4/10 | Project Sum | mary | | Manual Summary | | | Critical Split | | | | | |
| | | | Inactive Tasl | k | | Start-only | Е | | Progress | | | | | |
| | | | Inactive Mile | estone | | Finish-only | 3 | | Manual Progress | | | | | |
| | | | l | | | Page 4 | | | | | | | | |

| ID | 0 | Task Mode | Task Name | Duration | Start | Finish | | eptember 9 16/11 | 21 January 18/1 22/3 | 1 Jun 24/5 | | 11 Oct | ober 29/11 | 21 Feb | ruary 3/4 | 1 Ju 5/6 |
|--------|------------|--------------|---------------------------|----------|-------------|-----------------------|---|---------------------|-------------------------|---------------|------------|--------|---------------|--------|--------------|-------------|
| 73 | | -5 | Internal Flo | 14 days | Thu 10/9/15 | Tue 29/9/15 | | | | | | | | | | |
| 74 | | -5 | Renderin | 2 days | Thu 10/9/15 | Fri 11/9/15 | | | | | | | | | | |
| 75 | | -5 | Tiling Wo | 14 days | Thu 10/9/15 | Tue 29/9/15 | | | | | | | | | | |
| 76 | | -5 | Internal Cei | 7 days | Thu 10/9/15 | Fri 18/9/15 | | | | | | | | | | |
| 77 | | -5 | External Fir | 14 days | Thu 10/9/15 | Tue 29/9/15 | | | | | | 1 | | | | |
| 78 | | -5 | Plasterin | 14 days | Thu 10/9/15 | Tue 29/9/15 | | | | | | ı | | | | |
| 79 | | -5 | Tiling Wo | 14 days | Thu 10/9/15 | Tue 29/9/15 | | | | | | i | | | | |
| 80 | | -5 | Ceiling Fi | 7 days | Thu 10/9/15 | Fri 18/9/15 | | | | | | | | | | |
| 81 | | -5 | Plumbing V | 7 days | Mon 3/8/15 | Tue 11/8/15 | | | | | | | | | | |
| 82 | | -5 | Electrical W | 7 days | Mon 3/8/15 | Tue 11/8/15 | | | | | | | | | | |
| 83 | | -5 | Mechanical | 7 days | Mon 3/8/15 | Tue 11/8/15 | | | | | | | | | | |
| 84 | | -5 | Sanitary Fit | 7 days | Mon 3/8/15 | Tue 11/8/15 | | | | | Ĭ | | | | | |
| 85 | | -5 | Apron | 7 days | Mon 3/8/15 | Tue 11/8/15 | | | | | Ť | | | | | |
| 86 | | * | Restoran Ikan Bakar | 204 days | Sat 4/7/15 | Wed 13/4/16 | | | | | | | | | | |
| 87 | | -5 | Preparation O | 1 day | Thu 4/6/15 | Thu 4/6/15 | | | | * | | | | | | |
| 88 | | -5 | Setting Out | 1 day | Fri 5/6/15 | Fri 5/6/15 | | | | | | | | | | |
| 89 | | -5 | Work Below Floor Level | 10 days | Mon 6/7/15 | Fri 17/7/15 | | | | H | I | | | | | |
| 90 | | - | Column Stu | 10 days | Mon 6/7/15 | Fri 17/7/15 | | | | H | l | | | | | |
| 91 | | - | Re-bar | 2 days | Mon 6/7/15 | Tue 7/7/15 | | | | * | | | | | | |
| 92 | | -5 | Formwork | 2 days | Wed 8/7/15 | Thu 9/7/15 | | | | | | | | | | |
| 93 | III | | Concretin | 2 days | Fri 10/7/15 | Mon 13/7/15 | | | | | | | | | | |
| | | | Task | | | Inactive Summary | | | External Tasks | | | | | | | |
| | | | Split | | | Manual Task | | | External Milesto | ne | \Diamond | | | | | |
| Projec | -+· EVI | ISTING | Milestone | | ♦ | Duration-only | | | Deadline | | • | | | | | |
| _ | | 11/4/18 | Summary | | | Manual Summary Rollup | | | Critical | | | | | | | |
| | | , ., . | Project Sum | mary | | Manual Summary | | | Critical Split | | | | | | | |
| | | | Inactive Task | < | | Start-only | Г | | Progress | | | | | | | |
| | | | Inactive Mile | estone | | Finish-only | 3 | | Manual Progres | S | | | | | | |
| | | | ' | | | Page 5 | | | | | | | | | | |

| ID | 0 | Task Mode | Task Name | Duration | Start | Finish | | ptember 16/11 | 21 January 18/1 22/3 | 1 Jun 3 24/5 | | 11 Oct | 21 Feb 31/1 | oruary 3/4 | 1 Ju 5/6 |
|-------|---------|--------------|---------------------------------------|----------|-------------|-----------------------|---|------------------|-------------------------|-----------------|------------|--------|----------------|---------------|-------------|
| 94 | | - | Striking Fo | | Tue 14/7/15 | Thu 16/7/15 | | | | li | h | | | | |
| 95 | | -5 | Backfilling | 1 day | Fri 17/7/15 | Fri 17/7/15 | | | | | | | | | |
| 96 | | * | Ground Floor Slab & Ground Ream | 0 days | Mon 2/2/15 | Mon 2/2/15 | | | 2/2 | | _ | | | | |
| 97 | | -5 | Ground Bea | 15 days | Fri 17/7/15 | Thu 6/8/15 | | | | | Н | | | | |
| 98 | | -5 | Excavatio | 1 day | Fri 17/7/15 | Fri 17/7/15 | | | | | † | | | | |
| 99 | | -9 | Lean Con | 3 days | Mon 20/7/15 | Wed 22/7/15 | | | | | Τ, | | | | |
| 100 | | -5 | Formwork | 3 days | Thu 23/7/15 | Mon 27/7/15 | | | | | 5 | | | | |
| 101 | | -5 | Re-bar | 2 days | Tue 28/7/15 | Wed 29/7/15 | | | | | 5 | | | | |
| 102 | | -9 | Concretin | 2 days | Thu 30/7/15 | Fri 31/7/15 | | | | | Κ, | | | | |
| 103 | | -5 | Striking Fo | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | h | | | | |
| 104 | | -5 | Backfilling | 1 day | Thu 6/8/15 | Thu 6/8/15 | | | | | K | | | | |
| 105 | | * | Ground Slab | 11 days | Thu 6/8/15 | Thu 20/8/15 | | | | | 1 | | | | |
| 106 | | -5 | Termite T | 2 days | Thu 6/8/15 | Fri 7/8/15 | | | | | K | | | | |
| 107 | | -5 | DPM Shee | 1 day | Mon 10/8/15 | Mon 10/8/15 | | | | | # | | | | |
| 108 | | -5 | BRC | 2 days | Tue 11/8/15 | Wed 12/8/15 | | | | | | | | | |
| 109 | | -5 | Formwork | 2 days | Thu 13/8/15 | Fri 14/8/15 | | | | | * | | | | |
| 110 | | -5 | Concretin | • | Mon 17/8/15 | Mon 17/8/15 | | | | | K | | | | |
| 111 | | -5 | Striking Fo | 3 days | Tue 18/8/15 | Thu 20/8/15 | | | | | K | | | | |
| 112 | | -5 | GF Column | 9 days | Fri 21/8/15 | Wed 2/9/15 | | | | | m | | | | |
| 113 | | -5 | Re-bar | 3 days | Fri 21/8/15 | Tue 25/8/15 | | | | | | | | | |
| 114 | | -9 | Formwork | 3 days | Wed 26/8/15 | Fri 28/8/15 | | | | | <u> </u> | | | | |
| | | | Task | | | Inactive Summary | | | External Tasks | | | | | | |
| | | | Split | | | Manual Task | | | External Milest | one | \Diamond | | | | |
| | . =>.// | CT11.10 | Milestone | | ♦ | Duration-only | | | Deadline | | • | | | | |
| • | | STING | Summary | | | Manual Summary Rollup | | | Critical | | | | | | |
| Date. | vveu | 11/4/18 | Project Sum | mary | | Manual Summary | | | Critical Split | | | | | | |
| | | | Inactive Task | < | | Start-only | Е | | Progress | | | | | | |
| | | | Inactive Mile | estone | | Finish-only | 3 | | Manual Progre | ess | | | | | |
| | | | | | | Page 6 | | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | | eptember /9 16/11 | 21 January 18/1 22/ | 1 Jun 3 24/5 | | 11 Oct | | 21 Feb | ruary 3/4 | 1 Ju 5/6 |
|-------|---------|--------------|------------------------------------|----------|--------------|----------------------|----|----------------------|------------------------|-----------------|------------|----------|---|--------|--------------|-------------|
| 115 | | -5 | Concreting | 1 day | Mon 31/8/15 | Mon 31/8/15 | | | | | K | | | | | |
| 116 | | -5 | Striking Forn | , | Tue 1/9/15 | Wed 2/9/15 | | | | | K | | | | | |
| 117 | | -5 | Roof Beam & S | 196 days | Mon 2/2/15 | Mon 2/11/1! | 5 | | | | | | | | | |
| 118 | | -5 | Formwork | 14 days | Thu 3/9/15 | Tue 22/9/15 | | | | | | | | | | |
| 119 | | -5 | | 4 days | Wed 23/9/15 | Mon 28/9/15 | | | | | | K | | | | |
| 120 | | -5 | Concreting | 1 day | Tue 29/9/15 | Tue 29/9/15 | | | | | | K | | | | |
| 121 | | -5 | Striking Forn | 3 days | Wed 30/9/15 | Fri 2/10/15 | | | | | | 5 | | | | |
| 122 | | * | Roof | 0 days | Mon 2/2/15 | Mon 2/2/15 | | | ♦ 2/2 | | | | | | | |
| 123 | | | R.C Slab & Roof Truss | 14 days | Mon 5/10/15 | Thu 22/10/1 | 5 | | | | | | | | | |
| 124 | | -5 | Clay Roo | 7 days | Fri 23/10/15 | Mon 2/11/15 | | | | | | | | | | |
| 125 | | * | Brick Work And Partition | | Mon 2/2/15 | Mon 2/2/15 | | | ♦ 2/2 | | | - | | | | |
| 126 | | - | External Wall | 10 days | Mon 5/10/15 | Fri 16/10/15 | | | | | | | | | | |
| 127 | | - | Wall | 10 days | Mon 5/10/15 | Fri 16/10/15 | | | | | | | | | | |
| 128 | | * | Window, Door & Ironmongeries | • | Mon 2/2/15 | Mon 2/2/15 | | | 2/2 | | | | 1 | | | |
| 129 | | * | Windows | 0 days | Mon 2/2/15 | Mon 2/2/15 | | | 2/2 | | | | | | | |
| 130 | | -5 | Outer Fra | 3 days | Mon 19/10/15 | Wed 21/10/1 | .5 | | | | | | | | | |
| 131 | | -5 | Inner Frame & Glass | 3 days | Mon 19/10/15 | Wed 21/10/1 | .5 | | | | | | | | | |
| 132 | | * | | 0 days | Mon 2/2/15 | Mon 2/2/15 | | | 2/2 | | | | | | | |
| | | | Task | | | Inactive Summary | | | External Tasks | ; | | | | | | |
| | | | Split | | | Manual Task | | | External Miles | tone | \Diamond | | | | | |
| | | | Milestone | | • | Duration-only | | | Deadline | | • | | | | | |
| • | | STING | Summary | | | Manual Summary Rollu | D | | Critical | | | | | | | |
| Date: | wed | 11/4/18 | Project Sum | marv | | Manual Summary | · | _ | Critical Split | | | | | | | |
| | | | Inactive Task | • | | Start-only | C | | Progress | | | | | | | |
| | | | Inactive Mile | | | Finish-only | 3 | | Manual Progr | ess | | | | | | |
| | | | illactive lyllie | .3(0)16 | · I | i ii ii 311 Offity | | | ivialiual r 10gl | <i></i> | | | | | | |

| ID | 0 | Task Mode | Task Name | Duration | Start | Finish | | 11 Septemb | | 21 Janua 18/1 | | 1 June | 26/7 | 11 Oc | | 21 Fe 31/1 | bruary 3/4 | 1 Ju 5/6 |
|-------|----------|------------------|---------------------------|----------|--------------|----------------------|----------|------------|-----|------------------|----------|--------|------------|-------|---|---------------|---------------|-------------|
| 133 | | -5 | Door Fran | | Mon 19/10/15 | Wed 21/10/1 | 5 | | | | | | | T | | | | |
| 134 | | - | Door Leaf | 3 days | Mon 19/10/15 | Wed 21/10/1 | 5 | | | | | | | T | | | | |
| 135 | | * | Internal Wa | 0 days | Mon 2/2/15 | Mon 2/2/15 | | | • | 2/2 | | | | - | | | | |
| 136 | | -5 | Plasterin | 14 days | Tue 3/11/15 | Fri 20/11/15 | | | | | | | | | | | | |
| 137 | | - | Cement I | 7 days | Tue 3/11/15 | Wed 11/11/1 | 5 | | | | | | | | | | | |
| 138 | | -5 | Painting | 14 days | Tue 3/11/15 | Fri 20/11/15 | | | | | | | | | | | | |
| 139 | | * | Internal Flo | 0 days | Mon 2/2/15 | Mon 2/2/15 | | | • | 2/2 | | | | | | | | |
| 140 | | -5 | Renderin | 7 days | Mon 23/11/15 | Tue 1/12/15 | | | | | | | | | | | | |
| 141 | | -5 | Tiling Wo | 14 days | Mon 23/11/15 | Thu 10/12/15 | , | | | | | | | | | | | |
| 142 | | - | Roof Truss | 7 days | Mon 23/11/15 | Tue 1/12/15 | | | | | | | | | | | | |
| 143 | | -5 | Wet Kitchen | 7 days | Mon 23/11/15 | Tue 1/12/15 | | | | | | | | | | | | |
| 144 | | -5 | External Fir | 14 days | Mon 23/11/15 | Thu 10/12/1 | 5 | | | | | | | ľ | 7 | | | |
| 145 | | -5 | Plasterin | 14 days | Mon 23/11/15 | Thu 10/12/15 | | | | | | | | | | | | |
| 146 | | -5 | Timber T | 14 days | Mon 23/11/15 | Thu 10/12/15 | | | | | | | | | | | | |
| 147 | | -5 | Plumbing W | 7 days | Mon 23/11/15 | Tue 1/12/15 | | | | | | | | | | | | |
| 148 | | - | Electrical W | 7 days | Mon 23/11/15 | Tue 1/12/15 | | | | | | | | | | | | |
| 149 | | -5 | Mechanical | 7 days | Mon 23/11/15 | Tue 1/12/15 | | | | | | | | | | | | |
| 150 | | * | Gerai Hasil Laut | 79 days | Fri 3/7/15 | Wed 21/10/1 | .5 | | | | | | | | | | | |
| 151 | | -5 | Preparation O | 1 day | Fri 3/7/15 | Fri 3/7/15 | | | | | | | | | | | | |
| 152 | | -5 | Setting Out | 1 day | Fri 3/7/15 | Fri 3/7/15 | | | | | | | | | | | | |
| 153 | | - | Work Below Floor Level | 8 days | Mon 6/7/15 | Wed 15/7/15 | , | | | | | 1-1 | | | | | | |
| | | | Task | | | Inactive Summary | | | E | xternal T | Гasks | | | | | | | |
| | | | Split | | | Manual Task | | | Ex | xternal N | Milestor | ne | \Diamond | | | | | |
| D: | .t. FVI | CTINIC | Milestone | | ♦ | Duration-only | | | D | eadline | | | • | | | | | |
| _ | | STING 11/4/18 | Summary | | | Manual Summary Rollu | р | | C | ritical | | | | | | | | |
| Date. | · · · Cu | . 1, 7, 10 | Project Sumi | mary | | Manual Summary | | | l c | ritical Sp | olit | | | | | | | |
| | | | Inactive Task | (| | Start-only | Е | | Pi | rogress | | | | | | | | |
| | | | Inactive Mile | stone | | Finish-only | 3 | | M | 1anual P | rogress | ; | | | _ | | | |
| | | | 1 | | | Page 8 | | | | | | | | | | | | |

| 154 155 156 | | | | | | Finish | | tember 16/11 | 21 January 18/1 22/3 | 1 June 24/5 | | 11 Oc 27/9 | 29/11 | 31/1 | bruary 3/4 | 1 Jul 5/6 |
|-------------------|---------|---------|---------------------------------------|---------|-------------|-----------------------|---|-----------------|-------------------------|----------------|------------|---------------|-------|------|---------------|--------------|
| | | -9 | Column Stu | | Mon 6/7/15 | Wed 15/7/15 | | | | H | | | | | | |
| 156 | | -5 | Re-bar | | Mon 6/7/15 | Tue 7/7/15 | | | | K | | | | | | |
| | | -5 | Formwork | 2 days | Wed 8/7/15 | Thu 9/7/15 | | | | K | | | | | | |
| 157 | | -5 | Concreting | • | Fri 10/7/15 | Fri 10/7/15 | | | | K | | | | | | |
| 158 | | -5 | Striking Fo | • | Mon 13/7/15 | Tue 14/7/15 | | | | F | | | | | | |
| 159 | | | Backfilling | • | Wed 15/7/15 | Wed 15/7/15 | | | | F | | | | | | |
| 160 | | * | Ground Floor Slab & Ground Beam | 21 days | Thu 16/7/15 | Thu 13/8/15 | | | | 6 | | | | | | |
| 161 | | -5 | Ground Bea | 10 days | Thu 16/7/15 | Wed 29/7/15 | | | | r | 1 | | | | | |
| 162 | | -5 | Excavatio | • | Thu 16/7/15 | Thu 16/7/15 | | | | F | | | | | | |
| 163 | | -5 | Lean Con | 1 day | Fri 17/7/15 | Fri 17/7/15 | | | | F | † | | | | | |
| 164 | | -5 | Formwork | 2 days | Mon 20/7/15 | Tue 21/7/15 | | | | l | † | | | | | |
| 165 | | -5 | | 2 days | Wed 22/7/15 | Thu 23/7/15 | | | | | <u></u> | | | | | |
| 166 | | -9 | Concreting | 1 day | Fri 24/7/15 | Fri 24/7/15 | | | | | | | | | | |
| 167 | | -5 | Striking Fo | • | Mon 27/7/15 | Tue 28/7/15 | | | | | 5 | | | | | |
| 168 | | -5 | Backfilling | • | Wed 29/7/15 | Wed 29/7/15 | | | | | | | | | | |
| 169 | | | Ground Slat | - | Wed 29/7/15 | Thu 13/8/15 | | | | | Н | | | | | |
| 170 | | - | Termite Ti | • | Wed 29/7/15 | Wed 29/7/15 | | | | | 5 | | | | | |
| 171 | | - | DPM She | 1 day | Thu 30/7/15 | Thu 30/7/15 | | | | | Ϋ́ . | | | | | |
| 172 | | - | | 2 days | Fri 31/7/15 | Mon 3/8/15 | | | | | K | | | | | |
| 173 | | -9 | Formwork | • | Tue 4/8/15 | Wed 5/8/15 | | | | | K | | | | | |
| 174 | | | Concreting | 1 day | Thu 6/8/15 | Thu 6/8/15 | | | | | H | | | | | |
| | | | Task | | | Inactive Summary | | | External Tasks | | | | | | | |
| | | | Split | | | Manual Task | | | External Milesto | ne | \Diamond | | | | | |
| | | | Milestone | | ♦ | Duration-only | | | Deadline | | • | | | | | |
| • | | STING | Summary | | | Manual Summary Rollup | | | Critical | | | | | | | |
| Date: | vved | 11/4/18 | Project Sumr | mary | | Manual Summary | | _ | Critical Split | | | | | | | |
| | | | Inactive Task | • | | Start-only | Е | | Progress | | | | | | | |
| | | | Inactive Mile | | | Finish-only | 3 | | Manual Progres | S | | | | | | |
| | | | | | | Page 9 | | | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | | tember 16/11 | 21 January 18/1 22/3 | 1 June 24/5 | | 11 Oct | ober 29/11 | 21 Feb | oruary 3/4 | 1 J 5/6 |
|-------|---------|------------------|-----------------------------|------------------|-------------------------|-------------------------|---|-----------------|-------------------------|----------------|------------|----------|---------------|--------|---------------|------------|
| 175 | | -5 | Striking F | 2 days | Fri 7/8/15 | Mon 10/8/15 | | | | | H | | | | | |
| 176 | | -5 | Apron | 3 days | Tue 11/8/15 | Thu 13/8/15 | | | | | | | | | | |
| 177 | | -5 | GF Column | 8 days | Fri 14/8/15 | Tue 25/8/15 | | | | | HI I | | | | | |
| 178 | | -5 | Re-bar | 2 days | Fri 14/8/15 | Mon 17/8/15 | | | | | | | | | | |
| 179 | | -5 | | 2 days | Tue 18/8/15 | Wed 19/8/15 | | | | | 5 | | | | | |
| 180 | | -5 | Concreting | 1 day | Thu 20/8/15 | Thu 20/8/15 | | | | | K | | | | | |
| 181 | | -5 | Striking Forn | 3 days | Fri 21/8/15 | Tue 25/8/15 | | | | | | | | | | |
| 182 | | -5 | Roof Beam & S | 27 days | Wed 26/8/15 | Thu 1/10/15 | | | | | | 1 | | | | |
| 183 | | -5 | Formwork | 7 days | Wed 26/8/15 | Thu 3/9/15 | | | | | | | | | | |
| 184 | | -5 | Re-bar | 2 days | Fri 4/9/15 | Mon 7/9/15 | | | | | K | | | | | |
| 185 | | -5 | Concreting | 1 day | Tue 8/9/15 | Tue 8/9/15 | | | | | K | | | | | |
| 186 | | -5 | Striking Forn | 3 days | Wed 9/9/15 | Fri 11/9/15 | | | | | K | • | | | | |
| 187 | | * | Roof | 14 days | Mon 14/9/15 | Thu 1/10/15 | | | | | | 1 | | | | |
| 188 | | -5 | R.C Slab & Roof Truss | 7 days | Mon 14/9/15 | Tue 22/9/15 | | | | | | | | | | |
| 189 | | -5 | Clay Roo | 7 days | Wed 23/9/15 | Thu 1/10/15 | | | | | | - | | | | |
| 190 | | * | Brick Work | | Mon 14/9/15 | Tue 22/9/15 | | | | | | | | | | |
| | | | And Partition | | | | | | | | | _ | | | | |
| 191 | | -5 | External Wall | 7 days | Mon 14/9/15 | Tue 22/9/15 | | | | | | | | | | |
| 192 | | -5 | Internal Wall | 7 days | Mon 14/9/15 | Tue 22/9/15 | | | | | | | | | | |
| 191 | | - 5 | Internal | 7 days 7 days | Mon 14/9/15 Mon 14/9/15 | Tue 22/9/15 Tue 22/9/15 | | | | | | | | | | |
| | | | Task | I | | nactive Summary | | | External Tasks | | | | | | | _ |
| | | | Split | | N | Manual Task | | | External Milestor | ne | \Diamond | | | | | |
| | . 5.4 | CTINIC | Milestone | • | • | Ouration-only | | | Deadline | | • | | | | | |
| • | | STING 11/4/18 | Summary | | | Manual Summary Rollup | | | Critical | | | | | | | |
| Jale. | vveu | 11/4/10 | Project Sum | mary | | Manual Summary | | | Critical Split | | | | | | | |
| | | | Inactive Tasl | • | | Start-only | Е | | Progress | | | | | | | |
| | | | Inactive Mile | | | inish-only | 3 | | Manual Progress | i | | | _ | | | |
| | | | 1 | | | Page 10 | | | | | | | | | | |

| D | 0 | Task Mode | | Duration | Start | Finish | | otember 16/11 | 21 January 18/1 22/3 | 1 June | | 11 Oc | tober 29/11 | 21 Feb 31/1 | ruary 3/4 | 1 Ju 5/6 |
|-------|---------|-------------------|------------------------------------|----------|--------------|-----------------------|----------|------------------|-------------------------|--------|------------|------------|----------------|----------------|--------------|-------------|
| 193 | | -5 | Window, Door & Ironmongeries | • | Wed 23/9/15 | Wed 21/10/15 | ; | | | | | | | | | |
| 194 | | - | | 3 days | Wed 23/9/15 | Fri 25/9/15 | | | | | | | | | | |
| 195 | | -5 | Outer Fra | 3 days | Wed 23/9/15 | Fri 25/9/15 | | | | | | Ť | | | | |
| 196 | | -5 | Inner Frame & Glass | 3 days | Wed 23/9/15 | Fri 25/9/15 | | | | | | | | | | |
| 197 | | -5 | | 3 days | Wed 23/9/15 | Fri 25/9/15 | | | | | | | | | | |
| 198 | - | - | Roller Sh | 3 days | Wed 23/9/15 | Fri 25/9/15 | | | | | | Ť | | | | |
| 199 | | -5 | Door Fran | 3 days | Wed 23/9/15 | Fri 25/9/15 | | | | | | Ť | | | | |
| 200 | | -5 | Door Leaf | 3 days | Wed 23/9/15 | Fri 25/9/15 | | | | | | Ť | | | | |
| 201 | | -5 | Internal Wa | 14 days | Fri 2/10/15 | Wed 21/10/15 | ; | | | | | 1 | | | | |
| 202 | | -5 | Plasterin | 7 days | Fri 2/10/15 | Mon 12/10/15 | | | | | | | | | | |
| 203 | - | - | Tiling Wo | 7 days | Tue 13/10/15 | Wed 21/10/15 | | | | | | | | | | |
| 204 | | - | Painting | 7 days | Tue 13/10/15 | Wed 21/10/15 | | | | | | | | | | |
| 205 | | - | Internal Flo | 7 days | Tue 13/10/15 | Wed 21/10/15 | ; | | | | | н | | | | |
| 206 | | -5 | Renderin | 1 day | Tue 13/10/15 | Tue 13/10/15 | | | | | | | | | | |
| 207 | - | -5 | Tiling Wo | 7 days | Tue 13/10/15 | Wed 21/10/15 | | | | | | | | | | |
| 208 | | -5 | Internal Cei | 3 days | Tue 13/10/15 | Thu 15/10/15 | | | | | | | | | | |
| 209 | | -5 | External Fir | 1 day | Tue 13/10/15 | Tue 13/10/15 | | | | | | | | | | |
| 210 | | -5 | Plasterin | 1 day | Tue 13/10/15 | Tue 13/10/15 | | | | | | | | | | |
| 211 | | -5 | Cement I | 1 day | Tue 13/10/15 | Tue 13/10/15 | | | | | | | | | | |
| 212 | | -5 | Pabble W | 1 day | Tue 13/10/15 | Tue 13/10/15 | | | | | | | | | | |
| 213 | | | Tiling Wo | 1 day | Tue 13/10/15 | Tue 13/10/15 | | | | | | | | | | |
| | | | Task | | | Inactive Summary | | | External Tasks | | | | | | | |
| | | | Split | | | Manual Task | | | External Milesto | ne | \Diamond | | | | | |
| ъ. | . 5\" | ICTIN'S | Milestone | | ♦ | Duration-only | | | Deadline | | • | | | | | |
| • | | ISTING 11/4/18 | Summary | | | Manual Summary Rollup | | | Critical | | | | | | | |
| Date. | v v CU | 11/7/10 | Project Sumi | mary | | Manual Summary | | | Critical Split | | | | | | | |
| | | | Inactive Task | (| | Start-only | Е | | Progress | | | | | | | |
| | | | Inactive Mile | estone | | Finish-only | 3 | | Manual Progres | s | | | _ | | | |
| | | | I | | | Page 11 | | | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | | otember 16/11 | 21 January 18/1 22/3 | 1 June 24/5 | | 11 Octo | | 21 Feb 31/1 | ruary 3/4 | 1 5/6 |
|-------|------------|-------------------|-----------------|----------|--------------|-----------------------|---|------------------|-------------------------|----------------|------------|---------|---|----------------|--------------|----------|
| 214 | | -5 | Ceiling Fi | i 1 day | Tue 13/10/15 | Tue 13/10/15 | | | | | | Y | | | | |
| 215 | | | Plumbing V | 7 days | Wed 23/9/15 | Thu 1/10/15 | | | | | | | | | | |
| 216 | | -5 | Electrical Wo | , | Wed 23/9/15 | Thu 1/10/15 | | | | | | | | | | |
| 217 | - | -5 | Mechanical \ | | Wed 23/9/15 | Thu 1/10/15 | | | | | | | | | | |
| 218 | III | -5 | Builder's Wo | 1 day | Wed 23/9/15 | Wed 23/9/15 | | | | | | | | | | |
| 219 | | -5 | Apron | 7 days | Fri 2/10/15 | Mon 12/10/15 | 5 | | | | | Ť | | | | |
| 220 | | * | Public Toilet | 114 days | Fri 3/7/15 | Wed 9/12/15 | | | | | | | | | | |
| 221 | | -5 | Preparation C | 1 day | Fri 3/7/15 | Fri 3/7/15 | | | | | | | | | | |
| 222 | | -5 | Setting Out | 1 day | Mon 6/7/15 | Mon 6/7/15 | | | | K | | | | | | |
| 223 | | -5 | Work Below Fi | 9 days | Tue 7/7/15 | Fri 17/7/15 | | | | | | | | | | |
| 224 | | -5 | Column Stump | 9 days | Tue 7/7/15 | Fri 17/7/15 | | | | ırı | | | | | | |
| 225 | - | -5 | Re-bar | 2 days | Tue 7/7/15 | Wed 8/7/15 | | | | | • | | | | | |
| 226 | | - | Formwork | 2 days | Thu 9/7/15 | Fri 10/7/15 | | | | K | | | | | | |
| 227 | | - | Concretin | 1 day | Mon 13/7/15 | Mon 13/7/15 | | | | 5 | | | | | | |
| 228 | | -5 | Striking F | 3 days | Tue 14/7/15 | Thu 16/7/15 | | | | F | | | | | | |
| 229 | | -5 | Backfiling | 1 day | Fri 17/7/15 | Fri 17/7/15 | | | | F | | | | | | |
| 230 | | - | Ground Floor | 28 days | Mon 20/7/15 | Wed 26/8/15 | | | | ľ | - | | | | | |
| 231 | | -5 | Ground Be | 11 days | Mon 20/7/15 | Mon 3/8/15 | | | | ľ | 1 | | | | | |
| 232 | III | -5 | Excavation | | Mon 20/7/15 | Mon 20/7/15 | | | | 1 | | | | | | |
| 233 | | - | Lean Cor | | Tue 21/7/15 | Tue 21/7/15 | | | | l l | | | | | | |
| 234 | | -5 | Formwor | | Wed 22/7/15 | Thu 23/7/15 | | | | ı li | | | | | | |
| 235 | | - | Re-bar | 2 days | Fri 24/7/15 | Mon 27/7/15 | | | | | Κ | | | | | |
| | | | Task | | | Inactive Summary | | | External Tasks | | | | | | | |
| | | | Split | | | Manual Task | | | External Milestor | ne | \Diamond | | | | | |
| | | | Milestone | | ♦ | Duration-only | | | Deadline | | • | | | | | |
| • | | ISTING 11/4/18 | Summary | | | Manual Summary Rollup |) | | Critical | | | | | | | |
| Jale. | vved | 11/4/10 | Project Sum | mary | | Manual Summary | | | Critical Split | | | | | | | |
| | | | Inactive Tasl | • | | Start-only | Е | | Progress | | | | _ | | | |
| | | | Inactive Mile | | | Finish-only | 3 | | Manual Progress | | | | _ | | | |
| | | | 1 | | | Page 12 | | | | | | | | | | |

| ID | 0 | Task Mode | Task Name | Duration | Start | Finish | | September 4/9 16/11 | 21 January 18/1 22/3 | 1 Jun 24/5 | | 11 Octo | | 21 Feb | ruary 3/4 | 1 Jul 5/6 |
|-------|---------|--------------|------------------------|---------------------|-------------|-------------------------------------|---------------|--------------------------|-------------------------|---------------------------------------|------------|---|---|--------|--------------|--------------|
| 236 | | -5 | Concretir | 1 day | Tue 28/7/15 | Tue 28/7/15 | | | | | | | | | | |
| 237 | | - | Striking F | • | Wed 29/7/15 | Fri 31/7/15 | | | | | | | | | | |
| 238 | | -5 | Backfillin | | Mon 3/8/15 | Mon 3/8/15 | | | | | | | | | | |
| 239 | | | Ground Sla | - | Mon 3/8/15 | Wed 26/8/1 | 5 | | | | 1 | | | | | |
| 240 | | | Termite T | | Mon 3/8/15 | Mon 3/8/15 | | | | | K | | | | | |
| 241 | | -5 | DPM She | 1 day | Tue 4/8/15 | Tue 4/8/15 | | | | | K | | | | | |
| 242 | | -5 | | 2 days | Wed 5/8/15 | Thu 6/8/15 | | | | | F | | | | | |
| 243 | | - | Formwork | | Fri 7/8/15 | Tue 11/8/15 | | | | | T I | | | | | |
| 244 | | | Concretin | • | Wed 12/8/15 | Wed 12/8/1 | 5 | | | | | | | | | |
| 245 | | | Striking F | 3 days | Thu 13/8/15 | Mon 17/8/1 | 5 | | | | K | | | | | |
| 246 | | - | Apron | 7 days | Tue 18/8/15 | Wed 26/8/1 | 5 | | | | | | | | | |
| 247 | | -5 | GF Column | 9 days | Thu 27/8/15 | Tue 8/9/15 | | | | | Н | | | | | |
| 248 | | - | Re-bar | 2 days | Thu 27/8/15 | Fri 28/8/15 | | | | | K | | | | | |
| 249 | | -5 | Formwork | 3 days | Mon 31/8/15 | Wed 2/9/15 | | | | | K | | | | | |
| 250 | | - | Concreting | | Thu 3/9/15 | Thu 3/9/15 | | | | | K | | | | | |
| 251 | | - | Striking Forn | • | Fri 4/9/15 | Tue 8/9/15 | | | | | K | | | | | |
| 252 | | -5 | Roof Beam & S | 42 days | Wed 9/9/15 | Thu 5/11/15 | | | | | 1 | | | | | |
| 253 | | - | Formwork | 14 days | Wed 9/9/15 | Mon 28/9/1 | 5 | | | | | h | | | | |
| 254 | | -5 | Re-bar | 3 days | Tue 29/9/15 | Thu 1/10/15 | | | | | | K | | | | |
| 255 | | -5 | Concreting | | Fri 2/10/15 | Fri 2/10/15 | | | | | | Image: Control of the | | | | |
| 256 | | -5 | Striking Forn | ¹ 3 days | Mon 5/10/15 | Wed 7/10/1 | 5 | | | | | 5 | | | | |
| 257 | | -5 | Roof | 21 days | Thu 8/10/15 | Thu 5/11/15 | | | | | | | | | | |
| | | | Task | | | Inactive Summary | | | External Tasks | | | | _ | | | |
| | | | Split | | | Manual Task | | | External Mileston | ne | \Diamond | | | | | |
| | | | Milestone | | ^ | Duration-only | • | | Deadline | | Ţ | | | | | |
| - | | ISTING | | | | • | ın. | | | | • | | | | | |
| Date: | Wed | 11/4/18 | Summary Project Sum | man. | | Manual Summary Roll Manual Summary | тр ——— | | Critical Split | | | | | | | |
| | | | Project Sum | • | u U | • | | | Critical Split | | | | | | | |
| | | | Inactive Tasl | | | Start-only | | | Progress | _ | | | | | | |
| | | | Inactive Mile | esione | ◇ | Finish-only |] | | Manual Progress | · · · · · · · · · · · · · · · · · · · | | | | | | |
| | | | | | | Page 13 | | | | | | | | | | |

| ID | 0 | Task Mode | | Duration | Start | Finish | | 11 Sept | ember 16/11 | 21 Janua 18/1 | | 1 June 24/5 | | 11 Octo | | 21 Feb | ruary 3/4 | 1 Ju 5/6 |
|------------|------------|------------------|---------------|----------|--------------|--------------------|------------|---------|----------------|------------------|-----------|----------------|------------|------------|---|--------|--------------|-------------|
| 258 | | -5 | R.C Slab | 14 days | Thu 8/10/15 | Tue 27/10/1 | L 5 | | | | | | | 1 | | | | |
| 259 | | -5 | Clay Roo | 7 days | Wed 28/10/15 | 5 Thu 5/11/15 | 5 | | | | | | | | | | | |
| 260 | | - 5 | Brick Work Ar | 14 days | Thu 8/10/15 | Tue 27/10/1 | 15 | | | | | | | H | | | | |
| 261 | | -5 | External Wa | 14 days | Thu 8/10/15 | Tue 27/10/1 | L 5 | | | | | | | | | | | |
| 262 | *** | -5 | Internal Wa | • | Thu 8/10/15 | Tue 27/10/1 | L 5 | | | | | | | | | | | |
| 263 | | -5 | Window, Door | 45 days | Thu 8/10/15 | Wed 9/12/1 | L 5 | | | | | | | 1 | | | | |
| 264 | | -5 | Doors | 3 days | Wed 28/10/1 | 5 Fri 30/10/19 | 5 | | | | | | | | | | | |
| 265 | III | -5 | Door Frame | 3 days | Wed 28/10/1 | 5 Fri 30/10/15 | 5 | | | | | | | | | | | |
| 266 | III | - 5 | Door Leaf | 3 days | Wed 28/10/15 | 5 Fri 30/10/15 | 5 | | | | | | | | | | | |
| 267 | | -5 | Internal Wa | 28 days | Mon 2/11/15 | Wed 9/12/1 | L 5 | | | | | | | - | | | | |
| 268 | | -5 | Plasterin | 14 days | Mon 2/11/15 | Thu 19/11/1 | L5 | | | | | | | ± | | | | |
| 269 | | -9 | Tiling Wo | 14 days | Fri 20/11/15 | Wed 9/12/1 | .5 | | | | | | | | | | | |
| 270 | | -5 | Painting | 7 days | Fri 20/11/15 | Mon 30/11/ | 15 | | | | | | | | | | | |
| 271 | | -5 | Internal Flo | 7 days | Fri 20/11/15 | Mon 30/11/ | /15 | | | | | | | П | | | | |
| 272 | | -5 | Renderin | 2 days | Fri 20/11/15 | Mon 23/11/ | '15 | | | | | | | | | | | |
| 273 | | -5 | Tiling Wo | 7 days | Fri 20/11/15 | Mon 30/11/ | '15 | | | | | | | | | | | |
| 274 | | -5 | Internal Cei | 7 days | Fri 20/11/15 | Mon 30/11/ | '15 | | | | | | | | | | | |
| 275 | | -5 | External Fir | 14 days | Thu 8/10/15 | Tue 27/10/1 | 15 | | | | | | | Н | | | | |
| 276 | | -5 | Plasterin | 14 days | Thu 8/10/15 | Tue 27/10/1 | L 5 | | | | | | | | | | | |
| 277 | | -9 | Cement I | 1 day | Thu 8/10/15 | Thu 8/10/15 | 5 | | | | | | | H | | | | |
| 278 | | -5 | Pebble W | 7 days | Fri 9/10/15 | Mon 19/10/ | '15 | | | | | | | | | | | |
| 279 | === | -5 | Tiling Wo | 7 days | Fri 9/10/15 | Mon 19/10/ | '15 | | | | | | | | | | | |
| | | | Task | | | Inactive Summary | | | | External T | asks | | | | | | | |
| | | | Split | | | Manual Task | | | | External N | ∕lilestor | ne | \Diamond | | | | | |
| . . | . 514 | CTINIC | Milestone | | ♦ | Duration-only | | | | Deadline | | | • | | | | | |
| • | | STING 11/4/18 | Summary | | | Manual Summary Rol | lup | | | Critical | | | | | | | | |
| Date. | vvcu | 11/7/10 | Project Sumr | mary | | Manual Summary | | | _ | Critical Sp | olit | | | | | | | |
| | | | Inactive Task | | | Start-only | Е | | | Progress | | | | | _ | | | |
| | | | Inactive Mile | stone | | Finish-only | 3 | | | Manual Pi | rogress | | | | _ | | | |
| | | | , | | | Page 14 | | | | | | | | | | | | |

| 280 | D | 0 | Task Mode | Task Name | Duration | Start | Finish | 11 September 14/9 16/11 | 21 January 18/1 22/3 | 1 June | | 11 Octo | 21 Februa | |
|--|-----|-----|--------------|---|-----------|-------------|---|----------------------------|--|--------|---|---------|-----------|--|
| Electrical W(7 days Thu 8/10/15 Fri 16/10/15 | 280 | | - | Ceiling Fi | i7 days | Fri 9/10/15 | Mon 19/10/15 | | | | | Ĭ | | |
| 283 | 281 | | -5 | Plumbing V | 7 days | Thu 8/10/15 | Fri 16/10/15 | | | | | | | |
| Sanitary Fit 7 days | 282 | | -5 | | • | Thu 8/10/15 | Fri 16/10/15 | | | | | | | |
| Surau (Musholla 204 days Mon 2/2/15 Thu 12/11/15 | 283 | | -5 | Mechanical \ | 7 days | Thu 8/10/15 | Fri 16/10/15 | | | | | | | |
| Preparation 1 day | 284 | | | Sanitary Fit | 7 days | Thu 8/10/15 | Fri 16/10/15 | | | | | | | |
| On Site Setting Out 1 day Mon 6/7/15 Mon 20/7/15 Work Below FI 10 days Tue 7/7/15 Mon 20/7/15 289 Column Stu 10 days Tue 7/7/15 Mon 20/7/15 290 Re-bar 2 days Tue 7/7/15 Wed 8/7/15 291 Setting Out 1 day Tue 14/7/15 Tue 14/7/15 292 Setting Out 1 day Tue 14/7/15 Tue 14/7/15 293 Setting Out 1 day Tue 14/7/15 Tue 14/7/15 294 Setting Out 1 day Tue 14/7/15 Fri 17/7/15 295 Setting Out 1 day Mon 20/7/15 Mon 20/7/15 Ground Floor 28 days Slab & Ground Beam Tue 21/7/15 Thu 27/8/15 296 Setting Out 1 day Tue 21/7/15 Tue 21/7/15 Project: EXISTING Project: EXISTING Out 1/4/18 Project: EXISTING Out 1/4/18 Project: EXISTING Out 1/4/18 Date: Wed 11/4/18 Out 1/4/18 Date: Wed 11/4/18 Out 2/4/18 Date: Wed 11/4/18 Out 2/4/18 Out 2/4/18 Date: Wed 11/4/18 Out 2/4/18 Out 2/4/15 Out 2/4/15 | 285 | | * | Surau (Musholla | 204 days | Mon 2/2/15 | Thu 12/11/15 | | 0 | | | | | |
| Work Below Fi 10 days Tue 7/7/15 Mon 20/7/15 | 286 | | -5 | · | 1 day | Fri 3/7/15 | Fri 3/7/15 | | | | | | | |
| Column Stu 10 days Tue 7/7/15 Mon 20/7/15 | 287 | | -9 | Setting Out | 1 day | Mon 6/7/15 | Mon 6/7/15 | | | | | | | |
| Re-bar 2 days Tue 7/7/15 Wed 8/7/15 | 288 | | - | Work Below Fi | 10 days | Tue 7/7/15 | Mon 20/7/15 | | | H | | | | |
| Formwork 3 days | 289 | | | Column Stu | 10 days | Tue 7/7/15 | Mon 20/7/15 | | | 1-1 | | | | |
| 292 | 290 | === | | | | Tue 7/7/15 | Wed 8/7/15 | | | 5 | | | | |
| Striking Formwork 294 | 291 | | | | • | Thu 9/7/15 | Mon 13/7/15 | | | K | | | | |
| Backfilling 1 day Mon 20/7/15 Mon 20/7/15 295 Ground Floor 28 days Ground Beam 296 Ground Bea 12 days Tue 21/7/15 Wed 5/8/15 297 Excavatio 1 day Tue 21/7/15 Tue 21/7/15 Task Split Manual Task External Tasks Split Manual Task External Milestone Summary Manual Summary Rollup Critical Project: EXISTING Date: Wed 11/4/18 Project Summary Manual Summary Critical Progress | 292 | | -5 | Concretin | 1 day | Tue 14/7/15 | Tue 14/7/15 | | | F | | | | |
| Ground Floor Slab & Ground Beam 296 Ground Bea 12 days Excavatio 1 day Tue 21/7/15 Wed 5/8/15 Tue 21/7/15 Tue 21/7/15 | 293 | | -5 | Striking Formwork | 3 days | Wed 15/7/15 | Fri 17/7/15 | | | F | | | | |
| Slab & Ground Beam 296 Ground Bea 12 days Excavatio 1 day Tue 21/7/15 Tue 21/7/15 Tue 21/7/15 Froject: EXISTING Date: Wed 11/4/18 Task Split Manual Task Duration-only Summary Manual Summary Manual Summary Project Summary Inactive Summary Manual Task External Milestone Summary Manual Summary Rollup Critical Project Summary Inactive Task Start-only Progress | 294 | | - | Backfilling | 1 day | Mon 20/7/15 | Mon 20/7/15 | | | ì | | | | |
| Project: EXISTING Date: Wed 11/4/18 Excavatio 1 day Tue 21/7/15 Fixernal Tasks External Milestone Duration-only Deadline Summary Manual Summary Rollup Critical Project Summary Inactive Task Start-only Frogress | 295 | | -5 | Slab & | • | Tue 21/7/15 | Thu 27/8/15 | | | 0 | 1 | | | |
| Project: EXISTING Date: Wed 11/4/18 Task Split Manual Task Split Manual Summary Manual Summary Manual Summary Inactive Task Start-only Inactive Task Inactive Summary Manual Summary Critical Progress | 296 | | -5 | Ground Bea | 12 days | Tue 21/7/15 | Wed 5/8/15 | | | ı | - | | | |
| Project: EXISTING Date: Wed 11/4/18 Task Split Manual Task Split Manual Task External Tasks External Milestone Duration-only Deadline Summary Manual Summary Rollup Critical Project Summary Inactive Task Start-only External Tasks External Tasks External Tasks Critical Project Summary Project Summary Start-only Progress | 297 | | - | Excavatio | 1 day | | | | | | | | | |
| mactive winestone V Timish only | _ | | | Split Milestone Summary Project Sum Inactive Tasl | mary k | • | Manual Task Duration-only Manual Summary Rollup Manual Summary Start-only | | External Milesto Deadline Critical Critical Split Progress | | + | | | |
| Page 15 | | | | mactive iville | | ~ | | | | | | | | |


| ID | 0 | Task Mode | Task Name | Duration | Start | Finish | | September 4/9 16/11 | 21 January 18/1 22/3 | 1 June 24/5 | 26/7 | 11 Octo | | 21 Fel | bruary 3/4 | 1 J 5/6 |
|-----------|-------------|------------------|----------------------|----------|-------------|---------------------|----------|------------------------|-------------------------|----------------|------------|---------|---|--------|---------------|------------|
| 298 | | -5 | Lean Concrete | 1 day | Wed 22/7/15 | Wed 22/7/1 | | | | F | | | | | | |
| 299 | === | -5 | Formwork | 3 days | Thu 23/7/15 | Mon 27/7/1 | 5 | | | | | | | | | |
| 300 | === | -5 | Re-bar | 2 days | Tue 28/7/15 | Wed 29/7/1 | 5 | | | i | | | | | | |
| 301 | | -5 | Concretin | | Thu 30/7/15 | Thu 30/7/15 | | | | | Ϋ́ | | | | | |
| 302 | | -5 | Striking F | | Fri 31/7/15 | Tue 4/8/15 | | | | | K | | | | | |
| 303 | | -5 | Backfilling | | Wed 5/8/15 | Wed 5/8/15 | | | | | Ĭ | | | | | |
| 304 | | -5 | Ground Sla | - | Wed 5/8/15 | Thu 27/8/15 | 5 | | | | Н | | | | | |
| 305 | | -5 | Termite T | | Wed 5/8/15 | Wed 5/8/15 | | | | | | | | | | |
| 306 | | -5 | DPM She | 1 day | Thu 6/8/15 | Thu 6/8/15 | | | | | F | | | | | |
| 307 | | -5 | | 2 days | Fri 7/8/15 | Mon 10/8/1 | 5 | | | | H | | | | | |
| 308 | | - | Formwork | | Tue 11/8/15 | Wed 12/8/1 | 5 | | | | | | | | | |
| 309 | | -5 | Concretin | • | Thu 13/8/15 | Thu 13/8/15 | | | | | | | | | | |
| 310 | | -5 | Striking F | 3 days | Fri 14/8/15 | Tue 18/8/15 | | | | | 5 | | | | | |
| 311 | | -5 | | 7 days | Wed 19/8/15 | Thu 27/8/15 | | | | | | | | | | |
| 312 | | -5 | GF Column | 9 days | Wed 19/8/15 | Mon 31/8/1 | 5 | | | | 171 | | | | | |
| 313 | | -5 | Re-bar | 2 days | Wed 19/8/15 | Thu 20/8/15 | | | | | 5 | | | | | |
| 314 | | -5 | Formwork | 3 days | Fri 21/8/15 | Tue 25/8/15 | | | | | K | | | | | |
| 315 | === | -5 | Concreting | 1 day | Wed 26/8/15 | Wed 26/8/1 | 5 | | | | K | | | | | |
| 316 | | -5 | Striking Formwork | 3 days | Thu 27/8/15 | Mon 31/8/1 | 5 | | | | | | | | | |
| 317 | | -5 | Roof Beam & Slab | 35 days | Tue 1/9/15 | Mon 19/10/ | 15 | | | | 1 | | | | | |
| | | | Task | | | Inactive Summary | | | External Tasks | | | | | | | |
| | | | Split | | | Manual Task | | | External Milestor | ne | \Diamond | | | | | |
| D., . : - | FV! | CTINIC | Milestone | | ♦ | Duration-only | | | Deadline | | • | | | | | |
| • | | STING 11/4/18 | Summary | | | Manual Summary Roll | up | | Critical | | | | | | | |
| Date. | vvcu | 1 1/4/10 | Project Sum | mary | | Manual Summary | | | Critical Split | | | | | | | |
| | | | Inactive Tasl | k | | Start-only | Е | | Progress | | | | _ | | | |
| | | | Inactive Mile | estone | | Finish-only | 3 | | Manual Progress | i | | | _ | | | |
| | | | 1 | | | Page 16 | | | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | | September 16/11 | 21 January | | | 11 October 27/9 29/1 | bruary 3/4 | |
|-------|--------------------|-------------------|------------------------------------|----------|-------------|---------------------|----|--------------------|----------------|--------|----------------|----------------------|---------------|---|
| 318 | | -5 | Formwork | 7 days | Tue 1/9/15 | Wed 9/9/15 | | | | | T ₁ | | | |
| 319 | - | -5 | Re-bar | 3 days | Thu 10/9/15 | Mon 14/9/15 | 5 | | | | ľ | | | |
| 320 | - | -5 | Concreting | 1 day | Tue 15/9/15 | Tue 15/9/15 | | | | | F | | | |
| 321 | | -5 | Striking Formwork | 3 days | Wed 16/9/15 | Fri 18/9/15 | | | | | ì | | | |
| 322 | | - | Roof | 21 days | Mon 21/9/15 | Mon 19/10/ | 15 | | | | ı | — | | |
| 323 | | -9 | R.C Slab & Roof Truss | 14 days | Mon 21/9/15 | Thu 8/10/15 | | | | | | | | |
| 324 | | 5 | Clay Roof | 7 days | Fri 9/10/15 | Mon 19/10/2 | 15 | | | | | Ĭ | | |
| 325 | | 5 | Brick Work And Partition | 7 days | Mon 21/9/15 | Tue 29/9/15 | | | | | I | ľ | | |
| 326 | | 5 | External Wall | 7 days | Mon 21/9/15 | Tue 29/9/15 | | | | | | | | |
| 327 | | 5 | Wall | 7 days | Mon 21/9/15 | Tue 29/9/15 | | | | | | | | |
| 328 | | -5 | Window, Door & Ironmongeries | • | Mon 21/9/15 | Fri 6/11/15 | | | | | ı | 1 | | |
| 329 | | - | Windows | 3 days | Mon 21/9/15 | Wed 23/9/1 | 5 | | | | I | | | |
| 330 | | - | Outer Fra | 3 days | Mon 21/9/15 | Wed 23/9/15 | 5 | | | | | | | |
| 331 | | -5 | Inner Frame & Glass | 3 days | Mon 21/9/15 | Wed 23/9/15 | 5 | | | | | | | |
| 332 | | - | | 1 day | Mon 21/9/15 | Mon 21/9/1 | 5 | | | | I | | | _ |
| | | | Task | | | Inactive Summary | | | External Tas | ks | | | | _ |
| | | | Split | | | Manual Task | | | External Mil | estone | \Diamond | | | |
| | . =>:: | CTING | Milestone | | ♦ | Duration-only | | | Deadline | | • | | | |
| • | | ISTING 11/4/18 | Summary | | | Manual Summary Roll | ıp | | Critical | | | | | |
| Jaic. | v v C U | 1 1/4/10 | Project Sum | mary | | Manual Summary | | | Critical Split | | | | | |
| | | | Inactive Tas | k | | Start-only | Е | | Progress | | | | | |
| | | | Inactive Mile | | | Finish-only | 3 | | Manual Prog | gress | | | | |
| | | | I | | | Page 17 | | | | | | | | _ |

| ID | 0 | Task Mode | Task Name | Duration | Start | Finish | 11 September 14/9 16/11 | 21 January 18/1 22/3 | 1 June 24/5 | 26/7 | 11 October 27/9 29/11 | 21 Feb | oruary 3/4 | 1 Jul 5/6 |
|--------|---------|--------------|-------------------------------|--------------------|--------------|-----------------------|----------------------------|-------------------------|----------------|------------|--------------------------|--------|---------------|--------------|
| 333 | | -5 | Door Fran | | Mon 21/9/15 | Mon 21/9/15 | | | | | | | | |
| 334 | - | | Door Lea | ^f 1 day | Mon 21/9/15 | Mon 21/9/15 | | | | | | | | |
| 335 | | -59 | Internal Floor Finishes | 21 days | Wed 30/9/15 | Wed 28/10/15 | | | | | | | | |
| 336 | - | | Plasterin | 14 days | Wed 30/9/15 | Mon 19/10/15 | | | | | | | | |
| 337 | | -5 | Tiling Wo | 7 days | Tue 20/10/15 | Wed 28/10/15 | | | | | | | | |
| 338 | - | -5 | Painting | 7 days | Tue 20/10/15 | Wed 28/10/15 | | | | | | | | |
| 339 | | -59 | Internal Floor Finishes | 8 days | Wed 30/9/15 | Fri 9/10/15 | | | | | П | | | |
| 340 | | - | Renderir | 1 day | Wed 30/9/15 | Wed 30/9/15 | | | | | | | | |
| 341 | - | - | Tiling Wo | 7 days | Thu 1/10/15 | Fri 9/10/15 | | | | | <u> </u> | | | |
| 342 | | - | Internal Ce | i7 days | Mon 12/10/15 | Tue 20/10/15 | | | | | Ť | | | |
| 343 | | - | External Fi | 28 days | Wed 30/9/15 | Fri 6/11/15 | | | | | | | | |
| 344 | | -5 | Plasterin | 14 days | Wed 30/9/15 | Mon 19/10/15 | | | | | | | | |
| 345 | | | Tiling Wo | 7 days | Tue 20/10/15 | Wed 28/10/15 | | | | | | | | |
| 346 | | -5 | Ceiling F | i 7 days | Thu 29/10/15 | Fri 6/11/15 | | | | | Y | | | |
| 347 | | -5 | Plumbing V | 7 days | Wed 30/9/15 | Thu 8/10/15 | | | | | | | | |
| 348 | | | Electrical W | • | Wed 30/9/15 | Thu 8/10/15 | | | | j | | | | |
| 349 | | | Mechanical | | Wed 30/9/15 | Thu 8/10/15 | | | | | | | | |
| 350 | | * | External Works | 135 days | Tue 7/7/15 | Mon 11/1/16 | | | | | | | | |
| 351 | | -5 | Surface Water | 116 days | Tue 7/7/15 | Tue 15/12/15 | | | | | | | | |
| | | | | | | | ' | | | | | | | |
| | | | Task | | | nactive Summary | | External Tasks | | | | | | |
| | | | Split | | | Manual Task | | External Mileston | ne | \Diamond | | | | |
| Projec | ct: FXI | STING | Milestone | • | | Ouration-only | | Deadline | | • | | | | |
| _ | | 11/4/18 | Summary | | l N | Manual Summary Rollup | | Critical | | | | | | |
| | | | Project Sum | mary I | | Manual Summary | | Critical Split | | | | | | |
| | | | Inactive Tas | k | 5 | tart-only | Г | Progress | | | | | | |
| | | | Inactive Mile | estone | > F | inish-only | 3 | Manual Progress | 5 | | | | | |
| , | | | • | | | Page 18 | | | | | | | | |

| ID | 0 | Task Mode | Task Name | Duration | Start | Finish | | tember 16/11 | 21 Janua 18/1 | | 1 June 24/5 | 26/7 | 11 Oct | tober 29/11 | 21 Fel | bruary 3/4 | 1 Ju 5/6 |
|-------|------------|------------------|---------------------------|----------|--------------|----------------------|---|-----------------|------------------|----------|----------------|------------|--------|----------------|--------|---------------|-------------|
| 352 | | * | Drain, Box Concrete | 60 days | Wed 23/9/15 | Tue 15/12/1 | 5 | | | | | | | | | | |
| 353 | | -5 | 900mm | 60 days | Wed 23/9/15 | Tue 15/12/15 | | | | | | | | | | | |
| 354 | | -5 | 900mm | 60 days | Wed 23/9/15 | Tue 15/12/15 | i | | | | | | | | | | |
| 355 | === | -5 | Others | 90 days | Tue 7/7/15 | Mon 9/11/15 | | | | | | | | | | | |
| 356 | | -5 | Roadworks & Pavements | 45 days | Tue 10/11/15 | Mon 11/1/16 | • | | | | | | | _ | | | |
| 357 | | -5 | Interlocking | 21 days | Tue 10/11/15 | Tue 8/12/15 | | | | | | | | | | | |
| 358 | === | -5 | Roadworks | 30 days | Tue 10/11/15 | Mon 21/12/1 | 5 | | | | | | | | | | |
| 359 | === | -5 | Road Furnit | 15 days | Tue 22/12/15 | Mon 11/1/16 | | | | | | | | | | | |
| 360 | | -5 | Water Reticula | 44 days | Fri 7/8/15 | Wed 7/10/15 | | | | | | | 7 | | | | |
| 361 | | - | Pipe line | 30 days | Fri 7/8/15 | Thu 17/9/15 | | | | | | | | | | | |
| 362 | | -5 | Pipe Fittings | 30 days | Fri 7/8/15 | Thu 17/9/15 | | | | | | _ | | | | | |
| 363 | III | -5 | JBA - Meter | 14 days | Fri 18/9/15 | Wed 7/10/15 | | | | | | | | | | | |
| 364 | | 5 | Sewerage (Septic Tank) | 14 days | Fri 18/9/15 | Wed 7/10/15 | | | | | | | | | | | |
| 365 | | -5 | Fencing & Railings | 21 days | Tue 10/11/15 | Tue 8/12/15 | | | | | | | | 1 | | | |
| 366 | === | - | Fencing | 21 days | Tue 10/11/15 | Tue 8/12/15 | | | | | | | | | | | |
| 367 | === | - | Railing | 21 days | Tue 10/11/15 | Tue 8/12/15 | | | | | | | | | | | |
| 368 | | - | Electrical Serv | 40 days | Tue 10/11/15 | Mon 4/1/16 | | | | | | | - | | | | |
| 369 | | -5 | LV Cable | 40 days | Tue 10/11/15 | Mon 4/1/16 | | | | | | | | | | | |
| | | | Task | | | Inactive Summary | | | External 1 | Tasks | | | | | | | |
| | | | Split | | | Manual Task | | | External N | Milestor | ne | \Diamond | | | | | |
| D | | ICTINIC | Milestone | | ♦ | Duration-only | | | Deadline | | | • | | | | | |
| _ | | STING 11/4/18 | Summary | | | Manual Summary Rollu | р | | Critical | | | | | | | | |
| Date. | vvcu | . 1, 4, 10 | Project Sum | mary | | Manual Summary | | _ | Critical Sp | olit | | | | | | | |
| | | | Inactive Task | k | | Start-only | Е | | Progress | | | | | _ | | | |
| | | | Inactive Mile | estone | | Finish-only | 3 | | Manual P | rogress | | | | | | | |
| | | | l | | | Page 19 | | | | | | | | | | | |

| ID | | Task | Task Name | Duration | Start | Finish | 11 September 21 January 1 June 11 October 21 February 1 Ju |
|-----|---------|------|--------------------------|----------|--------------|------------|--|
| | U | Mode | | | | | 14/9 16/11 18/1 22/3 24/5 26/7 27/9 29/11 31/1 3/4 5/6 |
| 370 | | -5 | Compound | 40 days | Tue 10/11/15 | Mon 4/1/16 | |
| 371 | | | TESTING AND COMMISIONING | 20 days | Tue 5/1/16 | Mon 1/2/16 | |
| 372 | | -5 | FINAL INSPECTION | 1 day | Tue 2/2/16 | Tue 2/2/16 | The second secon |
| 373 | | -5 | HANDING OVER | 1 day | Wed 3/2/16 | Wed 3/2/16 | <u> </u> |



APPENDIX B MICROSOFT PROJECT FOR RESCHEDULE PLAN OF MEDAN IKAN BAKAR PROJECT

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | 25 | 11 August /5 24/8 | 23/11 | 21 Februa 22/2 | ary 24/5 | 1 September 23/8 22/11 | 11 Marc 21/2 |
|----|---------|--------------------|--|-----------|-------------|--|----|-----------------------|--------------|-------------------|----------|---------------------------|-----------------|
| 1 | | | Membina dan Menyiapkan Sebuah Pusat Pembangunan Anjung Makanan Laut Dan Kompleks Hasil Laut | 252 days | Mon 2/2/15 | Mon 1/2/16 | | | | | | | |
| 2 | | -5 | Start | 1 day | Mon 2/2/15 | Mon 2/2/15 | | | - | | | | |
| 3 | | -5 | Mobilisation On Sit | 3 days | Tue 3/2/15 | Thu 5/2/15 | | | | | | | |
| 4 | | -5 | Water & Power Temporary Supply | 28 days | Fri 6/2/15 | Tue 17/3/15 | | | Ì | | | | |
| 5 | | - | Site Office Set-Up | 28 days | Fri 6/2/15 | Tue 17/3/15 | | | Ì | | | | |
| 6 | | -5 | Surveying Work | 14 days | Tue 10/2/15 | Fri 27/2/15 | | | | | | | |
| 7 | | -5 | Site Preparation & Earthwork | 56 days | Wed 18/3/15 | Wed 3/6/15 | | | | | _ | | |
| 8 | === | -5 | Clear The Site | 14 days | Wed 18/3/15 | Mon 6/4/15 | | | | | | | |
| 9 | | -5 | Imported Earth / Sand Zone A | 14 days | Tue 7/4/15 | Fri 24/4/15 | | | | | | | |
| 10 | | -5 | Imported Earth / Sand Zone B | 28 days | Mon 27/4/15 | Wed 3/6/15 | | | | l† | | | |
| 11 | | -5 | External Work 1 | 14 days | Tue 7/4/15 | Fri 24/4/15 | | | | Н | | | |
| 12 | | -5 | Wash Through/Silt | 14 days | Tue 7/4/15 | Fri 24/4/15 | | | | | | | |
| 13 | | -9 | Water Tank 200 Gallon | 14 days | Tue 7/4/15 | Fri 24/4/15 | | | | | | | |
| , | | SCHEDUL 11/4/18 | Task Split Milestone Summary Project Sum Inactive Task | mary < | • | Inactive Summary Manual Task Duration-only Manual Summary Roll Manual Summary Start-only Finish-only | ıp | Deadli Critica Progre | l I Split | | | | |
| | | | I | | | Page 1 | | | | | | | |

| ID | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Februa 22/2 | iry 24/5 | 1 Septe | ember 22/11 | 11 Marc 21/2 |
|-------|------------|---------------------|---------------------------------------|----------|-------------|----------------------|------------|------|-------------------|-------------|-------------------|----------|---------|----------------|-----------------|
| 14 | | | External Work 2 | 127 days | Wed 15/4/15 | Thu 15/10/15 | 5 | | | | | | 1 | | |
| 15 | | -5 | Temporary Pavir | 14 days | Wed 15/4/15 | Mon 4/5/15 | | | | | | | | | |
| 16 | | -5 | Gabion Wall | 119 days | Mon 27/4/15 | Thu 15/10/15 | | | | | | | | | |
| 17 | | -5 | Building Work | 192 days | Mon 27/4/15 | Mon 1/2/16 | | | | | - | | | | |
| 18 | | -5 | Kompleks Hasil | 113 days | Mon 27/4/15 | Tue 6/10/15 | | | | | - | | 1 | | |
| 19 | | -5 | Preparation C | 1 day | Mon 27/4/15 | Mon 27/4/15 | | | | | 5 | | | | |
| 20 | | -5 | Setting Out | 1 day | Tue 28/4/15 | Tue 28/4/15 | | | | | Ť | | | | |
| 21 | | -5 | Work Below Fi | 9 days | Tue 28/4/15 | Fri 8/5/15 | | | | | п | | | | |
| 22 | | -5 | Column Stu | 9 days | Tue 28/4/15 | Fri 8/5/15 | | | | | н | | | | |
| 23 | | -9 | Re-bar | 2 days | Tue 28/4/15 | Wed 29/4/15 | | | | | <u> </u> | | | | |
| 24 | | -5 | Formwork | 2 days | Thu 30/4/15 | Fri 1/5/15 | | | | | K | | | | |
| 25 | | - | Concretin | 2 days | Mon 4/5/15 | Tue 5/5/15 | | | | | K | | | | |
| 26 | | - | Striking F | 3 days | Wed 6/5/15 | Fri 8/5/15 | | | | | | | | | |
| 27 | | - | Backfilling | 1 day | Wed 6/5/15 | Wed 6/5/15 | | | | | | | | | |
| 28 | | - | Ground Floor Slab & Ground Ream | 24 days | Thu 7/5/15 | Tue 9/6/15 | | | | | r | | | | |
| 29 | | -5 | | 15 days | Thu 7/5/15 | Wed 27/5/15 | | | | | r | ٦ | | | |
| 30 | | 5 | Excavatio | 1 day | Thu 7/5/15 | Thu 7/5/15 | | | | | - | | | | |
| 31 | | - 5 | Lean Con | 3 days | Fri 8/5/15 | Tue 12/5/15 | | | | | | | | | |
| 32 | | -5 | Formwork | 3 days | Wed 13/5/15 | Fri 15/5/15 | | | | | Ì | <u> </u> | | | |
| 33 | | - 5 | Re-bar | 2 days | Mon 18/5/15 | Tue 19/5/15 | | | | | | <u> </u> | | | |
| 34 | III | -5 | Concretin | 2 days | Wed 20/5/15 | Thu 21/5/15 | | | | | | <u> </u> | | | |
| | | | Task | | | Inactive Summary | | | Exterr | nal Tasks | | | | | |
| | | | Split | | | Manual Task | | | Exter | nal Milesto | ne \diamondsuit | | | | |
| ъ. | . 55 | CCLIEDINI | Milestone | | ♦ | Duration-only | | | Dead | line | + | | | | |
| - | | SCHEDULI 11/4/18 | E Summary | | | Manual Summary Rollu | o <u> </u> | | Critica | al | | | | | |
| Date. | vveu | 11/4/10 | Project Sum | mary | | Manual Summary | | | Critica | al Split | | | | | |
| | | | Inactive Task | < | | Start-only | Е | | Progr | | _ | | | | |
| | | | Inactive Mile | | | Finish-only | J | | _ | al Progres | s – | | | | |
| | | | I | | | Page 2 | | | | | | | | | |

|) | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 1 August 24/8 | 23/11 | 21 Februar 22/2 | y 24/5 | 1 Sept | 11 Mar 21/2 |
|-------|-----|--------------|---------------------|----------|-------------|----------------------|---|------|----------------------------|-------------|--------------------|-------------------------|--------|----------------|
| 35 | | | Striking Fo | 3 days | Fri 22/5/15 | Tue 26/5/15 | | | | | | K | | |
| 36 | | -5 | Backfilling | 1 day | Wed 27/5/15 | Wed 27/5/15 | <u>, </u> | | | | | H | | |
| 37 | | -5 | Ground Slab | 10 days | Wed 27/5/15 | Tue 9/6/15 | | | | | | 1-11 | | |
| 38 | | -9 | Termite T | | Wed 27/5/15 | Thu 28/5/15 | | | | | | | | |
| 39 | | -5 | DPM She | 1 day | Thu 28/5/15 | Thu 28/5/15 | | | | | | $\overline{\mathbf{h}}$ | | |
| 40 | | -5 | | 2 days | Fri 29/5/15 | Mon 1/6/15 | | | | | | K | | |
| 41 | | -5 | Formwork | 2 days | Tue 2/6/15 | Wed 3/6/15 | | | | | | | | |
| 42 | | -5 | Concreting | 1 day | Thu 4/6/15 | Thu 4/6/15 | | | | | | T | | |
| 43 | | -5 | Striking Fo | 3 days | Fri 5/6/15 | Tue 9/6/15 | | | | | | | | |
| 44 | | -5 | GF Column | 9 days | Wed 10/6/15 | Mon 22/6/1 | 5 | | | | | 0-1 | | |
| 45 | | -5 | Re-bar | 3 days | Wed 10/6/15 | Fri 12/6/15 | | | | | | | | |
| 46 | | -5 | Formwork | 3 days | Mon 15/6/15 | Wed 17/6/15 |) | | | | | K | | |
| 47 | | -5 | Concreting | | Thu 18/6/15 | Thu 18/6/15 | | | | | | K | | |
| 48 | | -5 | Striking Form | 2 days | Fri 19/6/15 | Mon 22/6/15 | , | | | | | K | | |
| 49 | | - | Roof Beam & Slab | 43 days | Tue 23/6/15 | Thu 20/8/15 | | | | | | I | 1 | |
| 50 | | -5 | Formwork | 14 days | Tue 23/6/15 | Fri 10/7/15 | | | | | | | | |
| 51 | | -5 | | 4 days | Mon 13/7/15 | Thu 16/7/15 | | | | | | K | | |
| 52 | | -5 | Concreting | 1 day | Fri 17/7/15 | Fri 17/7/15 | | | | | | | | |
| 53 | | -5 | Striking Form | 3 days | Mon 20/7/15 | Wed 22/7/15 | | | | | | | | |
| 54 | | -5 | Roof | 21 days | Thu 23/7/15 | Thu 20/8/15 | | | | | | 0 | 7 | |
| | | | Task | | | Inactive Summary | | | ¶ Externa | ıl Tasks | - | | | |
| | | | Split | | | Manual Task | | | | ıl Milestor | ne 💠 | | | |
| | | | Milestone | | ♦ | Duration-only | | | Deadlir | | | | | |
| - | | SCHEDUL | E Summary | | | Manual Summary Rollu | ın | | Critical | | * | | | |
| Date: | Wed | 11/4/18 | Project Sumi | man/ | | Manual Summary | ٦٢ | | 1 Critical | | | | | |
| | | | | - | | Start-only | [| | Progres | - | | | | |
| | | | Inactive Task | | | • | _ | | _ | | | | | |
| | | | Inactive Mile | stone | ♦ | Finish-only |] | | Manua | l Progress | | _ | | |
| | | | | | | Page 3 | | | | | | | | |

|) | 0 | Task Mode | Task Name | Duration | Start | Finish | | | - 25/5 | 11 August 24/8 | 23/11 | 21 Februa 22/2 | ary 24/5 | 1 Septe 23/8 | ember 22/11 | 11 Marc 21/2 |
|-------|-------------|--------------------|-----------------------------|----------|-------------|---------------------|------|---|-----------|-------------------|-------------|----------------|----------|--------------|----------------|-----------------|
| 55 | | -5 | R.C Slab & Roof Truss | 14 days | Thu 23/7/15 | Tue 11/8/15 | | | | | | | | | | |
| 56 | | -5 | Clay Roo | 7 days | Wed 12/8/15 | Thu 20/8/15 | | | | | | | | K | | |
| 57 | | -5 | Brick Work And Partition | _ | Mon 20/7/15 | Fri 31/7/15 | | | | | | | m | | | |
| 58 | | -5 | External Wall | 10 days | Mon 20/7/15 | Fri 31/7/15 | | | | | | | | | | |
| 59 | | -5 | Internal Wall | 10 days | Mon 20/7/15 | Fri 31/7/15 | | | | | | | | | | |
| 60 | | -5 | Window, Door & | _ | Mon 3/8/15 | Tue 6/10/15 | | | | | | | | 1 | | |
| 61 | | -5 | Vindows | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | | | | | | |
| 62 | | -5 | Outer Fra | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | | | | † | | |
| 63 | | -5 | Inner Frame & Glass | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | | | | † | | |
| 64 | | -5 | Doors | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | | | | | | |
| 65 | | -5 | M.S Stee | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | | | | † | | |
| 66 | | -5 | Door Fra | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | | | , | † | | |
| 67 | === | -5 | Door Leaf | 3 days | Mon 3/8/15 | Wed 5/8/15 | | | | | | | | † | | |
| 68 | | -5 | Internal Wa | 29 days | Fri 21/8/15 | Tue 6/10/15 | | | | | | | | 1 | | |
| 69 | | -5 | Plasterin | 14 days | Fri 21/8/15 | Thu 10/9/15 | | | | | | | | | | |
| 70 | | -5 | Tiling Wo | 14 days | Fri 11/9/15 | Mon 5/10/1 | 5 | | | | | | | | | |
| 71 | **** | -5 | Painting | 15 days | Fri 11/9/15 | Tue 6/10/15 | | | | | | | | | | |
| 72 | | -5 | Pebble V | 7 days | Fri 11/9/15 | Tue 22/9/15 | | | | | | | | | | |
| | | | Task | | | Inactive Summary | | | | Exteri | nal Tasks | | | | | |
| | | | Split | | | Manual Task | | | | Exteri | nal Milesto | ne \diamond | | | | |
| | . 5.54 | | _ Milestone | | ♦ | Duration-only | | | | Dead | line | • | | | | |
| • | | SCHEDUL 11/4/18 | _E Summary | | | Manual Summary Roll | ир 🔳 | | | Critical | al | | | | | |
| Jaie. | vveu | 11/4/10 | Project Sum | mary | | Manual Summary | 1 | | | T Critica | al Split | | | | | |
| | | | Inactive Tasl | k | | Start-only | | | | Progr | - | _ | | | | |
| | | | Inactive Mile | estone | \Diamond | Finish-only | = | 1 | | _ | al Progres | s – | | | | |
| | | | · | | | Page 4 | | | | | | | | | | |

| ID | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Februa 22/2 | ary 24/ | | tember 3 22/11 | 11 Marcl 21/2 |
|----------|------|--------------------|---------------------------|----------|-------------|----------------------|------------|------|-------------------|--------------|-------------------|---------|----------|-------------------|------------------|
| 73 | | | Internal Fl | 14 days | Fri 11/9/15 | Mon 5/10/15 | | | | | | | I 1 | | |
| 74 | | -5 | Renderir | 2 days | Fri 11/9/15 | Mon 14/9/15 | | | | | | | | | |
| 75 | | -5 | Tiling Wo | 14 days | Fri 11/9/15 | Mon 5/10/15 | | | | | | | | | |
| 76 | | -5 | Internal Ce | i7 days | Fri 11/9/15 | Tue 22/9/15 | | | | | | | | | |
| 77 | | -5 | External Fi | 14 days | Fri 11/9/15 | Mon 5/10/15 | | | | | | | r1 | | |
| 78 | | -5 | Plasterin | 14 days | Fri 11/9/15 | Mon 5/10/15 | | | | | | | | | |
| 79 | | -5 | Tiling Wo | 14 days | Fri 11/9/15 | Mon 5/10/15 | | | | | | | | | |
| 80 | | -5 | Ceiling F | i 7 days | Fri 11/9/15 | Tue 22/9/15 | | | | | | | | | |
| 81 | | -5 | Plumbing V | 8 days | Mon 3/8/15 | Wed 12/8/15 | | | | | | | | | |
| 82 | | -5 | Electrical W | 8 days | Mon 3/8/15 | Wed 12/8/15 | | | | | | | | | |
| 83 | | -5 | Mechanica | l8 days | Mon 3/8/15 | Wed 12/8/15 | | | | | | | | | |
| 84 | | -5 | Sanitary Fit | 8 days | Mon 3/8/15 | Wed 12/8/15 | | | | | | | | | |
| 85 | | -5 | Apron | 8 days | Mon 3/8/15 | Wed 12/8/15 | | | | | | | Ť | | |
| 86 | | - | Restoran Ikan Bakar | 145 days | Thu 4/6/15 | Tue 5/1/16 | | | | | | | | | |
| 87 | | -5 | Preparation C | 1 day | Thu 4/6/15 | Thu 4/6/15 | | | | | | K | | | |
| 88 | | - | Setting Out | 1 day | Fri 5/6/15 | Fri 5/6/15 | | | | | | | | | |
| 89 | | -5 | Work Below Floor Level | 10 days | Wed 8/7/15 | Tue 21/7/15 | | | | | | | 1 | | |
| 90 | | -5 | Column Stu | 10 days | Wed 8/7/15 | Tue 21/7/15 | | | | | | | 1 | | |
| 91 | - | -5 | Re-bar | 2 days | Wed 8/7/15 | Thu 9/7/15 | | | | | | T |) | | |
| 92 | | -5 | Formwork | 2 days | Fri 10/7/15 | Mon 13/7/15 | | | | | | ı | | | |
| 93 | | -5 | Concretin | 2 days | Tue 14/7/15 | Wed 15/7/15 | | | | | | i | <u> </u> | | |
| | | | Task | | | Inactive Summary | | | Exte | rnal Tasks | | | | | |
| | | | Split | | | Manual Task | | | Exte | rnal Milesto | ne \Diamond | · | | | |
| . | . 55 | CCLIEDIN | Milestone | | ♦ | Duration-only | | | Dead | dline | • | • | | | |
| - | | SCHEDUL 11/4/18 | .E Summary | | | Manual Summary Rollu | o = | | Critic | cal | | | | | |
| Date. | vveu | 11/4/10 | Project Sum | mary | | Manual Summary | ľ | | Critic | cal Split | | | | | |
| | | | Inactive Tasl | k | | Start-only | Е | | Prog | ıress | _ | | | | |
| | | | Inactive Mile | estone | | Finish-only |] | I | _ | ual Progres | s - | | | | |
| | | | ſ | | | Page 5 | | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Februa 22/2 | ry 24/5 | | eptemb 3/8 | er 22/11 | 11 Marc 21/2 |
|-------|------|--------------------|---------------------------------------|----------|-------------|-----------------------|---|------|-------------------|-------------|-------------------|---------|----------------|---------------|-------------|-----------------|
| 94 | | - | Striking Fo | 3 days | Thu 16/7/15 | Mon 20/7/15 | | | | | | | | | , | , _ |
| 95 | | - | Backfilling | 1 day | Tue 21/7/15 | Tue 21/7/15 | | | | | | _ i | † | | | |
| 96 | | -5 | Ground Floor Slab & Ground Ream | 26 days | Tue 21/7/15 | Tue 25/8/15 | | | | | | ı | | | | |
| 97 | | - | Ground Bea | 15 days | Tue 21/7/15 | Mon 10/8/15 | | | | | | ı | Н | | | |
| 98 | | - | Excavatio | 1 day | Tue 21/7/15 | Tue 21/7/15 | | | | | | | † | | | |
| 99 | | - | Lean Con | 3 days | Wed 22/7/15 | Fri 24/7/15 | | | | | | | Κ | | | |
| 100 | | - | Formwork | 3 days | Mon 27/7/15 | Wed 29/7/15 | | | | | | | 5 | | | |
| 101 | | - | Re-bar | 2 days | Thu 30/7/15 | Fri 31/7/15 | | | | | | | 5 | | | |
| 102 | | - | Concreting | 2 days | Mon 3/8/15 | Tue 4/8/15 | | | | | | | ן ו | | | |
| 103 | | - | Striking Fo | 3 days | Wed 5/8/15 | Fri 7/8/15 | | | | | | | † | | | |
| 104 | | - | Backfilling | 1 day | Mon 10/8/15 | Mon 10/8/15 | | | | | | | K | | | |
| 105 | | -5 | Ground Slab | 12 days | Mon 10/8/15 | Tue 25/8/15 | | | | | | | m | | | |
| 106 | | -5 | Termite T | 2 days | Mon 10/8/15 | Tue 11/8/15 | | | | | | | | | | |
| 107 | | -5 | DPM She | 2 days | Wed 12/8/15 | Thu 13/8/15 | | | | | | | | | | |
| 108 | | - | BRC | 2 days | Fri 14/8/15 | Mon 17/8/15 | | | | | | | | | | |
| 109 | - | - | Formwork | 2 days | Tue 18/8/15 | Wed 19/8/15 | | | | | | | | | | |
| 110 | | - | Concreting | 1 day | Thu 20/8/15 | Thu 20/8/15 | | | | | | | | | | |
| 111 | | - | Striking Fo | 3 days | Fri 21/8/15 | Tue 25/8/15 | | | | | | | <u> </u> | | | |
| 112 | | - | GF Column | 9 days | Wed 26/8/15 | Tue 8/9/15 | | | | | | | m | | | |
| 113 | | - | Re-bar | 3 days | Wed 26/8/15 | Fri 28/8/15 | | | | | | | 片 | | | |
| 114 | | - | Formwork | 3 days | Tue 1/9/15 | Thu 3/9/15 | | | | | | | <u> </u> | | | |
| | | | Task | | | Inactive Summary | | | Exterr | nal Tasks | | | | | | |
| | | | Split | | | Manual Task | | | Exterr | nal Milesto | ne \diamondsuit | | | | | |
| | . 55 | CUEDIU | _ Milestone | | ♦ | Duration-only | | | Deadl | ine | • | | | | | |
| • | | SCHEDUL 11/4/18 | E Summary | | | Manual Summary Rollup | | | Critica | al | | | | | | |
| Date. | vveu | 11/4/10 | Project Sum | mary | | Manual Summary | | | C ritica | al Split | 111 | | | | | |
| | | | Inactive Task | • | | Start-only | Е | | Progr | • | _ | | | - | | |
| | | | Inactive Mile | stone | | Finish-only | 3 | | | al Progres | s - | | | - | | |
| | | | I | | | Page 6 | | | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Febru 22/2 | ary 24/5 | 1 Septer 23/8 | mber 22/11 | 11 Mai 21/2 |
|-------|------------|--------------|------------------------------------|----------|--------------|----------------------|---|------|-------------------|------------|------------------|----------|---------------|---------------|----------------|
| 115 | | -5 | Concreting | | Fri 4/9/15 | Fri 4/9/15 | | | | | | | K | | |
| 116 | | -5 | Striking Forn | 2 days | Mon 7/9/15 | Tue 8/9/15 | | | | | | | 片 | | |
| 117 | | -5 | Roof Beam & S | 45 days | Wed 9/9/15 | Tue 17/11/1 | 5 | | | | | | | 1 | |
| 118 | | -5 | Formwork | 14 days | Wed 9/9/15 | Thu 1/10/15 | | | | | | | | | |
| 119 | | -5 | Re-bar | 4 days | Fri 2/10/15 | Wed 7/10/15 | , | | | | | | | | |
| 120 | | -5 | Concreting | 1 day | Thu 8/10/15 | Thu 8/10/15 | | | | | | | | | |
| 121 | | -5 | Striking Forn | 3 days | Fri 9/10/15 | Tue 13/10/1 | 5 | | | | | | | | |
| 122 | | -5 | Roof | 23 days | Thu 15/10/15 | Tue 17/11/1 | 5 | | | | | | | 1 | |
| 123 | | -5 | R.C Slab & Roof Truss | 14 days | Thu 15/10/15 | Tue 3/11/15 | | | | | | | | | |
| 124 | | | Clay Roo | 9 days | Wed 4/11/15 | Tue 17/11/1 | 5 | | | | | | | <u></u> | |
| 125 | | -5 | Brick Work And Partition | | Thu 15/10/15 | Thu 29/10/1 | 5 | | | | | | l-1 | | |
| 126 | III | -5 | External Wall | 11 days | Thu 15/10/15 | Thu 29/10/1 | 5 | | | | | | | | |
| 127 | | -5 | Internal Wall | 11 days | Thu 15/10/15 | Thu 29/10/1 | 5 | | | | | | | | |
| 128 | | -5 | Window, Door & Ironmongeries | • | Fri 30/10/15 | Tue 5/1/16 | | | | | | | ı | <u> </u> | |
| 129 | | -5 | Windows | 4 days | Fri 30/10/15 | Wed 4/11/1 | 5 | | | | | | 10 | | |
| 130 | | - | Outer Fra | 4 days | Fri 30/10/15 | Wed 4/11/15 | , | | | | | | | | |
| 131 | | -5 | Inner Frame & Glass | 4 days | Fri 30/10/15 | Wed 4/11/15 | ; | | | | | | | | |
| 132 | | -5 | Doors | 4 days | Fri 30/10/15 | Wed 4/11/1 | 5 | | | | | | n | | |
| | | | Task | | | Inactive Summary | | | Extern | al Tasks | | | | | |
| | | | Split | | | Manual Task | | | Extern | al Milesto | ne < | > | | | |
| | | | _ Milestone | | ♦ | Duration-only | | | Deadli | ine | 4 | • | | | |
| , | | SCHEDUL | E Summary | | | Manual Summary Rolli | р | | Critica | I | | | | | |
| Date: | vvea | 11/4/18 | Project Sum | mary | | Manual Summary | · | | T Critica | | | | | | |
| | | | Inactive Tasl | • | | Start-only | Е | | Progre | | _ | | | | |
| | | | Inactive Mile | | | Finish-only |] | | _ | al Progres | s - | | | | |
| | | | | | | Page 7 | | | | | | | | | |

| ID | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Februa 22/2 | ary 24/5 | otember 8 22/11 | 11 Marc |
|-------|----------|--------------------|---------------------------|----------|--------------|---------------------|------|------|-------------------|------------|-------------------|----------|--------------------|---------|
| 133 | | -5 | Door Fran | 4 days | Fri 30/10/15 | Wed 4/11/1 | 5 | | | | | | | |
| 134 | | -5 | Door Leaf | 4 days | Fri 30/10/15 | Wed 4/11/1! | 5 | | | | | | | |
| 135 | | -5 | Internal Wa | 16 days | Wed 18/11/1 | Wed 9/12/1 | 5 | | | | | | 1 | |
| 136 | | -5 | Plasterin | 16 days | Wed 18/11/15 | Wed 9/12/1 | 5 | | | | | | * | |
| 137 | | -5 | Cement | 7 days | Wed 18/11/15 | Thu 26/11/1 | 5 | | | | | | | |
| 138 | | -5 | Painting | 16 days | Wed 18/11/15 | Wed 9/12/1 | 5 | | | | | | | |
| 139 | | -5 | Internal Flo | 14 days | Thu 10/12/15 | Thu 31/12/1 | 5 | | | | | | г | |
| 140 | | -5 | Renderin | 7 days | Thu 10/12/15 | Fri 18/12/15 | | | | | | | | |
| 141 | | -5 | Tiling Wo | 14 days | Thu 10/12/15 | Thu 31/12/1 | 5 | | | | | | | |
| 142 | | -5 | Roof Truss | 10 days | Thu 10/12/15 | Wed 23/12/2 | 15 | | | | | | | |
| 143 | | -5 | Wet Kitchen | 10 days | Thu 10/12/15 | Wed 23/12/2 | 15 | | | | | | | |
| 144 | | -5 | External Fir | 16 days | Thu 10/12/15 | Tue 5/1/16 | | | | | | | г | |
| 145 | | -5 | Plasterin | 16 days | Thu 10/12/15 | Tue 5/1/16 | | | | | | | | |
| 146 | | -5 | Timber T | 16 days | Thu 10/12/15 | Tue 5/1/16 | | | | | | | | |
| 147 | | -5 | Plumbing V | 10 days | Thu 10/12/15 | Wed 23/12/2 | 15 | | | | | | | |
| 148 | *** | - | Electrical W | 10 days | Thu 10/12/15 | Wed 23/12/2 | 15 | | | | | | | |
| 149 | | -5 | Mechanical | 10 days | Thu 10/12/15 | Wed 23/12/2 | 15 | | | | | | | |
| 150 | | -5 | Gerai Hasil Laut | 89 days | Fri 3/7/15 | Thu 12/11/1 | 5 | | | | | | | |
| 151 | | -5 | Preparation O | 1 day | Fri 3/7/15 | Fri 3/7/15 | | | | | | | | |
| 152 | | -5 | Setting Out | 1 day | Fri 3/7/15 | Fri 3/7/15 | | | | | | 1 | | |
| 153 | | -5 | Work Below Floor Level | 8 days | Mon 6/7/15 | Wed 15/7/1 | 5 | | | | | i-i | | |
| | | | Task | | | Inactive Summary | | | Extern | al Tasks | | | | |
| | | | Split | | | Manual Task | | | Extern | al Milesto | ne 🔷 | | | |
| D | DEC | CUEDIII | Milestone | | ♦ | Duration-only | | | Deadl | ine | 4 | | | |
| - | | SCHEDUL 11/4/18 | .E Summary | | | Manual Summary Roll | ıp 🚃 | | Critica | ıl | | | | |
| Date. | · · · Cu | . 1/ -// 10 | Project Sum | mary | | Manual Summary | | | Critica | ıl Split | | | | |
| | | | Inactive Task | (| | Start-only | Е | | Progre | ess | _ | | | |
| | | | Inactive Mile | estone | | Finish-only | 3 | | Manu | al Progres | s – | | | |
| | | | 1 | | | Page 8 | | | | | | | | |

| ID | 0 | Task Mode | | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Februa 22/2 | 24/5 | 1 Septe 23/8 | | 11 Marc 21/2 |
|-------|---------|--------------|---------------------------------------|----------|-------------|----------------------|---|------|-------------------|-------------|-------------------|--|--------------|---|-----------------|
| 154 | | -5 | Column Stu | | Mon 6/7/15 | Wed 15/7/15 | | | | | | H | | • | |
| 155 | | -5 | Re-bar | | Mon 6/7/15 | Tue 7/7/15 | | | | | | K | | | |
| 156 | | -5 | Formwork | 2 days | Wed 8/7/15 | Thu 9/7/15 | | | | | | K | | | |
| 157 | | -5 | Concreting | 1 day | Fri 10/7/15 | Fri 10/7/15 | | | | | | The state of the s | | | |
| 158 | | -5 | Striking Fo | | Mon 13/7/15 | Tue 14/7/15 | | | | | | | | | |
| 159 | | -5 | Backfilling | | Wed 15/7/15 | Wed 15/7/15 | | | | | | K | | | |
| 160 | | -5 | Ground Floor Slab & Ground Beam | 22 days | Thu 16/7/15 | Fri 14/8/15 | | | | | | | -1 | | |
| 161 | | -5 | Ground Bea | 10 days | Thu 16/7/15 | Wed 29/7/15 | | | | | | | ı | | |
| 162 | | -5 | Excavatio | • | Thu 16/7/15 | Thu 16/7/15 | | | | | | | | | |
| 163 | === | -5 | Lean Con | 1 day | Fri 17/7/15 | Fri 17/7/15 | | | | | | | | | |
| 164 | | -5 | Formwork | 2 days | Mon 20/7/15 | Tue 21/7/15 | | | | | | | | | |
| 165 | === | -5 | | 2 days | Wed 22/7/15 | Thu 23/7/15 | | | | | | F |) | | |
| 166 | === | -5 | Concreting | 1 day | Fri 24/7/15 | Fri 24/7/15 | | | | | | | | | |
| 167 | | -5 | Striking Fo | • | Mon 27/7/15 | Tue 28/7/15 | | | | | | | | | |
| 168 | | -5 | Backfilling | | Wed 29/7/15 | Wed 29/7/15 | | | | | | i | | | |
| 169 | | | Ground Slat | | Wed 29/7/15 | Fri 14/8/15 | | | | | | | | | |
| 170 | | -5 | Termite Ti | • | Wed 29/7/15 | Wed 29/7/15 | | | | | | | | | |
| 171 | | -5 | DPM She | 1 day | Thu 30/7/15 | Thu 30/7/15 | | | | | | | K | | |
| 172 | | -5 | | 2 days | Fri 31/7/15 | Mon 3/8/15 | | | | | | | <u> </u> | | |
| 173 | === | -5 | Formwork | - | Tue 4/8/15 | Wed 5/8/15 | | | | | | | <u> </u> | | |
| 174 | | -9 | Concreting | 1 day | Thu 6/8/15 | Thu 6/8/15 | | | | | | | H | | |
| | | | Task | | | Inactive Summary | | | Extern | nal Tasks | | | | | |
| | | | Split | | | Manual Task | | | Exterr | nal Milesto | ne \diamondsuit | | | | |
| | | | _ Milestone | | ♦ | Duration-only | | | Dead | line | • | | | | |
| , | | SCHEDUL | E Summary | | | Manual Summary Rollu | | | Critical | al | | | | | |
| Dale. | vveu | 11/4/18 | Project Sumr | mary | | Manual Summary | | | _ | al Split | 111 | | | | |
| | | | Inactive Task | • | | Start-only | Е | | Progr | - | _ | | | | |
| | | | Inactive Mile | stone | | Finish-only | 3 | | _ | al Progres | s – | | | | |
| | | | | | | Page 9 | | | | | | | | | |

| D | _ | Task | Task Name | Duration | Start | Finish | | | 11 August | | 21 Februa | ıry | 1 Septe | ember | 11 Marc |
|-------|-------------|----------|-----------------------------|----------|-------------|----------------------|---|------|-----------|--------------------|------------|------|--------------|-------|---------|
| | 0 | Mode | Otalisis - F | | | | | 25/5 | 24/8 | 23/11 | 22/2 | 24/5 | 23/8 | 22/11 | 21/2 |
| | | -5 | Striking F | | Fri 7/8/15 | Mon 10/8/15 | | | | | | | | | |
| | | - | | 4 days | Tue 11/8/15 | Fri 14/8/15 | | | | | | | | | |
| 177 | | - | | 8 days | Mon 17/8/15 | Wed 26/8/15 | 5 | | | | | | 01 | | |
| 178 | === | -5 | | 2 days | Mon 17/8/15 | Tue 18/8/15 | | | | | | | K I | | |
| 179 | === | - | | 2 days | Wed 19/8/15 | Thu 20/8/15 | | | | | | | K I | | |
| 180 | | - | Concreting | | Fri 21/8/15 | Fri 21/8/15 | | | | | | | K I | | |
| 181 | | -5 | Striking Forn | | Mon 24/8/15 | Wed 26/8/15 | | | | | | | K | | |
| 182 | | -5 | Roof Beam & S | 27 days | Thu 27/8/15 | Thu 8/10/15 | | | | | | | 1 | | |
| 183 | | - | Formwork | 7 days | Thu 27/8/15 | Mon 7/9/15 | | | | | | | | | |
| 184 | | - | Re-bar | 2 days | Tue 8/9/15 | Wed 9/9/15 | | | | | | | | | |
| 185 | | - | Concreting | 1 day | Thu 10/9/15 | Thu 10/9/15 | | | | | | | | | |
| 186 | | -5 | Striking Forn | 3 days | Fri 11/9/15 | Tue 15/9/15 | | | | | | | | | |
| 187 | | - | Roof | 14 days | Thu 17/9/15 | Thu 8/10/15 | | | | | | | 1-1 | | |
| 188 | | -9 | R.C Slab & Roof Truss | 7 days | Thu 17/9/15 | Tue 29/9/15 | | | | | | | | | |
| 189 | | - | Clay Roo | 7 days | Wed 30/9/15 | Thu 8/10/15 | | | | | | | | | |
| 190 | | -5 | Brick Work | 7 days | Thu 17/9/15 | Tue 29/9/15 | | | | | | | m | | |
| | | | And Partition | | | | | | | | | | | | |
| 191 | | -5 | External Wall | 7 days | Thu 17/9/15 | Tue 29/9/15 | | | | | | | | | |
| 192 | | -9 | Internal Wall | 7 days | Thu 17/9/15 | Tue 29/9/15 | | | | | | | | | |
| | | | Wall Internal | · | | | | | | | | | | | |
| | | | Task | | | Inactive Summary | | | Exterr | nal Tasks | | | | | |
| | | | Split | | | Manual Task | | | Exterr | nal Milesto | ne 💠 | | | | |
| | | | Milestone | | ♦ | Duration-only | | | Dead | line | • | | | | |
| _ | | SCHEDULI | E Summary | | | Manual Summary Rollu | р | | Critical | al | | | | | |
| Jate: | vvea | 11/4/18 | Project Sum | marv | | Manual Summary | | | | al Split | | | | | |
| | | | Inactive Task | • | u u | Start-only | C | | Progr | • | | | | | |
| | | | Inactive Mile | | | Finish-only | 3 | | _ | ess ial Progres | s – | | | | |
| | | | | | | Page 10 | | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Februa 22/2 | y 24/5 | 1 Septem 23/8 | ber 22/11 | 11 Ma 21/2 |
|-------|---------|--------------------|------------------------------------|---------------------|--------------|----------------------|---|------|-------------------|--------------|-------------------|-----------|---------------|--------------|---------------|
| 193 | | | Window, Door & Ironmongeries | • | Wed 30/9/15 | Thu 12/11/1 | 5 | | | 23/11 | | | | | 2.72 |
| 194 | | -5 | | 3 days | Wed 30/9/15 | Fri 2/10/15 | | | | | | | | | |
| 195 | - | - | Outer Fra | 3 days | Wed 30/9/15 | Fri 2/10/15 | | | | | | | | | |
| 196 | | | Inner Frame & Glass | 3 days | Wed 30/9/15 | Fri 2/10/15 | | | | | | | | | |
| 197 | | -5 | Doors | 3 days | Wed 30/9/15 | Fri 2/10/15 | | | | | | | | | |
| 198 | | -5 | Roller Sh | n 3 days | Wed 30/9/15 | Fri 2/10/15 | | | | | | | | | |
| 199 | | -5 | Door Fran | ⁿ 3 days | Wed 30/9/15 | Fri 2/10/15 | | | | | | | | | |
| 200 | | -5 | Door Lea | f 3 days | Wed 30/9/15 | Fri 2/10/15 | | | | | | | | | |
| 201 | | -5 | Internal W | 23 days | Fri 9/10/15 | Thu 12/11/1 | 5 | | | | | | | | |
| 202 | | -5 | Plasterin | 7 days | Fri 9/10/15 | Tue 20/10/15 | 5 | | | | | | | | |
| 203 | | -5 | Tiling Wo | c7 days | Wed 21/10/1 | 5 Thu 29/10/15 | 5 | | | | | | | | |
| 204 | | -5 | Painting | 9 days | Fri 30/10/15 | Thu 12/11/15 | 5 | | | | | | | | |
| 205 | | -5 | Internal Fl | l 9 days | Wed 28/10/1 | 5 Mon 9/11/1! | ; | | | | | | | | |
| 206 | | -5 | Renderir | n 1 day | Fri 30/10/15 | Fri 30/10/15 | | | | | | | † | | |
| 207 | | -5 | Tiling Wo | c9 days | Wed 28/10/1 | 5 Mon 9/11/15 | | | | | | | | | |
| 208 | | -5 | Internal Ce | ei3 days | Fri 30/10/15 | Tue 3/11/15 | | | | | | | | | |
| 209 | | -5 | External Fi | r1 day | Fri 30/10/15 | Fri 30/10/15 | | | | | | | | | |
| 210 | | -9 | Plasterin | n 1 day | Fri 30/10/15 | Fri 30/10/15 | | | | | | | | | |
| 211 | | -5 | Cement | I1 day | Fri 30/10/15 | Fri 30/10/15 | | | | | | | | | |
| 212 | | -5 | Pebble V | ∧1 day | Fri 30/10/15 | Fri 30/10/15 | | | | | | | | | |
| 213 | | -9 | Tiling Wo | c1 day | Fri 30/10/15 | Fri 30/10/15 | | | | | | | | | |
| | | | Task | | | Inactive Summary | | | Exterr | nal Tasks | | | | | |
| | | | Split | | | Manual Task | | | Exterr | nal Milestor | ne 💠 | | | | |
| D | D.E.C | CUEDIN | Milestone | | ♦ | Duration-only | | | Deadl | ine | • | | | | |
| • | | SCHEDUL 11/4/18 | E Summary | | | Manual Summary Rollu | р | | Critica | al | | | | | |
| Jaic. | vvcu | 11/7/10 | Project Sum | nmary | | Manual Summary | | | T Critica | al Split | | | | | |
| | | | Inactive Tas | ik | | Start-only | Е | | Progr | ess | _ | | | | |
| | | | Inactive Mile | estone | | Finish-only | 3 | | _ | al Progress | _ | | | | |
| | | | I | | | Page 11 | | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | 25/5 | 11 Au | ugust 14/8 23/ | 21 Febr | | | Septem 23/8 | nber 22/11 | 11 Mar 21/2 |
|-------|---------|--------------|----------------------|----------------------|--------------|-----------------------|------|-------|-------------------|---------|------------|--|----------------|---------------|----------------|
| 214 | | -5 | Ceiling F | i 1 day | Fri 30/10/15 | Fri 30/10/15 | | | | | | | | | |
| 215 | | -5 | Plumbing V | 10 days | Wed 30/9/15 | Tue 13/10/15 | | | | | | | | | |
| 216 | | -5 | Electrical W | ⁽ 10 days | Wed 30/9/15 | Tue 13/10/15 | | | | | | | | | |
| 217 | | 5 | Mechanical | \10 days | Wed 30/9/15 | Tue 13/10/15 | | | | | | | | | |
| 218 | | -5 | Builder's Wo | 1 day | Wed 30/9/15 | Wed 30/9/15 | | | | | | | | | |
| 219 | | 5 | Apron | 7 days | Thu 15/10/15 | Fri 23/10/15 | | | | | | | | | |
| 220 | | -5 | Public Toilet | 116 days | Fri 3/7/15 | Mon 21/12/1 | 5 | | | | - | | | — 1 | |
| 221 | | -5 | Preparation C | 1 day | Fri 3/7/15 | Fri 3/7/15 | | | | | | | | | |
| 222 | - | -5 | Setting Out | 1 day | Mon 6/7/15 | Mon 6/7/15 | | | | | K | | | | |
| 223 | | -5 | Work Below F | 19 days | Tue 7/7/15 | Fri 17/7/15 | | | | | r | 1 | | | |
| 224 | | -5 | Column Stump | 9 days | Tue 7/7/15 | Fri 17/7/15 | | | | | r | ı | | | |
| 225 | | -5 | Re-bar | 2 days | Tue 7/7/15 | Wed 8/7/15 | | | | | | | | | |
| 226 | - | -5 | Formwork | k 2 days | Thu 9/7/15 | Fri 10/7/15 | | | | | 1 | | | | |
| 227 | | -5 | Concretin | 1 day | Mon 13/7/15 | Mon 13/7/15 | | | | | | | | | |
| 228 | | -5 | Striking F | 3 days | Tue 14/7/15 | Thu 16/7/15 | | | | | i | | | | |
| 229 | - | -5 | Backfilling | g 1 day | Fri 17/7/15 | Fri 17/7/15 | | | | | | † | | | |
| 230 | | - | Ground Floor | 30 days | Mon 20/7/15 | Fri 28/8/15 | | | | | | - | | | |
| 231 | | -5 | Ground Be | e 11 days | Mon 20/7/15 | Mon 3/8/15 | | | | | | н | | | |
| 232 | | -5 | Excavati | ^c 1 day | Mon 20/7/15 | Mon 20/7/15 | | | | | | Κ . | | | |
| 233 | | -5 | Lean Co | ^r 1 day | Tue 21/7/15 | Tue 21/7/15 | | | | | | * | | | |
| 234 | - | -5 | Formwor | ¹ 2 days | Wed 22/7/15 | Thu 23/7/15 | | | | | | K | | | |
| 235 | | -5 | Re-bar | 2 days | Fri 24/7/15 | Mon 27/7/15 | | | | | | <u> </u> | | | |
| | | | Task | | | Inactive Summary | | | External Task | (S | | | | | |
| | | | Split | | | Manual Task | | | External Mile | estone | \Diamond | | | | |
| | | | Milestone | • | > | Duration-only | | | Deadline | , | • | | | | |
| • | | SCHEDUL | E Summary | | | Manual Summary Rollup |) | | Critical | ı | | | | | |
| Date: | vved | 11/4/18 | Project Sum | nmary | | Manual Summary | | _ | Critical Split | | | | | | |
| | | | Inactive Tas | • | | Start-only | [| | Progress | | | | | | |
| | | | Inactive Mile | | | Finish-only |] | | Manual Prog | ıress ' | | | _ | | |
| | | | | | | • | | | | • | | | | | |
| | | | | | | Page 12 | | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Februa 22/2 | ry 24/5 | 1 Sept | | 11 Marc 21/2 |
|-------|-------------|--------------|---------------|----------|--------------|--------------------|-------------|------|-------------------|-------------|-------------------|------------|----------|---|-----------------|
| 236 | III | -5 | Concretin | 1 day | Tue 28/7/15 | Tue 28/7/15 | 5 | | | | | Ь | | | |
| 237 | | -5 | Striking F | | Wed 29/7/15 | Fri 31/7/15 | | | | | | 5 | | | |
| 238 | | -5 | Backfilling | 1 day | Mon 3/8/15 | Mon 3/8/15 | ,) | | | | | Ì | | | |
| 239 | | -5 | Ground Slat | | Mon 3/8/15 | Fri 28/8/15 | | | | | | | | | |
| 240 | - | -5 | Termite T | | Mon 3/8/15 | Mon 3/8/15 | • | | | | | 5 | | | |
| 241 | | -5 | DPM She | 1 day | Tue 4/8/15 | Tue 4/8/15 | | | | | | K | 1 | | |
| 242 | III | -5 | | 2 days | Wed 5/8/15 | Thu 6/8/15 | | | | | | | | | |
| 243 | | -5 | Formwork | | Fri 7/8/15 | Tue 11/8/15 | 5 | | | | | | | | |
| 244 | III | -5 | Concretin | | Wed 12/8/15 | Wed 12/8/1 | .5 | | | | | i | | | |
| 245 | - | -5 | Striking Fo | 3 days | Thu 13/8/15 | Mon 17/8/1 | .5 | | | | | i | | | |
| 246 | | -5 | Apron | 9 days | Tue 18/8/15 | Fri 28/8/15 | | | | | | | K | | |
| 247 | | -5 | GF Column | 9 days | Tue 1/9/15 | Fri 11/9/15 | | | | | | | m | | |
| 248 | III | -5 | Re-bar | 2 days | Tue 1/9/15 | Wed 2/9/15 | • | | | | | | <u> </u> | | |
| 249 | | | Formwork | 3 days | Thu 3/9/15 | Mon 7/9/15 | | | | | | | 5 | | |
| 250 | III | -5 | | 1 day | Tue 8/9/15 | Tue 8/9/15 | | | | | | | | | |
| 251 | | -5 | Striking Form | | Wed 9/9/15 | Fri 11/9/15 | | | | | | | | | |
| 252 | | - | Roof Beam & S | 42 days | Mon 14/9/15 | Tue 17/11/ | 15 | | | | | | 1 | _ | |
| 253 | | | Formwork | 14 days | Mon 14/9/15 | Tue 6/10/15 | 5 | | | | | | | | |
| 254 | | -5 | Re-bar | 3 days | Wed 7/10/15 | Fri 9/10/15 | | | | | | | K | | |
| 255 | | - | Concreting | | Mon 12/10/15 | Mon 12/10/ | ' 15 | | | | | | | | |
| 256 | | -5 | Striking Form | 3 days | Tue 13/10/15 | Fri 16/10/15 | 5 | | | | | | | • | |
| 257 | | -9 | Roof | 21 days | Mon 19/10/15 | Tue 17/11/ | 15 | | | | | | ľ | 7 | |
| | | | Task | | | Inactive Summary | | | Exterr | nal Tasks | | | | | |
| | | | Split | | | Manual Task | | | Extern | nal Milesto | ne \diamondsuit | | | | |
| | | | Milestone | | ♦ | Duration-only | | | Deadl | ine | • | | | | |
| • | | SCHEDUL | E Summary | | | Manual Summary Rol | lup | | Critica | | | | | | |
| Date: | vvea | 11/4/18 | Project Sum | marv | | Manual Summary | | | _ | al Split | | | | | |
| | | | Inactive Task | • | | Start-only | | | Progr | • | | | | | |
| | | | Inactive Mile | | | Finish-only | 3 | | _ | al Progress | s - | | | | |
| | | | | | | Page 13 | | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Februa 22/2 | ary 24/5 | 1 Septer 23/8 | mber 22/11 | 11 Marcl 21/2 |
|-------|---------|--------------------|---------------|----------|--------------|---------------------|---------|------|-------------------|------------|-------------------|----------|---------------|------------------|------------------|
| 258 | | | R.C Slab | 14 days | Mon 19/10/15 | Thu 5/11/15 | | | | | | | |) | |
| 259 | | -5 | Clay Roo | 7 days | Fri 6/11/15 | Tue 17/11/1 | 5 | | | | | | | | |
| 260 | | -5 | Brick Work Ar | 14 days | Mon 19/10/1 | 5 Thu 5/11/15 | | | | | | | | | |
| 261 | | -5 | External Wa | 14 days | Mon 19/10/15 | Thu 5/11/15 | | | | | | | | | |
| 262 | | -5 | Internal Wa | 14 days | Mon 19/10/15 | Thu 5/11/15 | | | | | | | | | |
| 263 | | -5 | Window, Door | 45 days | Mon 19/10/1 | Mon 21/12/ | 15 | | | | | | I | 1 | |
| 264 | | -5 | Doors | 3 days | Fri 6/11/15 | Wed 11/11/ | 15 | | | | | | l In | | |
| 265 | | - | Door Frame | 3 days | Fri 6/11/15 | Wed 11/11/1 | 15 | | | | | | | | |
| 266 | | -5 | Door Leaf | 3 days | Fri 6/11/15 | Wed 11/11/2 | 15 | | | | | | | | |
| 267 | | | Internal Wa | 28 days | Thu 12/11/15 | Mon 21/12/ | 15 | | | | | | | | |
| 268 | | -5 | Plasterin | 14 days | Thu 12/11/15 | Tue 1/12/15 | | | | | | | | * | |
| 269 | | -5 | Tiling Wo | 14 days | Wed 2/12/15 | Mon 21/12/2 | 15 | | | | | | | | |
| 270 | | -5 | Painting | 7 days | Wed 2/12/15 | Thu 10/12/1 | 5 | | | | | | | | |
| 271 | | -5 | Internal Flo | 7 days | Wed 2/12/15 | Thu 10/12/1 | 5 | | | | | | | П | |
| 272 | | -5 | Renderin | 2 days | Wed 2/12/15 | Thu 3/12/15 | | | | | | | | | |
| 273 | | -5 | Tiling Wo | 7 days | Wed 2/12/15 | Thu 10/12/1 | 5 | | | | | | | | |
| 274 | | -5 | Internal Cei | 7 days | Wed 2/12/15 | Thu 10/12/1 | 5 | | | | | | | | |
| 275 | | -5 | External Fir | 14 days | Mon 19/10/1 | 5 Thu 5/11/15 | | | | | | | h-1 | | |
| 276 | | -5 | Plasterin | 14 days | Mon 19/10/15 | Thu 5/11/15 | | | | | | | | | |
| 277 | | -5 | Cement I | 1 day | Mon 19/10/15 | Mon 19/10/1 | 15 | | | | | | H | | |
| 278 | | -5 | Pebble W | 8 days | Tue 20/10/15 | Thu 29/10/1 | 5 | | | | | | | | |
| 279 | | -5 | Tiling Wo | 8 days | Tue 20/10/15 | Thu 29/10/1 | 5 | | | | | | | | |
| | | | Task | | | Inactive Summary | | | Extern | al Tasks | | | | | |
| | | | Split | | | Manual Task | | | Extern | al Milesto | ne \diamond | | | | |
| | | | _ Milestone | | ♦ | Duration-only | | | Deadl | ine | • | | | | |
| - | | SCHEDUL 11/4/18 | .E Summary | | | Manual Summary Roll | ıp 🚃 qı | | Critica | I | | | | | |
| Date. | vveu | 11/4/10 | Project Sum | mary | | Manual Summary | | | T Critica | l Split | | | | | |
| | | | Inactive Task | • | | Start-only | Е | | Progre | - | _ | | | | |
| | | | Inactive Mile | | | Finish-only | 3 | | _ | al Progres | s <u> </u> | | | | |
| | | | | | | Page 14 | | | | | | | | | |

| ID | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Februar 22/2 | y 24/5 | 1 Septe 23/8 | | 11 Mar |
|------------|-------------|--------------------|---------------------------------------|----------|--------------|---------------------|----|------|-------------------|-------------|--------------------|---------------------|--------------|---|--------|
| 280 | <u> </u> | - 5 | Ceiling Fi | 8 days | Tue 20/10/15 | Thu 29/10/1 | 5 | 23/3 | L-1/ U | 23/11 | | | 25/0 | | 21/2 |
| 281 | | -5 | Plumbing W | 10 days | Mon 19/10/15 | 5 Fri 30/10/15 | | | | | | | | | |
| 282 | | <u>_</u> | Electrical Wo | 10 days | Mon 19/10/15 | 5 Fri 30/10/15 | | | | | | | | | |
| 283 | === | -5 | Mechanical \ | 10 days | Mon 19/10/15 | 5 Fri 30/10/15 | | | | | | | | | |
| 284 | | -5 | Sanitary Fit | 10 days | Mon 19/10/15 | 5 Fri 30/10/15 | | | | | | | | ĺ | |
| 285 | | - | Surau (Musholla | 106 days | Thu 4/6/15 | Thu 5/11/15 | | | | | | | | 1 | |
| 286 | | | Preparation On Site | 1 day | Thu 4/6/15 | Thu 4/6/15 | | | | | | K | | | |
| 287 | | -5 | Setting Out | 1 day | Fri 5/6/15 | Fri 5/6/15 | | | | | | | | | |
| 288 | | -5 | Work Below FI | 10 days | Tue 7/7/15 | Mon 20/7/1 | 5 | | | | | Н | | | |
| 289 | | -5 | Column Stu | 10 days | Tue 7/7/15 | Mon 20/7/1 | 5 | | | | | Н | | | |
| 290 | | -5 | Re-bar | 2 days | Tue 7/7/15 | Wed 8/7/15 | | | | | | Ь | | | |
| 291 | | -5 | Formwork | 3 days | Thu 9/7/15 | Mon 13/7/1 | 5 | | | | | T T | | | |
| 292 | === | -5 | Concreting | 1 day | Tue 14/7/15 | Tue 14/7/15 | | | | | | | | | |
| 293 | - | -5 | Striking Fo | • | Wed 15/7/15 | Fri 17/7/15 | | | | | | 5 | | | |
| 294 | | -5 | Backfilling | 1 day | Mon 20/7/15 | Mon 20/7/1 | 5 | | | | | K | | | |
| 295 | | -5 | Ground Floor Slab & Ground Beam | 29 days | Tue 21/7/15 | Fri 28/8/15 | | | | | | - | 7 | | |
| 296 | | -5 | Ground Bea | 12 days | Tue 21/7/15 | Wed 5/8/15 | | | | | | 1-1 | | | |
| 297 | | -5 | Excavatio | 1 day | Tue 21/7/15 | Tue 21/7/15 | | | | | | | | | |
| 298 | | -5 | Lean Concrete | 1 day | Wed 22/7/15 | Wed 22/7/1 | 5 | | | | | | | | |
| | | | Task | | | Inactive Summary | | | Extern | nal Tasks | | | | | |
| | | | Split | | | Manual Task | | | Extern | nal Milesto | ne 🔷 | | | | |
| . . | . 55 | CUEDIU | Milestone | | ♦ | Duration-only | | | Deadl | ine | • | | | | |
| • | | SCHEDUL 11/4/18 | .E Summary | | | Manual Summary Roll | ıp | | Critica | al | | | | | |
| Dutc. | vvcu | . 1/ -// 10 | Project Sum | mary | | Manual Summary | | | 1 Critica | al Split | | | | | |
| | | | Inactive Task | (| | Start-only | Е | | Progre | ess | _ | | | | |
| | | | Inactive Mile | estone | | Finish-only | 3 | | Manu | al Progres | <u> </u> | | | | |
| | | | I | | | Page 15 | | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | 2 | 1 25/5 | 1 August 24/8 | 23/11 | 21 Februa 22/2 | ry 24/5 | 1 Sep | otember 8 22/11 | 11 Mar 21/2 |
|-------|---------|--------------|----------------------|----------|-------------|----------------------|---|-----------|------------------|-------------|-------------------|---------------------------------------|----------|--------------------|----------------|
| 299 | | -5 | Formwork | 3 days | Thu 23/7/15 | Mon 27/7/15 | | | | | | K | | | |
| 300 | | -5 | | 2 days | Tue 28/7/15 | Wed 29/7/15 | | | | | | , , , , , , , , , , , , , , , , , , , | | | |
| 301 | | -5 | Concretin | | Thu 30/7/15 | Thu 30/7/15 | | | | | | K | | | |
| 302 | | -5 | Striking F | | Fri 31/7/15 | Tue 4/8/15 | | | | | | Š | | | |
| 303 | | -5 | Backfilling | | Wed 5/8/15 | Wed 5/8/15 | | | | | | Ì | | | |
| 304 | | -5 | Ground Sla | - | Wed 5/8/15 | Fri 28/8/15 | | | | | | l l | 1 | | |
| 305 | *** | -5 | Termite T | | Wed 5/8/15 | Wed 5/8/15 | | | | | | 5 | | | |
| 306 | | -5 | DPM She | 1 day | Thu 6/8/15 | Thu 6/8/15 | | | | | | 5 | | | |
| 307 | | -5 | BRC | 2 days | Fri 7/8/15 | Mon 10/8/15 | | | | | | | | | |
| 308 | | -5 | Formwork | | Tue 11/8/15 | Wed 12/8/15 | | | | | | F | | | |
| 309 | | -5 | Concretin | | Thu 13/8/15 | Thu 13/8/15 | | | | | | F | | | |
| 310 | | -5 | Striking F | 3 days | Fri 14/8/15 | Tue 18/8/15 | | | | | | | | | |
| 311 | | -5 | Apron | 8 days | Wed 19/8/15 | Fri 28/8/15 | | | | | | | | | |
| 312 | | -5 | GF Column | 9 days | Wed 19/8/15 | Tue 1/9/15 | | | | | | I | H1 | | |
| 313 | | -5 | Re-bar | 2 days | Wed 19/8/15 | Thu 20/8/15 | | | | | | | K | | |
| 314 | | -5 | Formwork | 3 days | Fri 21/8/15 | Tue 25/8/15 | | | | | | | K | | |
| 315 | | -5 | Concreting | 1 day | Wed 26/8/15 | Wed 26/8/15 | | | | | | | K | | |
| 316 | | -3 | Striking Formwork | 3 days | Thu 27/8/15 | Tue 1/9/15 | | | | | | | | | |
| 317 | | - | Roof Beam & Slab | 35 days | Wed 2/9/15 | Mon 26/10/1 | 5 | | | | | | | 1 | |
| 318 | | 5 | Formwork | 7 days | Wed 2/9/15 | Thu 10/9/15 | | | | | | | | | |
| 319 | | -5 | Re-bar | 3 days | Fri 11/9/15 | Tue 15/9/15 | | | | | | | K | | |
| | | | Task | | | Inactive Summary | | | Extern | al Tasks | | | | | |
| | | | Split | | | Manual Task | | | Extern | al Milestor | ne \diamondsuit | | | | |
| | | | Milestone | | ♦ | Duration-only | | | Deadl | | • | | | | |
| • | | SCHEDUL | E Summary | | <u> </u> | Manual Summary Rollu | 0 | | Critica | | | | | | |
| Date: | vved | 11/4/18 | Project Sum | marv | | Manual Summary | | | 1 Critica | | | | | | |
| | | | Inactive Tasi | • | | Start-only | E | | Progre | - | | | | | |
| | | | Inactive Mile | | | Finish-only | 3 | | _ | al Progress | _ | | | | |
| | | | | | | • | | | | | | | | | |
| | | | | | | Page 16 | | | | | | | | | |

|) | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Februa 22/2 | ry 24/5 | 1 Septer 23/8 | mber 22/11 | 11 Mar 21/2 |
|-------|------------|--------------|------------------------------------|----------|--------------|----------------------|----|------|-------------------|-------------|-------------------|------------|---------------|---------------|----------------|
| 320 | <u> </u> | -5 | Concreting | 1 day | Thu 17/9/15 | Thu 17/9/15 | | 25/5 | 2-70 | 23/11 | <i>LL,L</i> | | 1 1 | | 21/2 |
| 321 | | -5 | Striking Formwork | 3 days | Fri 18/9/15 | Tue 22/9/15 | | | | | | | | | |
| 322 | | 5 | Roof | 21 days | Wed 23/9/15 | Mon 26/10/ | 15 | | | | | | - | | |
| 323 | III | -5 | R.C Slab & Roof Truss | 14 days | Wed 23/9/15 | Thu 15/10/1 | 5 | | | | | | | | |
| 324 | | -5 | Clay Roof | 7 days | Fri 16/10/15 | Mon 26/10/2 | 15 | | | | | | | | |
| 325 | | -5 | Brick Work And Partition | 7 days | Wed 23/9/15 | Mon 5/10/1 | 5 | | | | | | 0 1 | | |
| 326 | | -5 | External Wall | 7 days | Wed 23/9/15 | Mon 5/10/15 | 5 | | | | | | | | |
| 327 | == | -5 | Internal Wall | 7 days | Wed 23/9/15 | Mon 5/10/15 | 5 | | | | | | | | |
| 328 | | -5 | Window, Door & Ironmongeries | | Wed 23/9/15 | Thu 5/11/15 | | | | | | | | | |
| 329 | | -5 | | 3 days | Wed 23/9/15 | Tue 29/9/15 | | | | | | | ri | | |
| 330 | | -5 | Outer Fra | 3 days | Wed 23/9/15 | Tue 29/9/15 | | | | | | | | | |
| 331 | III | -5 | Inner Frame & Glass | 3 days | Wed 23/9/15 | Tue 29/9/15 | | | | | | | | | |
| 332 | | -5 | Doors | 1 day | Wed 23/9/15 | Wed 23/9/1 | 5 | | | | | | 1 | | |
| 333 | *** | -5 | Door Fran | 1 day | Wed 23/9/15 | Wed 23/9/15 | 5 | | | | | | | | |
| 334 | III | -5 | Door Leaf | 1 day | Wed 23/9/15 | Wed 23/9/15 | 5 | | | | | | H | | |
| | | | Task | | | Inactive Summary | | | Exterr | nal Tasks | | | | | |
| | | | Split | | | Manual Task | | | Exterr | nal Milesto | ne 💠 | | | | |
| | | | _ Milestone | | ♦ | Duration-only | | | Deadl | ine | • | | | | |
| • | | SCHEDUL | .E Summary | | | Manual Summary Rolls | ір | | Critica | al | | | | | |
| Jaie. | vveu | 11/4/18 | Project Sum | mary | | Manual Summary | | | | al Split | | | | | |
| | | | Inactive Tasl | • | | Start-only | Е | | Progr | | _ | | | | |
| | | | Inactive Mile | | | Finish-only | 3 | | | al Progres | _ | | | | |
| | | | I | | | Page 17 | | | | | | | | | |

|) | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Februar 22/2 | y 24/5 | 1 Septem 23/8 | ber 22/11 | 11 Ma 21/2 |
|------|---------|--------------------|-------------------------------|----------|--------------|----------------------|----------|------|-------------------|------------|--------------------|-----------|---------------|--------------|---------------|
| 335 | | -5 | Internal Floor Finishes | 21 days | Fri 2/10/15 | Mon 2/11/15 | | | | | | | | | |
| 336 | | | Plasterin | 14 days | Fri 2/10/15 | Thu 22/10/15 | , | | | | | | | | |
| 337 | | -5 | Tiling Wo | 7 days | Fri 23/10/15 | Mon 2/11/15 | | | | | | | | | |
| 338 | | -5 | Painting | 7 days | Fri 23/10/15 | Mon 2/11/15 | | | | | | | | | |
| 339 | | -5 | Internal Floor Finishes | 8 days | Fri 2/10/15 | Tue 13/10/15 | 5 | | | | | | П | | |
| 340 | | -5 | Renderin | 1 day | Fri 2/10/15 | Fri 2/10/15 | | | | | | | | | |
| 341 | | - | Tiling Wo | 7 days | Mon 5/10/15 | Tue 13/10/15 | • | | | | | | | | |
| 342 | | -5 | Internal Cei | 7 days | Thu 15/10/15 | Fri 23/10/15 | | | | | | | | | |
| 343 | | - | External Fir | 28 days | Mon 28/9/15 | Thu 5/11/15 | | | | | | | | | |
| 344 | | - | Plasterin | 14 days | Mon 28/9/15 | Fri 16/10/15 | | | | | | | | | |
| 345 | | -5 | Tiling Wo | 7 days | Mon 19/10/15 | Tue 27/10/15 | | | | | | | | | |
| 346 | | -5 | Ceiling Fi | 7 days | Wed 28/10/15 | Thu 5/11/15 | | | | | | | | | |
| 347 | | -5 | Plumbing V | 10 days | Fri 2/10/15 | Fri 16/10/15 | | | | | | | | | |
| 348 | | -5 | Electrical Wo | • | Fri 2/10/15 | Fri 16/10/15 | | | | | | | | | |
| 349 | | -5 | Mechanical \ | | Fri 2/10/15 | Fri 16/10/15 | | | | | | | | | |
| 350 | | -5 | External Works | 162 days | Mon 8/6/15 | Mon 1/2/16 | | | | | | 0 | | | |
| 351 | | -5 | Surface Water | 147 days | Mon 8/6/15 | Mon 11/1/16 | , | | | | | ı | | 1 | |
| 352 | | -5 | Drain, Box Concrete | 70 days | Tue 29/9/15 | Mon 11/1/16 | ; | | | | | | | 1 | |
| 353 | | -5 | 900mm | 70 days | Tue 29/9/15 | Mon 11/1/16 | | | | | | | | | |
| | | | Task | | | Inactive Summary | | | Externa | ıl Tasks | | | | | |
| | | | Split | | | Manual Task | | | Externa | l Milesto | ne 💠 | | | | |
| | | CHES! | Milestone | • | > | Duration-only | | | Deadlin | ne | • | | | | |
| - | | SCHEDUL 11/4/18 | E Summary | | | Manual Summary Rollu | р | | Critical | | | | | | |
| ate. | vveu | 11/4/10 | Project Sum | mary | | Manual Summary | | | 1 Critical | | | | | | |
| | | | Inactive Task | (| | Start-only | Е | | Progres | SS | _ | | | | |
| | | | Inactive Mile | estone | | Finish-only | 3 | | _ | l Progress | - | | | | |
| | | | I | | | Page 18 | | | | | | | | | |

| D | 0 | Task Mode | Task Name | Duration | Start | Finish | | 25/5 | 11 August 24/8 | 23/11 | 21 Februa 22/2 | ary 24/5 | 1 Septer 23/8 | mber 22/11 | 11 Marcl 21/2 |
|-------|-------------|--------------------|---------------------------|----------|--------------|---------------------|----|------|-------------------|------------|-------------------|----------|---------------|---------------|------------------|
| 354 | | | 900mm | 70 days | Tue 29/9/15 | Mon 11/1/1 | 5 | | | | | | | | |
| 355 | | | Others | 90 days | Mon 8/6/15 | Fri 16/10/15 | | | | | | | _ |) | |
| 356 | | -5 | Roadworks & Pavements | 51 days | Wed 18/11/15 | Mon 1/2/16 | | | | | | | | | |
| 357 | | -5 | Interlocking | 24 days | Wed 18/11/15 | Mon 21/12/ | 15 | | | | | | , | | |
| 358 | *** | -5 | Roadworks | 33 days | Wed 18/11/15 | Wed 6/1/16 | | | | | | | , | | |
| 359 | | -5 | Road Furnit | 18 days | Thu 7/1/16 | Mon 1/2/16 | | | | | | | | | |
| 360 | | -5 | Water Reticula | 47 days | Tue 11/8/15 | Wed 21/10/ | 15 | | | | | ľ | | | |
| 361 | | - | Pipe line | 33 days | Tue 11/8/15 | Wed 30/9/1 | 5 | | | | | ì | | | |
| 362 | | - | Pipe Fittings | 33 days | Tue 11/8/15 | Wed 30/9/1 | 5 | | | | | ì | | | |
| 363 | | -5 | JBA - Meter | 14 days | Thu 1/10/15 | Wed 21/10/ | 15 | | | | | | | | |
| 364 | | -5 | Sewerage (Septic Tank) | 14 days | Thu 1/10/15 | Wed 21/10/ | 15 | | | | | | | | |
| 365 | | -5 | Fencing & Railings | 21 days | Wed 18/11/15 | Wed 16/12/ | 15 | | | | | | | | |
| 366 | | -9 | Fencing | 21 days | Wed 18/11/15 | Wed 16/12/ | 15 | | | | | | · | | |
| 367 | | -5 | Railing | 21 days | Wed 18/11/15 | Wed 16/12/ | 15 | | | | | | | | |
| 368 | | -9 | Electrical Serv | 40 days | Wed 18/11/15 | Fri 15/1/16 | | | | | | | | | |
| 369 | **** | -5 | LV Cable | 40 days | Wed 18/11/15 | Fri 15/1/16 | | | | | | | · | | |
| 370 | | | Compound | 40 days | Wed 18/11/15 | Fri 15/1/16 | | | | | | | · | | |
| 371 | | -5 | TESTING AND COMMISIONING | 20 days | Mon 18/1/16 | Tue 16/2/16 | | | | | | | | | |
| | | | Task | | | Inactive Summary | | | Extern | al Tasks | | | | | |
| | | | Split | | | Manual Task | | | Extern | al Milesto | ne 💠 | • | | | |
| | | | Milestone | | ♦ | Duration-only | | | Deadli | ine | 4 | | | | |
| - | | SCHEDUL 11/4/18 | .E Summary | | | Manual Summary Roll | ир | | Critica | I | | | | | |
| Date. | vveu | 11/4/10 | Project Sum | mary | | Manual Summary | | | T Critica | | | | | | |
| | | | Inactive Task | • | | Start-only | Е | | Progre | | _ | | | | |
| | | | Inactive Mile | | | Finish-only | 3 | | _ | al Progres | s – | | | | |
| | | | 1 | | | Page 19 | | | | | | | | | |

| | 0 | Task Mode | Task Name | Duration | Start | Finish | 25/5 | 11 Au | gust 4/8 23/11 | 21 February 22/2 | 24/5 | 1 Septem 23/8 | ber 22/11 | 11 M |
|-----|---|--------------------|--|-------------|-------------|---|------|-------|---|---------------------|------|------------------|--------------|------|
| 372 | | -5 | FINAL INSPECTION | 1 day | Wed 17/2/16 | Wed 17/2/16 | | | | | | | | |
| 373 | | - | HANDING OVER | 1 day | Thu 18/2/16 | Thu 18/2/16 | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | Task Split | | | Inactive Summary | | | External Tasks | e � | | _ | | |
| | | | Split | | | Manual Task | | | External Mileston | | _ | _ | | |
| | | SCHEDUL | Split Milestone | | | Manual Task Duration-only | | | External Mileston Deadline | ne 💠 | | _ | | |
| | | SCHEDUL 11/4/18 | Split Milestone Summary | • | | Manual Task Duration-only Manual Summary Rollup | | | External Mileston Deadline Critical | + | | _ | | |
| | | | Split Milestone Summary Project Sur | nmary | | Manual Task Duration-only Manual Summary Rollup Manual Summary | | | External Mileston Deadline Critical Critical Split | + | | | | |
| | | | Split Milestone Summary | nmary sk | | Manual Task Duration-only Manual Summary Rollup | | | External Mileston Deadline Critical | + | | | | |